

## SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FED 20% STATE ROADWAY 0005
				URBAN
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	247	247
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6557	6557
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	264	264
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	54	54
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2852	2852
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	247	247
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6557	6557
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	264	264
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	54	54
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	34	34

\* SPECIALTY ITEM

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -		869	4RS-4	FRANKLIN	11	5				
#MODELNAME#		CHECKED -	REVISED -		SCALE:      SHEET      OF      SHEETS      STA.      TO      STA.				CONTRACT NO. 78412				
		DATE -	REVISED -		(ILLINOIS) FED. AID PROJECT								