

PAVEMENT SCHEDULE

STATION TO STATION			POLY BITUMINOUS MATERIALS (PRIME COAT)	HMA SURFACE REMOVAL 2 1/4"	POLY HMA SURFACE COURSE, MIX "D", N90	POLY HMA LEVELING BINDER COURSE, N90 FG	MATERIAL TRANSFER DEVICE	TEMPORARY RAMP
			GALLON	SQ YD	TON	TON	TON	SQ YD
US 51 (WASHINGTON ST.)								
977+00.00	TO	980+00.00	140.0	1867	156.8	78.4	156.8	32.0
980+00.00	TO	983+71.00	167.0	2226	187.0	93.5	187.0	
983+71.00	TO	1006+39.00	1020.6	13608	1143.1	571.5	1143.1	
1006+39.00	TO	1006+47.00	RR OMISSION					
1006+47.00	TO	1023+00.00	986.6	13154	1105.0	552.5	1105.0	38.0
US 51 (POPLAR ST.)								
20+24.00	TO	19+02.00	36.6	488	41.0	20.5		
19+02.00	TO	16+20.00	84.6	1128	94.8	47.4		20.0
16+20.00	TO	2+15.00	OMISSION					
2+15.00	TO	1+58.00	17.1	228	19.2	9.6		20.0
1+58.00	TO	1+12.00	18.1	241	20.2	10.1		
US 51 (HICKORY ST.)								
99+15.00	TO	100+21.00	22.6	302	25.4	12.7		31.0
TOTAL			2493	33242	2792	1396	2592	141