





MODEL: Sheet-TS-6 GMR Int 1 - VMD Print
FILE NAME: C:\Users\jmaggle\OneDrive\Documents\maggle\303\04022022\087674\ts.dgn




USER NAME	= maggle,cox	DESIGNED	- JLS	REVISED	-
DRAWN	- MAC	REVIS	-	REVISED	-
PLOT SCALE	= 0.16666633''/in.	CHECKED	- BRM	REVISED	-
PLOT DATE	= 4/25/2024	DATE	- 9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CABLE DIAGRAM
GREEN MOUNT ROAD AND I-64 WESTBOUND RAMPS

SCALE: 1"=20' SHEET 16 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	402
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



MODEL: SH06LXNAMES
FILE NAME: p:\projects\illinois\valley\documents\projects\1165901 - PTB - 195-456 - 1st Widening and Reconstruction\CADD\CAD Sheets\0376K74-4b1-1S.dgn

ITEM	UNIT	TOTAL QUANTITY
SIGN PANEL - TYPE 1	SQ FT	16
SERVICE INSTALLATION, TYPE A	EACH	1
UNDERGROUND CONDUIT, GALVANIZED STEEL, 1" DIA.	FOOT	16
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	14
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	137
UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	265
UNDERGROUND CONDUIT, GALVANIZED STEEL, 5" DIA.	FOOT	60
UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	138
UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	508
UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	270
UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	120
UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	99
UNDERGROUND CONDUIT, PVC, 5" DIA.	FOOT	112
CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	374
HANDHOLE	EACH	10
DOUBLE HANDHOLE	EACH	1
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3669
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	499
ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4901
ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	43
ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO 6 1C	FOOT	903
TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	4
TRAFFIC SIGNAL POST, ALUMINUM 15 FT.	EACH	2
STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1
STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1
STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1
CONCRETE FOUNDATION, TYPE A	FOOT	18
CONCRETE FOUNDATION, TYPE D	FOOT	3
CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10
CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2
SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1
TRAFFIC SIGNAL BACKPLATE, RETROREFLECTIVE	EACH	7
INDUCTIVE LOOP DETECTOR	EACH	17
DETECTOR LOOP, TYPE I	FOOT	2264
TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4766
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4
REMOVE EXISTING HANDHOLE	EACH	8
REMOVE EXISTING CONCRETE FOUNDATION	EACH	5
GPS CLOCK SYNC UNIT	EACH	1
VIDEO VEHICLE DETECTION SYSTEM - TEMPORARY	EACH	1
REMOVE EXISTING TRAFFIC CONTROLLER AND CABINET	EACH	1
REMOVE EXISTING SIGNAL HEAD	EACH	13



USER NAME =	DESIGNED - JLS	REVISED -
	DRAWN - MAC	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED - BRM	REVISED -
PLOT DATE = 3/14/2025	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL PLANS QUANTITIES - I-64 WESTBOUND RAMPS			
SCALE: NTS	SHEET 17	OF 33 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	403
				CONTRACT NO. 76K74
		ILLINOIS	FED. AID PROJECT	


TRAFFIC SIGNAL FACES

12"
→R
→Y
FL
→Y
→G

12"
R
Y
G

LEFT TURN
YIELD
ON FLASHING
YELLOW
ARROW

Ⓐ ALL OTHERS © R10-12a
30"X36"
SIGN PANEL - TYPE 1



PHASE DESIGNATION DIAGRAM



MODEL: ST0001\JAMES
FILE NAME: p:\projects\state_valley\documents\project\169001 - PTB 195-456 - Left Widening and Reconstruction\CADD\CAD Sheets\037674-1-15-15.dgn



USER NAME =	DESIGNED - JLS	REVISED -
DRAWN - MAC	REVISED -	
PLOT SCALE = 0.16666633" / lin.	CHECKED - BRM	REVISED -
PLOT DATE = 4/25/2024	DATE - 9-10-24	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 1 - TEMPORARY TRAFFIC SIGNAL PLANS
GREEN MOUNT ROAD AND EASTBOUND I-64 RAMP

SCALE: 1"=20' SHEET 18 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	404
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL - MODEL NAMES
FILE NAME - p:\projects\stlouis_valley\documents\projects\116501 - PTB 195-456 - I-64 Widening and Reconstruction\CADD\CAD Sheets\037674-1-1-TS.dgn



USER NAME	=	DESIGNED	- JLS	REVISED	-
		DRAWN	- MAC	REVISED	-
PLOT SCALE	= 0.16666633" / ft.	CHECKED	- BRM	REVISED	-
PLOT DATE	= 4/25/2024	DATE	- 9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 1 - TEMPORARY TRAFFIC SIGNAL PLANS
GREEN MOUNT ROAD AND EASTBOUND I-64 RAMP

SCALE: 1"=20' SHEET 19 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	405
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: Sheet - TS20 GMR Int 2 - VMD St 1
FILE NAME: C:\Users\jgarcia\OneDrive\Documents\maggie\cadd\2024\20240826\20240826\TS20 GMR Int 2 - VMD St 1.dgn




USER NAME	= maggie.cox	DESIGNED	- JLS	REVISED	-
		DRAWN	- MAC	REVISED	-
PLOT SCALE	= 0.16666633''/in.	CHECKED	- BRM	REVISED	-
PLOT DATE	= 4/25/2024	DATE	- 9-10-24	REVISED	-


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 1 - CABLE DIAGRAM GREEN MOUNT ROAD AND I-64 EASTBOUND RAMP			
SCALE: 1"=20'	SHEET 20	OF 33 SHEETS	STA. TO STA.


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	406
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



TRAFFIC SIGNAL FACES



Ⓐ ALL OTHERS
Ⓢ R10-12a
30"X36"
SIGN PANEL - TYPE 1



PHASE DESIGNATION DIAGRAM



USER NAME = maggie.cox	DESIGNED - JLS	REVISED -
DRAWN - MAC	REVISED -	
PLOT SCALE = 0.16666633" / ft.	CHECKED - BRM	REVISED -
PLOT DATE = 4/25/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 2 - TEMPORARY TRAFFIC SIGNAL PLANS
GREEN MOUNT ROAD AND EASTBOUND I-64 RAMP

SCALE: 1"=20' SHEET 21 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	407
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: Sheet - TS22 GMR Int 2 - Plan 5-6 - S1.2
FILE NAME: C:\Users\jmaggle\OneDrive\Documents\76K74\76K74.dgn



USER NAME	= magglecox
PLOT SCALE	= 0.16666633''/ft.
PLOT DATE	= 4/25/2024

DESIGNED	- JLS
DRAWN	- MAC
CHECKED	- BRM
DATE	- 9-10-24



REVISED	-
REVISED	-
REVISED	-
REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 2 - TEMPORARY TRAFFIC SIGNAL PLANS
GREEN MOUNT ROAD AND I-64 EASTBOUND RAMP

SCALE: 1"=20' SHEET 22 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	408
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



MODEL: Sheet - TS23 GMR Int 2 - VMD S1 2
FILE NAME: C:\Users\jgarcia\OneDrive\Documents\maggie\cable\TS23.dgn



USER NAME	= maggie.cox	DESIGNED	- JLS	REVISED	-
		DRAWN	- MAC	REVISED	-
PLOT SCALE	= 0.166666633''/in.	CHECKED	- BRM	REVISED	-
PLOT DATE	= 4/25/2024	DATE	- 9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


STAGE 2 - CABLE DIAGRAM
GREEN MOUNT ROAD AND I-64 EASTBOUND RAMP

SCALE: 1"=20'


SHEET 23 OF 33 SHEETS

STA. TO STA.



F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	409
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				




TRAFFIC SIGNAL FACES



Ⓐ ALL OTHERS
Ⓢ R10-12a
30"X36"
SIGN PANEL - TYPE 1



PHASE DESIGNATION DIAGRAM



MODEL: Sheet-TS24 GMR Int. 2 - Plan 2 - S13
FILE NAME: C:\Users\jmaguire\OneDrive\Documents\maguire\0402024\240767474\SheetS13.dgn

MODEL: Sheet - 1 FILE NAME: c:\w... VOLKERT	USER NAME = maggiecox	DESIGNED = JLS	REVISED =	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STAGE 3 - TEMPORARY TRAFFIC SIGNAL PLANS GREEN MOUNT ROAD AND EASTBOUND I-64 RAMP		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	DRAWN = MAC	REVIS	REVISED =				64	82-7WRS-2	ST. CLAIR	691	410	
	PLOT SCALE = 0.16666633' / in.	CHECKED = BRM	REVISED =		SCALE: 1"=20'		SHEET 24 OF 33 SHEETS		STA.		TO STA.	
	PLOT DATE = 4/25/2024	DATE = 9-10-24	REVISED =								CONTRACT NO. 76K74	
								ILLINOIS	FED. AID PROJECT			

MODEL: Sheet - TS25 GMR Int 2 - Plan 5-6 - S1.3
FILE NAME: c:\w\p\p\working\maggie\304028262\087674\shp\S13.dgn



USER NAME	= maggie.cox
PLOT SCALE	= 0.16666633''/ft.
PLOT DATE	= 4/25/2024



DESIGNED	- JLS
DRAWN	- MAC
CHECKED	- BRM
DATE	- 9-10-24

REVISED	-
REVISED	-
REVISED	-
REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 3 - TEMPORARY TRAFFIC SIGNAL PLANS GREEN MOUNT ROAD AND EASTBOUND I-64 RAMP			
SCALE: 1"=20'	SHEET 25	OF 33 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	411
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



MODEL: Sheet - TS26 GMR Int 2 - VMD S1 3
FILE NAME: C:\Users\jg_mccormick\OneDrive\Documents\maggie\cable\0262622\0262622-0262622-0262622.dgn




USER NAME	= maggie.cox	DESIGNED	- JLS	REVISED	-
		DRAWN	- MAC	REVISED	-
PLOT SCALE	= 0.16666633''/in.	CHECKED	- BRM	REVISED	-
PLOT DATE	= 4/25/2024	DATE	- 9-10-24	REVISED	-


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 3 - CABLE DIAGRAM GREEN MOUNT ROAD AND I-64 EASTBOUND RAMP			
SCALE: 1"=20'	SHEET 26	OF 33 SHEETS	STA. TO STA.


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	412
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				




TRAFFIC SIGNAL FACES



Ⓐ ALL OTHERS
Ⓒ R10-12a
30"X36"
SIGN PANEL - TYPE 1



PHASE DESIGNATION DIAGRAM



MODEL: Sheet - T627 GMR Int 2 - Plan 2 - S14
FILE NAME: C:\Users\jmaggle\OneDrive\Documents\6304028262\067674\sheet14.sdp



USER NAME = magglecox	DESIGNED - JLS	REVISED -
	DRAWN - MAC	REVISED -
PLOT SCALE = 0.16666633" / lin.	CHECKED - BRM	REVISED -
PLOT DATE = 4/25/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 4 - TEMPORARY TRAFFIC SIGNAL PLANS
GREEN MOUNT ROAD AND EASTBOUND I-64 RAMP

SCALE: 1"=20' SHEET 27 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	413
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: Sheet - TS29 GMR Int 2 - Plan 5-6 - S14
FILE NAME: C:\Users\maggle\OneDrive\maggle\304023022\087674\shp\S29.dgn



USER NAME	= maggle.cox
PLOT SCALE	= 0.16666633''/in.
PLOT DATE	= 4/25/2024



DESIGNED	- JLS
DRAWN	- MAC
CHECKED	- BRM
DATE	- 9-10-24

REVISED	-
REVISED	-
REVISED	-
REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 4 - TEMPORARY TRAFFIC SIGNAL PLANS GREEN MOUNT ROAD AND EASTBOUND I-64 RAMP			
SCALE: 1"=20'	SHEET 28	OF 33 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	414
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



MODEL: Sheet - TS29 GMR Int 2 - WD S1 4
FILE NAME: C:\Users\jgarcia\OneDrive\Documents\maggle\cable\0282622\087674\ts29 S1 4.dgn




USER NAME	= maggle.cox	DESIGNED	- JLS	REVISED	-
		DRAWN	- MAC	REVISED	-
PLOT SCALE	= 0.16666633''/in.	CHECKED	- BRM	REVISED	-
PLOT DATE	= 4/25/2024	DATE	- 9-10-24	REVISED	-


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE 4 - CABLE DIAGRAM GREEN MOUNT ROAD AND I-64 EASTBOUND RAMP			
SCALE: 1"=20'	SHEET 29	OF 33 SHEETS	STA. TO STA.


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	415
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



TRAFFIC SIGNAL FACES



CONTROLLER PHASING								
PHASE	1	2	3	4	5	6	7	8
MOVEMENT	SBLT	NB		EB		SB		
CONCURRENT MOVEMENT PERMITTED	6	6	NOT USED	NONE	NOT USED	2	NOT USED	NOT USED



PHASE DESIGNATION DIAGRAM



USER NAME =	DESIGNED - JLS	REVISED -
DRAWN - MAC	REVISED -	
PLOT SCALE = 0.16666633" / in.	CHECKED - BRM	REVISED -
PLOT DATE = 5/3/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



TRAFFIC SIGNAL PLANS
GREEN MOUNT ROAD AND I-64 EASTBOUND RAMP

SCALE: 1"=20' SHEET 30 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	416
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: SHODLNAMEZ
FILE NAME: p:\projects\valley\Documents\Project\1165001 - PTB 194-456 - Left Widening and Reconstruction\CADD\CAD Sheets\0376K74-416-TS.dgn

MODEL - MODELNAME2
FILE NAME - p:\projects\valley\valley\valley\Documents\Project\16501 - PTB 195-456 - 164 Widening and Reconstruction\CADD\CAD Sheets\037674-1-1-TS.dgn



VOLKERT

USER NAME	=	DESIGNED	- JLS	REVISED	-
DRAWN	- MAC	REVISED	-		
PLOT SCALE	= 0.16666633" / in.	CHECKED	- BRM	REVISED	-
PLOT DATE	= 4/25/2024	DATE	- 9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL PLANS
GREEN MOUNT ROAD AND I-64 EASTBOUND RAMPS

SCALE: 1"=20' SHEET 31 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	417
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: Sheet_TSS2 GMR Int 2 - VMD Print
FILE NAME: C:\Users\jmaggle\OneDrive\Documents\maggle\3300402302622\08767474\hls\3300402302622.dgn





USER NAME = magglecox	DESIGNED - JLS	REVISED -
	DRAWN - MAC	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - BRM	REVISED -
PLOT DATE = 4/25/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CABLE DIAGRAM
GREEN MOUNT ROAD AND I-64 EASTBOUND RAMP

SCALE: 1"=20' SHEET 32 OF 33 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	418
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



GROUNDING SCHEMATIC
* GROUNDING SHALL INCLUDE:
CONTROLLER, 3 EACH MAST ARM POLES,
6 TRAFFIC SIGNAL POSTS, DOUBLE HANDHOLE,
AND 6 EACH HANDHOLES AT INTERSECTION.

PROPOSED CABLE DIAGRAM LEGEND

- 2/C INDICATES NUMBER OF CONDUCTORS IN CABLE
- S CABLE SPLICE
- ELECTRIC CABLE IN CONDUIT
- SERVICE INSTALLATION
- LD-IN ELECTRIC CABLE LEAD-IN, 1 PAIR
- CD CALL DELAY
- CCO CALL CARRY OVER
- TRAFFIC SIGNAL HEAD
- TRAFFIC SIGNAL HEAD WITH BACKPLATE, RETROREFLECTIVE

MODEL: SH06LX1M1E2
FILE NAME: p:\projects\illinois\valley\new\Documents\Projects\1165901 - PTB 195-456 - 464 Widening and Reconstruction\CADD\CAD Sheets\DS76K74-4b1-TS.dgn

ITEM	UNIT	TOTAL QUANTITY
SIGN PANEL - TYPE 1	SQ FT	16
SERVICE INSTALLATION, TYPE A	EACH	1
UNDERGROUND CONDUIT, GALVANIZED STEEL, 1" DIA.	FOOT	10
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	82
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	153
UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	240
UNDERGROUND CONDUIT, GALVANIZED STEEL, 5" DIA.	FOOT	83
UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	116
UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	509
UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	255
UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	57
UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	62
UNDERGROUND CONDUIT, PVC, 5" DIA.	FOOT	24
HANDHOLE	EACH	12
DOUBLE HANDHOLE	EACH	1
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2770
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	385
ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4285
ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	69
ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO 6 1C	FOOT	707
TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	4
TRAFFIC SIGNAL POST, ALUMINUM 15 FT.	EACH	2
STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1
STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1
STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1
CONCRETE FOUNDATION, TYPE A	FOOT	18
CONCRETE FOUNDATION, TYPE D	FOOT	3
CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	24
CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2
SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1
TRAFFIC SIGNAL BACKPLATE, RETROREFLECTIVE	EACH	7
INDUCTIVE LOOP DETECTOR	EACH	17
DETECTOR LOOP, TYPE I	FOOT	2167
TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5229
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4
REMOVE EXISTING HANDHOLE	EACH	10
REMOVE EXISTING CONCRETE FOUNDATION	EACH	5
GPS CLOCK SYNC UNIT	EACH	1
VIDEO VEHICLE DETECTION SYSTEM - TEMPORARY	EACH	1
REMOVE EXISTING TRAFFIC CONTROLLER AND CABINET	EACH	1
REMOVE EXISTING SIGNAL HEAD	EACH	13



USER NAME	=
PLOT SCALE	= 0.16666633 1/ in.
PLOT DATE	= 3/14/2025

DESIGNED	-	JLS
DRAWN	-	MAC
CHECKED	-	BRM
DATE	-	9-10-24

REVISED	-
REVISED	-
REVISED	-
REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL PLANS
QUANTITIES - I-64 EASTBOUND RAMPS


SCALE: NTS	SHEET 33	OF 33	SHEETS	STA.	TO STA.
------------	----------	-------	--------	------	---------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	419
		CONTRACT NO. 76K74		
		ILLINOIS	FED. AID PROJECT	

1. DESIGN OF THE NOISE ABATEMENT WALLS SHALL MEET THE REQUIREMENTS OF THE CURRENT EDITION OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION BUREAU OF BRIDGES AND STRUCTURES BRIDGE MANUAL, THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, AND SPECIAL PROVISIONS.
2. THE CONTRACTOR SHALL REVIEW THE MAINTENANCE OF TRAFFIC PLANS. THE CONSTRUCTION OF THE NOISE ABATEMENT WALLS MAY NEED TO BE SEQUENCED TO MATCH THE ROADWAY SEQUENCE OF CONSTRUCTION, AND THE CONTRACTOR MAY NOT BE ABLE TO CONSTRUCT THE NOISE ABATEMENT WALLS IN ONE CONTINUOUS OPERATION. ADDITIONAL MOBILIZATION/ DEMOBILIZATION REQUIRED WILL NOT BE MEASURED FOR PAYMENT, BUT SHALL BE INCLUDED IN THE COST OF NOISE ABATEMENT WALL, GROUND MOUNTED.
3. SEE UTILITIES AND DRAINAGE SHEETS FOR INFORMATION RELATED TO EXISTING AND PROPOSED FACILITIES ALONG THE PROPOSED NOISE ABATEMENT WALLS.
4. THE CONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UTILITIES AND STRUCTURES AND SHALL TAKE ALL NECESSARY PRECAUTIONS TO PERFORM THE WORK IN SUCH A MANNER AS TO NOT DAMAGE EXISTING UTILITIES OR STRUCTURES, LOCATED NEAR OR BENEATH THE NOISE ABATEMENT WALLS. ANY DAMAGE TO EXISTING UTILITIES OR STRUCTURES SHALL BE REPAIRED AT NO COST TO THE DEPARTMENT.
5. THE PROPOSED NOISE ABATEMENT WALL, GROUND MOUNTED FOUNDATIONS ARE TO BE DETERMINED BY THE CONTRACTOR AND SHALL BE DESIGNED TO AVOID CONFLICTS WITH THE EXISTING AND PROPOSED UTILITIES, EXISTING AND PROPOSED DRAINAGE CULVERTS, AND STRUCTURES.
6. THE CONTRACTOR SHALL VERIFY ACCESS DOOR LOCATIONS AND DIMENSIONS PRIOR TO MANUFACTURING OR INSTALLATION OF NOISE ABATEMENT WALLS.
7. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY EXISTING AND PROPOSED GROUND ELEVATIONS AT THE LOCATIONS OF THE PROPOSED GROUND MOUNTED NOISE ABATEMENT WALLS AND COMPARE TO THAT SHOWN ON THE PLANS. ADJUSTMENTS TO NOISE ABATEMENT WALL HEIGHTS AS REQUIRED TO ACCOMMODATE ACTUAL FIELD CONDITIONS SHALL BE MADE BY THE CONTRACTOR AT NO ADDITIONAL COST. COST TO COMPLY WITH THIS REQUIREMENT IS INCLUDED IN THE COST OF NOISE ABATEMENT WALL, GROUND MOUNTED.
8. THE CONTRACTOR SHALL PROVIDE 4" WEEP HOLES AT GROUND LEVEL IN THE BOTTOM OF THE WALL AT A SPACING OF 8 FEET, WHEN GROUND SURFACE SLOPES INDICATE THAT PONDING AT THE WALL FACE IS A CONCERN.

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1-3	NOISE WALL GENERAL NOTES & DETAILS
-	PLAN & ELEVATION - NOISE WALL 1 (NOT INCLUDED IN THIS PROJECT)
4-8	PLAN & ELEVATION - NOISE WALL 2
9-10	PLAN & ELEVATION - NOISE WALL 3
11	PLAN & ELEVATION - NOISE WALL 4
12-14	PLAN & ELEVATION - NOISE WALL 5
-	PLAN & ELEVATION - NOISE WALL 6 (COMBINED WITH WALL 5)
15-16	PLAN & ELEVATION - NOISE WALL 7
17	PLAN & ELEVATION - NOISE WALL 8
18-25	SOIL BORING LOGS - NOISE WALL 2
26-28	SOIL BORING LOGS - NOISE WALL 3
29-30	SOIL BORING LOGS - NOISE WALL 4
31-34	SOIL BORING LOGS - NOISE WALL 5
35-37	SOIL BORING LOGS - NOISE WALL 7
38	SOIL BORING LOGS - NOISE WALL 8

NOISE REDUCTION DATA					
NOISE WALL STRUCTURE NUMBER	FACE	FROM MAINLINE STA.	TO MAINLINE STA.	NOISE REDUCTION COEFFICIENT	COMMENTS
082-N6451 (WALL 2)	INTERSTATE FACE	14+00.00 *	816+20.00	REFLECTIVE	* WALL BEGINS WITH RAMP C STATIONING
	RESIDENTIAL FACE	14+00.00 *	816+20.00	ABSORPTIVE - 0.65	
082-N6454 (WALL 3)	INTERSTATE FACE	818+05.00	833+40.22	REFLECTIVE	ABSORPTIVE - 0.65
	HOSPITAL FACE	818+05.00	833+40.22	ABSORPTIVE - 0.65	
082-N6455 (WALL 4)	INTERSTATE FACE	832+70.00	841+05.00	REFLECTIVE	ABSORPTIVE - 0.65
	HOSPITAL FACE	832+70.00	841+05.00	ABSORPTIVE - 0.65	
082-N6456 (WALL 5)	INTERSTATE FACE	842+00.00	865+40.00	REFLECTIVE	ABSORPTIVE - 0.65
	RESIDENTIAL FACE	842+00.00	865+40.00	ABSORPTIVE - 0.65	
082-N6458 (WALL 7)	INTERSTATE FACE	865+15.00	879+80.00	REFLECTIVE	ABSORPTIVE - 0.65
	RESIDENTIAL FACE	865+15.00	879+80.00	ABSORPTIVE - 0.65	
082-N6459 (WALL 8)	INTERSTATE FACE	879+00.00	883+60.00	REFLECTIVE	ABSORPTIVE - 0.65
	RESIDENTIAL FACE	879+00.00	883+60.00	ABSORPTIVE - 0.65	



LOCATION OF NAME PLATE

ITEM	UNIT	WALL NO. 2	WALL NO. 3	WALL NO. 4	WALL NO. 5	WALL NO. 7	WALL NO. 8	TOTAL
NOISE ABATEMENT WALL, GROUND MOUNTED	SQ FT	81,604	31,441	17,440	40,298	25,416	5,756	201,955
NAME PLATES	EACH	1	1	1	1	1	1	6

DESIGN SPECIFICATIONS

AASHTO LRFD BRIDGE DESIGN
SPECIFICATIONS, 2020 EDITION

DESIGN STRESSES

FIELD UNITS

$f_c = 4,000 \text{ PSI}$
 $f_y = 60,000 \text{ PSI (REINFORCEMENT)}$
 $f_y = 50,000 \text{ PSI (STRUCT. STEEL, M270 GRADE 50, POSTS)}$
 $f_y = 36,000 \text{ PSI (STRUCT. STEEL, M270 GRADE 36, ALL OTHER STRUCTURAL STEEL)}$





PRECAST UNITS

$f_c = 4,500$ PSI
 $f_y = 60,000$ PSI (REINFORCEMENT)
 $f_y = 65,000$ PSI (WELDED WIRE REINFORCEMENT)


DESIGN STRESSES

STRENGTH III OR V WIND: 35 PSF
SERVICE I WIND: 15 PSF


	USER NAME =	DESIGNED - SJN	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	NOISE WALL GENERAL NOTES & DETAILS I-64 WIDENING AND RECONSTRUCTION				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 0.16666633' / in.	DRAWN - MAM	REVISED -						64	82-7HB-1	ST. CLAIR	691	420
	PLOT DATE = 5/2/2024	CHECKED - JLS	REVISED -		CONTRACT NO. 76K74								
		DATE - 9-10-24	REVISED -		SCALE: N/A	SHEET 1 OF 38 SHEETS	STA. N/A TO STA. N/A	ILLINOIS FED. AID PROJECT					



MODEL: \\MODEL\\NAMES
FILE NAME: \\proj\\states\\valley\\com\\valley\\cuse\\w\\Documents\\Projects\\I16601 - PTB 196-196 - Let Widening and Reconstruction\\CAD\\CAD Sheets\\D87674-St-Noise Walls-Details.dgn



SECTION F: NOISE WALL 4 (I-64)
N.T.S.
WALL 4 STA. 832+70.00 TO STA. 841+05.00



SECTION G: NOISE WALL 3 (I-64)
N.T.S.
WALL 4 STA. 818+05.00 TO STA. 833+40.22



USER NAME	=	DESIGNED	-	SJN	REVISED	-
		DRAWN	-	MAM	REVISED	-
PLOT SCALE	= 0.16666633''/in.	CHECKED	-	JLS	REVISED	-
PLOT DATE	= 5/2/2024	DATE	-	9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


NOISE WALL GENERAL NOTES & DETAILS
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 3 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	422
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				


TABLE OF POINT LOCATIONS

POINT	RAMP C/I-64 STA.	RAMP C/I-64 OFF.	NORTHING	EASTING
BEGIN	14+00.00	39.0' RT	137020.79	102427.03
KINK PT. 1	13+40.00	39.0' RT	136972.61	102462.80
KINK PT. 2	12+50.00	39.0' RT	136907.26	102517.63
KINK PT. 3	10+45.00	57.5' RT	136801.69	102678.21
KINK PT. 4	10+45.00	27.0' RT	136775.52	102662.47
KINK PT. 5	772+42.19	126.8' LT	136690.71	102871.13
KINK PT. 6	773+21.44	123.3' LT	136673.07	102946.25
KINK PT. 7	774+94.33	114.2' LT	136637.61	103111.13
KINK PT. 8	783+11.63	91.0' LT	136574.82	103907.28
END	816+20.00	91.0' LT	136692.66	107213.55



LEGEND

NOISE WALL SOIL BORINGS



NOISE ABATEMENT WALL
BUILT (YEAR) BY
STATE OF ILLINOIS
FAI 64
SECTION 82-7WRS-2
FROM STA. (14+00) TO STA. (816+20)
STRUCTURE NO. 082-N6451

NAME PLATE
SEE STD. 515001
GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-7WRS-2
ST. CLAIR COUNTY
STA. 14+00.00
TO STA 816+20.00

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 2
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 4 OF 38 SHEETS STA. 1099+00 TO STA. 1110+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	423
CONTRACT NO. 76K74				


ILLINOIS FED. AID PROJECT

MODEL: \\MODEL\NAMES
FILE NAME: \\projects\82-7wrs-2\Documents\Project\1099-1-PTB-19-406-1-64 Widening and Reconstruction\CADD\CAD Sheets\082-7WRS-2-1-64 Noise Wall 2.dgn

Volkert


USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

TABLE OF POINT LOCATIONS				
POINT	RAMP C/I-64 STA.	RAMP C/I-64 OFF.	NORTHING	EASTING
BEGIN	14+00.00	39.0' RT	137020.79	102427.03
KINK PT. 1	13+40.00	39.0' RT	136972.61	102462.80
KINK PT. 2	12+50.00	39.0' RT	136907.26	102517.63
KINK PT. 3	10+45.00	57.5' RT	136801.69	102678.21
KINK PT. 4	10+45.00	27.0' RT	136775.52	102662.47
KINK PT. 5	772+42.19	126.8' LT	136690.71	102871.13
KINK PT. 6	773+21.44	123.3' LT	136673.07	102946.25
KINK PT. 7	774+94.33	114.2' LT	136637.61	103111.13
KINK PT. 8	783+11.63	91.0' LT	136574.82	103907.28
END	816+20.00	91.0' LT	136692.66	107213.55



LEGEND

NOISE WALL SOIL BORINGS



GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-7WRS-2
ST. CLAIR COUNTY
STA. 14+00.00
TO STA 816+20.00



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


PLAN & ELEVATION - NOISE WALL 2
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 6 OF 38 SHEETS STA. 1121+00 TO STA. 1132+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	425
CONTRACT NO. 76K74				


ILLINOIS FED. AID PROJECT

TABLE OF POINT LOCATIONS				
POINT	RAMP C/I-64 STA.	RAMP C/I-64 OFF.	NORTHING	EASTING
BEGIN	14+00.00	39.0' RT	137020.79	102427.03
KINK PT. 1	13+40.00	39.0' RT	136972.61	102462.80
KINK PT. 2	12+50.00	39.0' RT	136907.26	102517.63
KINK PT. 3	10+45.00	57.5' RT	136801.69	102678.21
KINK PT. 4	10+45.00	27.0' RT	136775.52	102662.47
KINK PT. 5	772+42.19	126.8' LT	136690.71	102871.13
KINK PT. 6	773+21.44	123.3' LT	136673.07	102946.25
KINK PT. 7	774+94.33	114.2' LT	136637.61	103111.13
KINK PT. 8	783+11.63	91.0' LT	136574.82	103907.28
END	816+20.00	91.0' LT	136692.66	107213.55



LEGEND

NOISE WALL SOIL BORINGS



GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-TWRS-2
ST. CLAIR COUNTY
STA. 14+00.00
TO STA 816+20.00

MODEL: SHOTGUN
FILE NAME: D:\Projects\I-64 Widening and Reconstruction\CADD\CAD Sheets\82-TWRS-2\82-TWRS-2-New.dgn



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 2
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 7 OF 38 SHEETS STA. 1132+00 TO STA. 1143+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-TWB-1	ST. CLAIR	691	426
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

TABLE OF POINT LOCATIONS				
POINT	I-64 STA.	I-64 OFF.	NORTHING	EASTING
BEGIN	818+05.00	94.5' RT	136513.87	107405.54
KINK PT. 1	819+50.00	101.9' RT	136511.70	107550.71
KINK PT. 2	821+50.00	102.2' RT	136518.44	107750.60
KINK PT. 3	824+50.00	117.7' RT	136513.71	108050.95
KINK PT. 4	827+50.00	133.1' RT	136508.98	108351.31
END	833+40.22	181.9' RT	136481.26	108942.89



NOISE ABATEMENT WALL
BUILT (YEAR) BY
STATE OF ILLINOIS
FAI 64
SECTION 82-7WRS-2
FROM STA. (818+05) TO STA. (833+40.22)
STRUCTURE NO. 082-N6454

NAME PLATE
SEE STD. 515001
GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-7WRS-2
ST. CLAIR COUNTY
STA. 818+05.00
TO STA 833+40.22

MODEL: SHODENAMES
FILE NAME: \\proposals.vallier.com\volker-usa\sw\Documents\Project\116901 - PTB - 194-456 - Le4 Widening and Reconstruction\CADD\CAD Sheets\037627-ASH-DRP-AW3-New.dgn

VOLKERT

USER NAME =	DESIGNED - SJN	REVISED -
PLOT SCALE = 0.16666633" / in.	DRAWN - MAM	REVISED -
PLOT DATE = 5/2/2024	CHECKED - JLS	REVISED -
	DATE - 9-10-24	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 3
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 9 OF 38 SHEETS STA. 1199+00 TO STA. 1208+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	428
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

TABLE OF POINT LOCATIONS				
POINT	I-64 STA.	I-64 OFF.	NORTHING	EASTING
BEGIN	818+05.00	94.5' RT	136513.87	107405.54
KINK PT. 1	819+50.00	101.9' RT	136511.70	107550.71
KINK PT. 2	821+50.00	102.2' RT	136518.44	107750.60
KINK PT. 3	824+50.00	117.7' RT	136513.71	108050.95
KINK PT. 4	827+50.00	133.1' RT	136508.98	108351.31
END	833+40.22	181.9' RT	136481.26	108942.89



GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-7WRS-2
ST. CLAIR COUNTY
STA. 818+05.00
TO STA 833+40.22

MODEL: \\MODEL\\NAMES
FILE NAME: \\projects\\st.clair\\documents\\projects\\1169001 - PTB - 184-456 - 164 Widening and Reconstruction\\CAD\\CAD Sheets\\D376747-ASH-DRP-A\\W3-New.dgn



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 3
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 10 OF 38 SHEETS STA. 1208+00 TO STA. 1215+38.21


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7, 1B-1	ST. CLAIR	691	429
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

TABLE OF POINT LOCATIONS				
POINT	I-64 STA.	I-64 OFF.	NORTHING	EASTING
BEGIN	842+00.00	91.0' LT	136784.58	109792.41
KINK PT. 1	846+00.00	91.0' LT	136798.83	110192.16
KINK PT. 2	847+00.00	115.0' LT	136826.37	110291.24
KINK PT. 3	851+00.00	115.0' LT	136840.62	110690.99
KINK PT. 4	858+10.00	115.0' LT	136865.91	111400.53
KINK PT. 5	858+10.00	91.0' LT	136841.93	111401.39
KINK PT. 6	860+00.00	91.0' LT	136848.65	111591.55
KINK PT. 7	861+00.00	101.0' LT	136861.51	111692.00
KINK PT. 8	865+00.00	101.0' LT	136864.79	112095.26
END	865+40.00	111.0' LT	136874.40	112135.71



LEGEND

NOISE WALL SOIL BORINGS



NOISE ABATEMENT WALL
BUILT (YEAR) BY
STATE OF ILLINOIS
FAI 64
SECTION 82-7WRS-2
FROM STA. (842+00) TO STA. (866+54.23)
STRUCTURE NO. 082-N6456

NAME PLATE
SEE STD. 515001
GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-7WRS-2
ST. CLAIR COUNTY
STA. 842+00.00
TO STA 866+54.23

MODEL: SHORLNAME2
FILE NAME: \\proposals.volkert.com\volker-usa\sw\Documents\Project\1169301 - PTB - 184-186 - 164 Widening and Reconstruction\CADD\CAD Sheets\0378787-ASH-PTB-184-186-New.dgn

VOLKERT

USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 5
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 12 OF 38 SHEETS STA. 1399+00 TO STA. 1409+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	431
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

TABLE OF POINT LOCATIONS				
POINT	I-64 STA.	I-64 OFF.	NORTHING	EASTING
BEGIN	842+00.00	91.0' LT	136784.58	109792.41
KINK PT. 1	846+00.00	91.0' LT	136798.83	110192.16
KINK PT. 2	847+00.00	115.0' LT	136826.37	110291.24
KINK PT. 3	851+00.00	115.0' LT	136840.62	110690.99
KINK PT. 4	858+10.00	115.0' LT	136865.91	111400.53
KINK PT. 5	858+10.00	91.0' LT	136841.93	111401.39
KINK PT. 6	860+00.00	91.0' LT	136848.65	111591.55
KINK PT. 7	861+00.00	101.0' LT	136861.51	111692.00
KINK PT. 8	865+00.00	101.0' LT	136864.79	112095.26
END	865+40.00	111.0' LT	136874.40	112135.71



GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-TWRS-2
ST. CLAIR COUNTY
STA. 842+00.00
TO STA 866+54.23

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 5
I-64 WIDENING AND RECONSTRUCTION


SCALE: 1"=50' SHEET 13 OF 38 SHEETS STA. 1409+00 TO STA. 1419+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	432
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

VOLKERT


USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

TABLE OF POINT LOCATIONS				
POINT	I-64 STA.	I-64 OFF.	NORTHING	EASTING
BEGIN	842+00.00	91.0' LT	136784.58	109792.41
KINK PT. 1	846+00.00	91.0' LT	136798.83	110192.16
KINK PT. 2	847+00.00	115.0' LT	136826.37	110291.24
KINK PT. 3	851+00.00	115.0' LT	136840.62	110690.99
KINK PT. 4	858+10.00	115.0' LT	136865.91	111400.53
KINK PT. 5	858+10.00	91.0' LT	136841.93	111401.39
KINK PT. 6	860+00.00	91.0' LT	136848.65	111591.55
KINK PT. 7	861+00.00	101.0' LT	136861.51	111692.00
KINK PT. 8	865+00.00	101.0' LT	136864.79	112095.26
END	865+40.00	111.0' LT	136874.40	112135.71



LEGEND

NOISE WALL SOIL BORINGS



GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-TWRS-2
ST. CLAIR COUNTY
STA. 842+00.00
TO STA 866+54.23

Volkert

USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 5
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 14 OF 38 SHEETS STA. 1419+00 TO STA. 1423+73.25

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-TWB-1	ST. CLAIR	691	433
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

TABLE OF POINT LOCATIONS				
POINT	I-64 STA.	I-64 OFF.	NORTHING	EASTING
BEGIN	865+15.00	91.0' LT	136854.66	112110.29
KINK PT. 1	870+01.45	91.0' LT	136840.36	112600.10
END	879+80.00	91.0' LT	136754.77	113567.57



NOISE ABATEMENT WALL
BUILT (YEAR) BY
STATE OF ILLINOIS
FAI 64
SECTION 82-7WRS-2
FROM STA. (865+15) TO STA. (879+80)
STRUCTURE NO. 082-N6458

NAME PLATE
SEE STD. 515001
GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-7WRS-2
ST. CLAIR COUNTY
STA. 865+15.00
TO STA 879+80.00

VOLKERT

USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 7
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 15 OF 38 SHEETS STA. 1599+00 TO STA. 1609+00


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	434
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

TABLE OF POINT LOCATIONS				
POINT	I-64 STA.	I-64 OFF.	NORTHING	EASTING
BEGIN	879+00.00	111.0' LT	136784.61	113490.01
END	883+60.00	111.0' LT	136719.98	113949.62



LEGEND

NOISE WALL SOIL BORINGS



NOISE ABATEMENT WALL
BUILT (YEAR) BY
STATE OF ILLINOIS
FAI 64
SECTION 82-7WRS-2
FROM STA. (879+00) TO STA. (883+60)
STRUCTURE NO. 082-N6459

NAME PLATE
SEE STD. 515001
GENERAL PLAN & ELEVATION
NOISE ABATEMENT WALL
F.A.I. RTE. 64
SECTION 82-7WRS-2
ST. CLAIR COUNTY
STA. 879+00.00
TO STA 883+60.00



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN & ELEVATION - NOISE WALL 8
I-64 WIDENING AND RECONSTRUCTION

SCALE: 1"=50' SHEET 17 OF 38 SHEETS STA. 1699+00 TO STA. 1704+64.16

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	436
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



Page 1 of 1

Date 12/20/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1

Date 12/6/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)



Page 1 of 1

Date 12/6/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

MODEL: SHOTBLAMES
FILE NAME: g:\projects\valley\valley\new\Documents\Projects\116901 - PTB - 194-456 - Lea Widening and Reconstruction\CADD\CAD Sheets\B376K74-Sh-Noise Wall-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/5/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT H	BLOW S	UCS Qu	MOIST T	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-09					Groundwater Elev.:	
Station	6+00.00					First Encounter	
Offset	27.0 ft RT					Upon Completion	
Ground Surface Elev.	542.90	ft	(ft)	(/6")	(tsf)	(%)	After Hrs.
TOPSOIL - 2" 542.7							
CLAYEY SILT - Brown, med-stiff							
			WH				
		1	0.6	22			
		4	B				
becomes gray		1					
		3	1.7	25			
		5	B				
w/ some organics		1					
		2	1.8	21			
		5	B				
CLAY - Dark gray, med-stiff 535.4							
		2					
		2	1.2	28			
		3	B				
become moist		WH					
		WH	0.7	30			
		2	B				
SILTY CLAY - Gray and brown, med-stiff, wet 530.4							
		WH					
		1	0.7	27			
		2	B				
becomes soft		WH					
		WH	0.2	24			
		2	B				
becomes stiff		1					
		2	1.6	25			
		3	B				
End of Boring 522.9							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/5/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT H	BLOW S	UCS Qu	MOIST T	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-10					Groundwater Elev.:	
Station	4+00.00					First Encounter	
Offset	27.8 ft RT					Upon Completion	
Ground Surface Elev.	544.09	ft	(ft)	(/6")	(tsf)	(%)	After Hrs.
TOPSOIL - 2" 543.9							
CLAYEY SILT - Brown, med-stiff, w/ some organics							
		1					
		1	1.8	20			
		6	B				
becomes brown and gray		1					
		2	1.3	28			
		3	B				
becomes gray and brown, soft and moist		WH					
		1	0.4	26			
		2	B				
becomes med-stiff		1					
		1	1.0	33			
		2	B				
		1					
		1	0.7	27			
		2	B				
SILTY CLAY - Gray and brown, soft, wet 531.6							
		1					
		1	0.5	27			
		2	B				
		1					
		1	0.5	21			
		2	B				
CLAY - Gray, soft 526.6							
		WH					
		WH	0.6	31			
		1	B				
End of Boring 521.6							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/5/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT H	BLOW S	UCS Qu	MOIST T	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-11					Groundwater Elev.:	
Station	2+00.00					First Encounter	
Offset	31.1 ft RT					Upon Completion	
Ground Surface Elev.	546.55	ft	(ft)	(/6")	(tsf)	(%)	After Hrs.
TOPSOIL - 3" 546.3							
SILTY CLAY - Brown, med-stiff, w/ some organics							
			3				
		5	3.5	19			
		6	P				
becomes gray and brown, w/ some organics		1					
		2	1.4	18			
		3	B				
no more organics		1					
		1	0.7	31			
		1	B				
becomes soft		1					
		1	0.3	27			
		2	B				
becomes brown and gray, med-stiff		1					
		1	0.6	27			
		2	B				
becomes wet		WH					
		1	0.4	28			
		1	B				
		1					
		1	1.0	24			
		4	B				
SILTY CLAY - Gray, med-stiff, moist, w/ some sand 529.0							
		WH					
		1	0.9	27			
		2	B				
End of Boring 526.5							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 2
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 19 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	438
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

Page 1 of 1

Date 12/5/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____	D	B	U	M	Surface Water Elev. _____ ft
Station _____	E	L	C	O	Stream Bed Elev. _____ ft
	P	O	S	I	
BORING NO. _____	T	W		T	Groundwater Elev.: _____
Station _____	H	S	Qu		First Encounter _____ ft
Offset _____					Upon Completion _____ ft
					After _____ Hrs. _____ ft
Ground Surface Elev. 551.89 ft	(ft)	(6")	(tsf)	(%)	

Soil Description	Moisture Content (%)	Shrinkage (%)	Swelling (%)
TOPSOIL - 2.5"	551.7		
CLAYEY SILT - Brown, stiff, w/ some organics	3		
	4	20	22
	4	S	
becomes dark brown	2		
LL = 54, PL = 25, PI = 29	3	1.4	27
	3	B	
	5		
545.4	1		
SILTY CLAY - Brown and gray, med-stiff, w/ lignite stains	2	0.5	30
	2	B	
543.4	1		
CLAYEY SILT - Gray and brown, med-stiff	1	0.3	27
	1	B	
	10		
	2		
	3	1.2	25
	3	B	
becomes moist	2		
	1	0.6	26
	3	B	
	15		
becomes soft	WH		
	WH	0.4	28
	1	B	
becomes wet	1		
	2	0.5	30
	3	B	
531.9	20		

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1

Date 12/5/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____ Station _____	D E P T H	B L O W S	U C S	M O I S T	Surface Water Elev. _____ ft Stream Bed Elev. _____ ft	D E P T H	B L O W S	U C S	M O I S T
BORING NO. _____ Station _____ Offset _____	H	W	Qu	T	Groundwater Elev.: First Encounter _____ ft Upon Completion _____ ft After Hrs. _____ ft	H	W	Qu	T
Ground Surface Elev. 553.70 ft (ft) (/6") (tsf) (%)						(ft) (/6") (tsf) (%)			

	DEPTH	DESCRIPTION	MOISTURE (%)	WATER CONTENT (%)	LIQUID LIMIT (%)	PLASTICITY INDEX
TOPSOIL - 2.5"	-653.5					
CLAYEY SILT - Brown, med-stiff, w/ some organics	4 6 7		3.0 P	18		
	551.2					
SILT CLAY - Dark brown, med-stiff	2 2 2		0.5 B	27		
	-5					
becomes gray and brown, w/ lignite stains	2 2 4		1.0 B	29		
	546.2					
CLAYEY SILT - Gray and brown, soft to med-stiff	0 1 2		0.3 B	26		
	-10					
	1 2 4		0.9 B	26		
	1 1 2		0.5 B	26		
	-15					
becomes brown	1 2 1		0.4 B	26		
becomes gray and brown, moist, w/ some gravel	1 1 1		0.5 B	25		
	533.7					

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1

Date 12/2/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____	D E P T H	B L O W S	U C S	M O I S T	Surface Water Elev. _____	ft
Station _____					Stream Bed Elev. _____	ft
BORING NO. _____					Groundwater Elev.: _____	ft
Station _____					First Encounter _____	ft
Offset _____			Qu		Upon Completion _____	ft
Ground Surface Elev. _____	(ft)	(in)	(tsf)	(%)	After _____	ft
556.16					Hrs.	ft

Soil Description	Depth (ft)	Soil Type	Moisture (%)	Plasticity Index (PI)	Notes
TOPSOIL - 4"	555.8				
CLAYEY SILT - Drown, med-stiff	3				
	4	1.1	21		
	3	B			
	2				
	1	1.0	26		
	2	B			
	5				
becomes gray and brown	1				
	1	0.7	28		
	2	B			
	547.7				
SILTY CLAY - Gray and brown, med-stiff	1				
LL = 38, PL = 26, PI = 12	1	0.4	29		
	2	B			
	40				
	545.2				
CLAYEY SILT - Gray and brown, med-stiff	1				
	3	1.4	8		
	3	B			
	1				
	1	1.0	26		
	2	B			
	15				
becomes soft to med-stiff	1				
	1	0.8	27		
	2	B			
	1				
becomes brown and moist	2	0.8	27		
	2	B			
	536.2				

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

MODEL: SHOEI\JAMES
FILE NAME: g:\projects\state_valley\docs\valley\new\Documents\Project\116501 - PTB - 135-456 - Lea Widening and Reconstruction\CADD\CAD Sheets\B376K74-ASH-Noise Wall-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/1/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station		DEPTH	BLOWS	Qu	UCS	MOIST	Surface Water Elev.	Stream Bed Elev.		DEPTH	BLOWS	Qu	UCS	MOIST			
										ft								
BORING NO.	NWB-18							Groundwater Elev.:										
Station	794+00.00							First Encounter	541.8	ft								
Offset	91.0 ft LT							Upon Completion		ft								
Ground Surface Elev.	565.28	ft	(ft)	(/6")	(tsf)	(%)		After		Hrs.	(ft)	(/6")	(tsf)	(%)				
TOPSOIL - 3"																		
CLAYEY SILT - Brown, soft																		
				3								1						
				4	0.1	23			543.3			1	-	29				
				2	B			CLAYEY SILT - Brown, soft, moist										
									541.8									
Poor Recovery			WH					SAND - Brown, med-coarse, med-dense, wet										
			0	-	24			Gravel - 5.6%, Sand - 76.9%, Fines - 17.3%								2	-	24
			1					540.3			25							
			5					End of Boring										
			WH															
			1															
			2	0.3	25													
				B														
becomes med-stiff			1															
			1															
			2	0.4	26													
				B														
			1															
			1															
			2	0.7	25													
				B														
551.8																		
SILTY CLAY - Brown, med-stiff																		
			WH															
			1															
			2	0.5	19													
				B														
			1															
			1															
			2	0.8	26													
				B														
becomes moist			WH															
			1															
			2	0.8	26													
				B														
SANDY CLAY - Brown, moist, med-stiff			1															
			1															
			2	0.8	26													
				B														
548.8																		
CLAYEY SAND - Brown, med-coarse, med-dense, moist																		
			WH															
			1	-	20													
			1															

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/1/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.			D	B	U	M	Surface Water Elev.		ft
Station			E	L	C	O	Stream Bed Elev.		ft
			P	O	S	I			
			T	W		S			
			H	S	Qu	T			
BORING NO.	NWB-19						Groundwater Elev.:		
Station	796+00.00						First Encounter		ft
Offset	91.0 ft LT						Upon Completion		ft
Ground Surface Elev.	565.20	ft	(ft)	(/6")	(tsf)	(%)	After	Hrs.	ft
TOPSOIL - 3"									
CLAYEY SILT - Brown, med-stiff, w/ some organics									
				1					
				1	0.4	20			
				5	B				
				3					
becomes brown and gray				5	2.5	19			
				8	P				
				3					
becomes gray				4	1.2	19			
				6	B				
				2					
becomes dark gray				2	1.4	26			
				6	B				
				2					
				2	1.3	25			
				3	B				
				1					
				1	0.4	27			
				2	B				

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/1/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.			D	B	U	M	Surface Water Elev.		ft
Station			E	L	C	O	Stream Bed Elev.		ft
			P	L		I			
			T	O	Q	S			
BORING NO.	NWB-20		H	W	S	T	Groundwater Elev.:		
Station	798+00.00				Qu		First Encounter		ft
Offset	91.0 ft LT				(tsf)	(%)	Upon Completion		ft
Ground Surface Elev.	567.68	ft	(ft)	(/6")			After	Hrs.	ft
TOPSOIL - 3"		567.4							
CLAYEY SILT - Brown, med-stiff, w/ some organics			1						
			2	0.7	24				
			4	B					
		564.2							
SILTY CLAY - Brown and gray, stiff			3						
			7	3.3	24				
			8	S					
LL = 43, PL = 23, PI = 20			3						
			4	1.7	22				
			7	B					
		559.2							
CLAYEY SILT - Dark gray, med-stiff, w/ some organics			3						
			6	1.5	24				
			4	B					
CLAY - Gray, med-stiff		556.7							
			1						
			2	1.5	30				
			4	B					
becomes soft			1						
			1	0.3	27				
			2	B					
		551.7							
CLAYEY SILT - Gray and brown, soft, w/ lignitic stains, moist			1						
			2	0.3	29				
			3	B					
			2						
			1	0.1	27				
			3	B					
		547.7							

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 2
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 22 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	441
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



Page 1 of 1

Date 11/30/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1

Date 11/30/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The GPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)



Page 1 of 1

Date 11/30/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrator)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

MODEL: SH0601\AMES
FILE NAME: g:\projects\ames\volkert.com\volkert-usaw\Documents\Projects\116901 - PTB - 135-456 - Lea Widening and Reconstruction\CADD\CAD Sheets\B376K74-SH-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 11/30/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT H	BL O W S	UC S	MO I S T	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-24					Groundwater Elev.:	
Station	806+00.00					First Encounter	558.3 ft
Offset	91.0 ft LT					Upon Completion	ft
Ground Surface Elev.	574.32	ft	(ft)	(/6")	(tsf)	(%)	After Hrs.
TOPSOIL - 3"							
SILTY CLAY - Brown, med-stiff, w/ some organics							
			1				
			2	1.6	27		
			4	B			
becomes soft, brown and gray, w/ lignite stains							
			1				
			2	0.7	27		
			2	B			
CLAYEY SILT - Gray, med-stiff							
			2				
			2	0.6	27		
			2	B			
becomes gray and brown							
			1				
			2	0.7	25		
			2	B			
becomes moist							
			1				
			1	0.6	28		
			1	B			
becomes brown, soft and wet							
			WH				
			WH	0.4	25		
			1	B			
w/ some sand							
			WH				
			1	0.3	25		
			2	B			

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 11/30/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT H	BL O W S	UC S	MO I S T	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-25					Groundwater Elev.:	
Station	808+00.00					First Encounter	561.9 ft
Offset	91.0 ft LT					Upon Completion	ft
Ground Surface Elev.	575.42	ft	(ft)	(/6")	(tsf)	(%)	After Hrs.
TOPSOIL - 3"							
CLAYEY SILT - Brown, very soft, w/ some organics							
			1				
			1	0.1	25		
			1	B			
becomes soft							
			WH				
			1	0.2	27		
			1	B			
becomes soft, w/ some sand							
			WH				
			1	0.4	25		
			2	B			
SILTY CLAY - Brown, soft, moist							
			WH				
			1	0.3	22		
			1	B			
SANDY CLAY, Brown, soft, w/ some gravel							
			WH				
			1	0.2	21		
			1	B			
Poor Recovery becomes wet							
			WH				
			WH	-	21		
			WH				
SAND - Brown, med-coarse, loose, wet, poorly graded							
			3				
			5	-	16		
			9				
Gravel - 0.2%, Sand - 76.1%, Fines - 23.7%							
SILTY SAND - Gray, med-dense, fine grained, moist							
			4				
			8	-	14		
			7				

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 11/29/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT H	BL O W S	UC S	MO I S T	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-26					Groundwater Elev.:	
Station	810+00					First Encounter	ft
Offset	91.0 ft LT					Upon Completion	ft
Ground Surface Elev.	577.47	ft	(ft)	(/6")	(tsf)	(%)	After Hrs.
TOPSOIL - 3"							
CLAYEY SILT - Brown, very soft, w/ some organics							
			0				
			1	0.2	27		
			1	B			
becomes soft, w/ some sand							
			WH				
			1	0.3	26		
			2	B			
SILTY CLAY - Brown, soft, w/ some sand							
			WH				
			1	0.4	19		
			1	B			
SANDY CLAY - Brown, soft, moist, w/ sand and gravel							
			WH				
			WH	0.3	20		
			2	B			
CLAYEY SAND - Brown, med-dense, well graded, w/ some gravel, moist							
			1				
			2	-	20		
			2				
SAND - Brown, med-dense, poorly graded							
			1				
			2	-	18		
			4				
w/ some gravel							
			WH				
			3	-	14		
			7				

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



USER NAME	=	DESIGNED	-	SJN	REVISED	-
PLOT SCALE	=	DRAWN	-	MAM	REVISED	-
PLOT DATE	=	CHECKED	-	JLS	REVISED	-
		DATE	-	9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 2
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 24 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	443
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: SH06LX.MXES
FILE NAME: \\proj\scans\volkert.com\volkert-usaw\Documents\Projects\116901 - PTB - 135-456 - Lea Widening and Reconstruction\CADD\CAD Sheets\B376K74-ASH-Noise Wall-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 11/29/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTH	BL	UCS	MOIST	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-27						
Station	812+00.00						
Offset	91.0 ft LT						
Ground Surface Elev.	578.18	ft	(ft)	(/6")	(tsf)	(%)	
TOPSOIL - 3"							
CLAYEY SILT - Brown, very soft, w/ some organics							
			WH				
		1	1	0.1	25		
		1	1	B			
		1					
		2	1	0.3	24		
		1		B			
			WH				
		1	1	0.4	27		
		1		B			
			WH				
		1	1	0.5	24		
		1		B			
			WH				
		1	1	0.2	21		
		1		B			
			WH				
		1	1	0.5	25		
		1		B			
			WH				
		1	1	0.0	25		
		1		P			
			1				
		2		0.0	27		
		3		P			

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 11/29/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTH	BL	UCS	MOIST	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-28						
Station	814+00.00						
Offset	91.0 ft LT						
Ground Surface Elev.	579.24	ft	(ft)	(/6")	(tsf)	(%)	
TOPSOIL - 2"							
CLAYEY SILT - Brown, soft, w/ some organics							
		1					
		1		0.5	24		
		1		B			
		1					
		1		0.7	21		
		2		B			
			1				
		1		0.4	21		
		1		B			
			1				
		3		-	23		
		3					
			1				
		1		-	22		
		2					
			3				
		7		3.0	19		
		11		P			
			2				
		4		1.5	23		
		4		B			
			1				
		2		0.3	18		
		4		B			

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/20/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTH	BL	UCS	MOIST	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-29						
Station	816+00.00						
Offset	91.0 ft RT						
Ground Surface Elev.	580.88	ft	(ft)	(/6")	(tsf)	(%)	
SILTY CLAY - Brown and gray, med-stiff							
Poor Recovery							
			1				
		2		1.0	26		
		1		P			
			1				
		1		1.4	21		
		4		B			
			1				
		1		1.0	31		
		2		B			
			1				
		1		0.5	20		
		3		P			
			1				
		1		0.5	18		
		1		P			
			1				
		1		0.0	23		
		2		P			
			9				
		14		3.1	20		
		16		B			
			9				
		13		0.7	16		
		18		S			

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 2
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 25 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	444
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: SHOE\NAMEZ
FILE NAME: g:\projects\66\valley\cadd\cadd\shoe\Documents\Project\1165901 - PTB - 135-456 - Lea Widening and Reconstruction\CADD\CAD Sheets\B376K74-Shoe-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/23/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTH	BLOW	UNCONSOLIDATED	MOISTURE	Surface Water Elev.	Stream Bed Elev.	Groundwater Elev.:	First Encounter	Upon Completion	After	Hrs.
		ft	(ft)	(/6")	(tsf)	(%)						
BORING NO.	NWB-30											
Station	818+05.00											
Offset	94.5 ft RT											
Ground Surface Elev.	585.10											
SILTY CLAY - Light Brown, Soft												
		2										
		2	0.5	25								
		2	B									
becomes soft to medium stiff		WH										
		2	0.7	20								
		2	B									
		5										
579.1												
CLAY - Light Brown, Soft to Medium Stiff		1										
		2	0.8	28								
		2	B									
		5										
576.6												
SANDY LOAM - Light Brownish Red, Soft, w/ gravel pieces		WH										
		2	0.3	22								
		1	B									
		10										
574.1												
SAND - Light Brown, Loose to Medium Dense, Poorly Graded, Fine Grained w/ gravel pieces		3										
		3	0.2	19								
		4	B									
		5										
becomes wet and loose		1										
		1	-	28								
		2										
		15										
becomes very loose		1										
		WH										
		WH	-	29								
		5										
becomes coarse grained		4										
		4	-	18								
		5										
		20										
565.1												

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/24/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTH	BLOW	UNCONSOLIDATED	MOISTURE	Surface Water Elev.	Stream Bed Elev.	Groundwater Elev.:	First Encounter	Upon Completion	After	Hrs.
		ft	(ft)	(/6")	(tsf)	(%)						
BORING NO.	NWB-31											
Station	821+00.00											
Offset	102.2 ft RT											
Ground Surface Elev.	582.70											
SILTY CLAY - Brownish Gray, Medium Stiff												
		1										
		2	1.2	25								
		4	B									
		5										
		1										
		2	0.7	26								
		4	B									
		5										
		1										
		3	0.9	23								
		3	B									
		5										
becomes gray w/ orange stains and soft to medium stiff		WH										
		2	0.7	24								
		3	B									
		10										
w/ pebbles		WH										
		2	0.6	20								
		5	B									
		5										
569.2												
SAND - Dark Brown, Coarse, Medium Dense, Wet, w/ some pebbles		9										
		9	0.5	23								
		10	P									
		15										
becomes orange and fine		8										
		8	-	26								
		12										
		5										
		2										
		1	-	25								
		2										
		20										
562.7												

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/24/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTH	BLOW	UNCONSOLIDATED	MOISTURE	Surface Water Elev.	Stream Bed Elev.	Groundwater Elev.:	First Encounter	Upon Completion	After	Hrs.
		ft	(ft)	(/6")	(tsf)	(%)						
BORING NO.	NWB-32											
Station	824+00.00											
Offset	115.1 ft RT											
Ground Surface Elev.	585.60											
SILTY CLAY - Brownish Orange, Medium Stiff												
		2										
		2	1.0	22								
		2	B									
		5										
becomes soft to medium stiff		WH										
		2	0.2	20								
		2	B									
		5										
579.6												
SILT - Light Brown, Soft		4										
		5	1.8	21								
		6	B									
		5										
577.1												
SILT LOAM - Light Brown, Soft		2										
		2	>0.5	20								
		1	P									
		10										
574.6												
GLACIAL TILL - Brown + Gray, Very Stiff		2										
		6	3.7	14								
		9	B									
		5										
572.1												
CLAY TILL - Gray, Medium Stiff to Stiff		6										
		8	2.1	33								
		9	B									
		15										
		5										
		9	3.1	11								
		11	B									
		5										
567.1												
GLACIAL TILL - Gray, Medium Stiff to Stiff		6										
		11	1.4	17								
		16	B									
		20										
565.6												

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



USER NAME	=	DESIGNED	- SJN	REVISED	-
		DRAWN	- MAM	REVISED	-
PLOT SCALE	= 0.16666633' / in.	CHECKED	- JLS	REVISED	-
PLOT DATE	= 5/2/2024	DATE	- 9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 3
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 26 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	445
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: SHODENAMES
FILE NAME: \\proj\scans\valley\Documents\Projects\1165901 - PTB - 135-456 - Lea Widening and Reconstruction\CADD\CAD Sheets\B376K74-Sh-Noise Wall-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/25/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTHS	BLOW COUNTS	UNCONSOLIDATED	MOISTURE	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-33						
Station	826+00.00						
Offset	125.4 ft RT						
Ground Surface Elev.	583.70	ft	(ft)	(/6")	(tsf)	(%)	
SILTY CLAY - Brownish Orange, Medium Stiff, w/ pebbles							
		2					
		3	2	1	24		
		4		B			
w/ lignit stains							
		2					
		4		1.3	23		
		5		B			
becomes light brown and stiff							
		3					
		3		2.7	31		
		5		B			
		2					
		2		2.4	32		
		4		B			
		-10					
572.7							
SILTY CLAY LOAM - Light Brown, Soft							
		1					
		1		0.4	32		
		2		B			
		2					
		3		0.5	24		
		3		B			
		-15					
570.2							
SILT - Light Brownish Gray, Soft to Medium Stiff							
		2					
		3					
		3					
		4					
		21		2.1	22		
		20		S			
		13					
		17		2.6	17		
		22		S			
		-20					
563.7							
End of Boring							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/25/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTHS	BLOW COUNTS	UNCONSOLIDATED	MOISTURE	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-34						
Station	828+00.00						
Offset	137.2 ft RT						
Ground Surface Elev.	581.90	ft	(ft)	(/6")	(tsf)	(%)	
SILTY CLAY - Brown, Soft to Medium Stiff, w/ some small pebbles							
		2					
		2		1.2	21		
		3		B			
		1					
		2		0.6	23		
		2		B			
		-5					
575.9							
SILT - Light Brown, Soft							
		2					
		2		0.7	23		
		1		B			
		1					
		1		1.9	17		
		4		S			
		-10					
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					
		11		1.6	24		
		9		S			
		7					

MODEL: SH06ELNAME2
FILE NAME: g:\projects\valley\valley\documents\projects\116901 - PTB 195-456 - Let's Widening and Reconstruction\CADD\CAD Sheets\B376K74SH-4-Noise Walls-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/26/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTH (ft)	BLOWS (/6")	UCS Qu (tsf)	MOIST T (%)	Surface Water Elev. Stream Bed Elev.	ft ft	DEPTH (ft)	BLOWS (/6")	UCS Qu (tsf)	MOIST T (%)
BORING NO.	NWB-36					Groundwater Elev.: First Encounter Upon Completion After	566.2 ft ft				
Station	832+00.00					Hrs.					
Offset	170.3 ft RT										
Ground Surface Elev.	574.70	ft									
SILTY CLAY LOAM - Reddish Brown, Soft						End of Boring					
			2								
			2	0.5 B	26						
			3								
			2								
			2	0.3 B	25						
			4								
			1								
			2	0.7 B	26						
			3								
			1								
becomes wet			2	0.9 B	26						
			2								
			WH								
			1	0.6 B	22						
			2								
			WH								
			2	1.0 B	25						
			3								
	558.2		3								
			3	3.2 B	24						
			4								
			4								
			5	2.5 P	26						
			5								
SILTY SAND - Brown	554.7		5								

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



USER NAME	=	DESIGNED	-	SJN	REVISED	-
PLOT SCALE	=	DRAWN	-	MAM	REVISED	-
PLOT DATE	=	CHECKED	-	JLS	REVISED	-
		DATE	-	9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 3
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 28 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	447
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/26/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-TWRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____
Station _____

BORING NO. NWB-37
Station 834+00.00
Offset 166.5 ft RT
Ground Surface Elev. 570.40 ft

CLAYEY SILT - Brown

DEPTH (ft)	B L O W S (6")	U C S Q _u	M O I S T (%)
1			
2	0.2	27	
2	B		
WH			
2	0.2	28	
2	B		
1			
2	2.3	26	
2	P		
WH			
2	2.3	25	
2	P		
559.4			
1			
3	2.5	22	
3	P		
2			
3	3.8	26	
3	P		
554.4			
1			
2	-	37	
2			
553.4			
1			
5	-	26	
8			
550.4			

Surface Water Elev. _____ ft
Stream Bed Elev. _____ ft

Groundwater Elev.:
First Encounter _____ ft
Upon Completion _____ ft
After _____ Hrs. _____ ft

CLAY LOAM - Brown

SAND - Brown, Loose

SANDY CLAY TILL - Brownish
Gray

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

 Illinois Department of Transportation Division of Highways		SOIL BORING LOG		Page <u> 1 </u> of <u> 1 </u>		
ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158				Date 1/26/24		
SECTION 87-7WRS-2 LOCATION O'Fallon, IL						
COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"						
STRUCT. NO. _____ Station _____ BORING NO. NWB-38 Station 836+25.00 Offset 175.0 ft RT Ground Surface Elev. 562.90	ft	D E P T H S (ft)	B L O W S (/6")	U C S Q u (tsf)	M O I S T (%)	Surface Water Elev. _____ ft Stream Bed Elev. _____ ft Groundwater Elev.: First Encounter _____ ft Upon Completion _____ ft After _____ Hrs. _____ ft
SILTY CLAY LOAM - Gray						
		1				
		1	0.3	30		
		2	B			
		1				
		2	0.2	27		
		2	B			
		5				
becomes brown		2				
		3	0.5	28		
		2	B			
		WH				
		2	0.6	28		
		2	B			
		-10				
		WH				
		2	0.6	25		
		2	B			
		WH				
		6	1.1	21		
		2	B			
		-15				
becomes gray + brown		1				
		2	1.0	27		
		3	B			
		544.4				
SANDY CLAY TILL - Gray + Brown		2				
		3	1.3	20		
		4	B			
		542.9				
		-20				

End of Boring

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)

The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

**Illinois Department
of Transportation**
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/23/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	DEPT H	BLOW S	UCS	MOIST	Surface Water Elev.	ft
Station		OWS	Qu		Stream Bed Elev.	ft
BORING NO.					Groundwater Elev.:	
Station					First Encounter	ft
Offset					Upon Completion	ft
Ground Surface Elev.					After	Hrs.
NWB-39						
638+70.00					542.9	ft
175.0 ft RT						
556.40						
ft	(ft)	(/6")	(tsf)	(%)		
SILT - Dark Gray, Medium Stiff						
	2					
	4	2.0	20			
	8	P				
	1					
becomes light gray, soft to medium stiff, w/ organics	2	1.1	32			
	3	B				
	5					
550.4						
SILTY CLAY - Gray, Soft		WH				
	WH	0.5	27			
	1	B				
547.9						
CLAY - Light Gray + Brown, Medium Stiff						
	1					
	2	1.5	28			
	3	B				
	10					
545.4						
SILTY CLAY - Light Brown, Soft to Medium Stiff						
	1					
	2	0.8	26			
	3	B				
542.9						
SILT - Light Brown, Medium Stiff, Wet, w/ orange lignite stains						
	1					
	3	0.9	25			
	4	B				
	1					
	3	1.1	24			
	4	B				
537.9						
SILTY CLAY - Light Brown, Medium Stiff to Stiff						
	2					
	3	0.9	24			
	4	B				
536.4						
End of Boring						

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)

MODEL: SHOBELNAME
FILE NAME: \\proposals.vallet.com\vallet\user\w\Documents\Projects\116901 - PTB 195-456 - Lea Widening and Reconstruction\CADD\CAD Sheets\B376K74SH-4-Noise Walls-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 1/23/24

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION O'Fallon, IL

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. Station BORING NO. NWB-40 Station 841+05.00 Offset 340.0 ft RT Ground Surface Elev. 556.70 ft (ft) (ft) (/6") (tsf) (%) Surface Water Elev. Stream Bed Elev. Groundwater Elev.: First Encounter 545.7 ft Upon Completion After Hrs. ft

SILTY CLAY - Light Brown + Gray, Medium Stiff	2			
	1	0.7	31	
	3	B		
becomes soft	1			
	1	0.4	30	
	2	B		
	5			
550.7				
SILT - Gray, Soft to Medium Stiff, w/ brown + black stains	WH			
	2	0.4	27	
	3	B		
	2			
	1	0.3	28	
	3	B		
	10			
becomes brown, medium stiff, wet	WH			
	2	0.4	27	
	2	B		
w/ red lignite stains	1			
	2	0.8	29	
	3	B		
	15			
becomes gray, medium stiff to stiff, w/ some gravel pieces	2			
	4	1.2	25	
	4	B		
	2			
	2	1.3	23	
	4	B		
536.7	20			

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 4
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 30 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	449
				CONTRACT NO. 76K74
				ILLINOIS FED. AID PROJECT

Page 1 of 1

Date 12/14/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____ Station _____	D E P T	B L O W	U C S	M O I S T	Surface Water Elev. _____ ft Stream Bed Elev. _____ ft
BORING NO. _____ Station _____ Offset _____ Ground Surface Elev. _____	H S	W S	Qu		Groundwater Elev.: First Encounter _____ 535.3 ft Upon Completion _____ ft After _____ Hrs. _____ ft
		(ft)	(6")	(tsf)	(%)

CLAYEY SILT - Dark brown, very stiff			
	1		
	3	1.9	25
	4	B	
547.8			
SILTY CLAY - Brown and gray, med-stiff, w/ some organics	3		
	3	1.4	23
	5	B	
	2		
no more organics	3	0.9	25
	4	B	
542.8			
CLAYEY SILT - Gray, very soft LL = 40, PL = 25, PI = 15	1		
	1	0.6	28
	4	S	
	1		
	1	0.3	27
	1	S	
	WH		
	1	0.8	28
	2	B	
535.3 ▼			
SILTY CLAY - Dark gray, very stiff, wet	WH		
	2	1.2	26
	2	B	
	1		
	2	1.1	29
	2	B	
531.3			

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1

Date 12/13/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____	D	B	U	M	Surface Water Elev. _____ ft	D	B	U	M
Station _____	E	L	C	O	Stream Bed Elev. _____ ft	E	L	C	O
	P	O	S	I		P	O	S	I
BORING NO. _____	T	W	S	T	Ground Surface Elev.: _____ ft	T	W	S	T
Station _____	H	S	Qu		First Encounter _____ ft	H	S	Qu	
Offset _____					Upon Completion _____ ft				
					After _____ Hrs.				
Ground Surface Elev. 544.86 ft	(ft)	(/6")	(tsf)	(%)		(ft)	(/6")	(tsf)	(%)

TOPSOIL - 1"		SILTY CLAY - Brown and gray, med-stiff		SILTY CLAY - Brown and gray, med-stiff (continued)	
544.8	1	1.0	31		
	3	B			
	1				
	3	0.8	19		
	2	B			
-5				519.9	
	1				
	1	0.9	26		
	2	B			
	1				
	1	0.7	29		
-10	3	B			
	WH				
	1	0.8	27		
	2	B			
	WH				
	1	0.4	27		
-15	2	B			
	WH				
	2	0.0	20		
	2	B			
	WH				
	1	0.5	-		
-20	2	B			

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1Date 12/13/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____ Station _____	D E P T H	B L O W S	U C S Qu	M O I S T	Surface Water Elev. _____ ft Stream Bed Elev. _____ ft
BORING NO. _____ Station _____ Offset _____ Ground Surface Elev. _____	(ft)	(ft)	(tsf)	(%)	Groundwater Elev.: First Encounter _____ ft Upon Completion _____ ft After _____ Hrs. _____ ft
NWB-43 848+00.00 115.0 ft LT 544.20					

Soil Description	Depth (ft)	Soil Type	Moisture (%)	Plasticity (%)	Notes
CLAYEY SILT - Brown, very stiff, w/ some organics	1				
	3	2.4		26	
	4	B			
LL = 51, PL = 24, PI = 27	2				
	3	2.5		27	
	3	B			
becomes med-stiff	1				
	2	0.5		30	
	2	B			
becomes brown and gray	1				
	2	1.1		26	
	2	B			
SILTY CLAY - Brown and gray, med-stiff	533.2	WH			
		WH	0.6	28	
		1	B		
		WH			
		1	0.6	28	
		1	B		
		WH			
		1	0.7	27	
	2	B			
CLAYEY SILT - Dark gray, very stiff	525.7				
		WH			
		2	1.1	26	
		3	B		

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)



Page 1 of 1

Date 12/13/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1

Date 12/14/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1

Date 12/16/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

MODEL: SH06LX.MXES
FILE NAME: g:\projects\state_valley\docs\wall5\wall5-soil borings.dgn
User: jls Date: 5/2/2024 1:05:46 PM



USER NAME	=	DESIGNED	-	SJN	REVISED	-
		DRAWN	-	MAM	REVISED	-
PLOT SCALE	= 0.16666633' / in.	CHECKED	-	JLS	REVISED	-
PLOT DATE	= 5/2/2024	DATE	-	9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 5 I-64 WIDENING AND RECONSTRUCTION			
SCALE: N/A	SHEET 33	OF 38 SHEETS	STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	452
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/16/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.					Surface Water Elev.		ft
Station					Stream Bed Elev.		ft
BORING NO.	NWB-47				Groundwater Elev.:		
Station	856+00.00				First Encounter		ft
Offset	115.0 RLT				Upon Completion		ft
Ground Surface Elev.	531.11	ft	(ft)	(/6")	(tsf)	(%)	
CLAYEY SILT - Brown, very stiff							
			2				
			4	1.6	19		
			4	B			
			2				
			3	0.8	24		
			3	B			
			5				
	525.1		1				
			1	0.3	28		
			2	B			
			WH				
			2	0.6	26		
			2	B			
			10				
	520.1		WH				
			2	4.5	26		
			3	P			
			1				
			2	1.1	26		
			3	B			
			15				
			2				
			3	1.2	23		
			4	B			
			WH				
			2	1.3	23		
			2	B			
			20				
	511.1						

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/13/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.					Surface Water Elev.		ft
Station					Stream Bed Elev.		ft
BORING NO.	NWB-48				Groundwater Elev.:		
Station	858+00.00				First Encounter	507.4	ft
Offset	91.0 RLT				Upon Completion		ft
Ground Surface Elev.	525.92	ft	(ft)	(/6")	(tsf)	(%)	
TOPSOIL - 1"							
			2				
			1	0.4	29		
			1	B			
			2				
			3	0.5	25		
			2	S			
			5				
	522.4		2				
			3				
			2				
			5				
	519.9		WH				
			WH	0.1	28		
			1	S			
			WH				
			WH	0.2	28		
			1	B			
			10				
			1				
			1	0.3	25		
			2	B			
			WH				
			1	0.6	27		
			1	B			
			15				
			WH				
			1	0.5	22		
			1	S			
			2				
			1	0.2	15		
			4	S			
			20				
	507.4						
			1				
			2				
			4				
	505.9						

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/3/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.					Surface Water Elev.		ft
Station					Stream Bed Elev.		ft
BORING NO.	NWB-49				Groundwater Elev.:		
Station	859+99.90				First Encounter		ft
Offset	91.0 RLT				Upon Completion		ft
Ground Surface Elev.	523.69	ft	(ft)	(/6")	(tsf)	(%)	
TOPSOIL - 1.5"							
			2				
			1				
			2	0.6	24		
			2	B			
			2				
			2				
			3	0.6	27		
			4	B			
			5				
	520.2		2				
			3				
			4				
			5				
	517.7		1				
			1	0.3	25		
			1	S			
			515.2				
			1				
			1	0.4	27		
			2	S			
			10				
			WH				
			WH	0.5	26		
			2	B			
			510.2				
			1				
			2	1.3	22		
			2	B			
			15				
			1				
			3	1.5	21		
			4	B			
			505.2				
			WH				
			2	0.4	18		
			3	S			
			20				
	503.7						

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Page 1 of 1

Date 12/19/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____ Station _____	D E P T H	B L O W S	U C S	M O I S T	Surface Water Elev. _____ ft Stream Bed Elev. _____ ft
BORING NO. _____ Station _____ Offset _____ Ground Surface Elev. _____	H S	W S	Q _u		Groundwater Elev.: First Encounter _____ ft Upon Completion _____ ft After _____ Hrs. _____ ft
	ft	(ft)	(6")	(tsf)	(%)

TOPSOIL - 1"	522.6			
SILTY CLAY - Brown, med-stiff		1		
		3	0.4	16
	520.2	6	B	
CLAYEY SILT - Gray and brown, med-stiff		4		
		5	0.7	22
	517.7	6	S	
SILTY CLAY - Brown and gray, stiff, w/ some organics		2		
		3	0.9	23
		4	B	
		2		
		2	1.6	23
	-10	4	B	
becomes gray, med-stiff		1		
		2	1.5	22
		3	B	
becomes brown and gray, w/ some organics		2		
		2	1.3	16
	-15	4	B	
becomes gray		1		
		2	1.2	23
		3	B	
w/ some pebbles and gravel		2		
		3	0.7	22
	502.7	5	S	

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

Page 1 of 1

Date 12/19/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-TWRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____ Station _____	D E P T H	B L O W S	U C S Qu	M O I S T	Surface Water Elev. _____ ft Stream Bed Elev. _____ ft
BORING NO. _____ Station _____ Offset _____ Ground Surface Elev. _____	(ft)	(/6")	(tsf)	(%)	Groundwater Elev.: First Encounter _____ ft Upon Completion _____ ft After _____ Hrs. _____ ft
NWB-51 863+98.86 101.0 ft LT 520.59					

SILTY CLAY - Brown and gray, med-stiff	1	0.4	24
518.1	1 2	S	
CLAYEY SILT - Brown and gray, med-stiff, w/ some organics LL = 30, PL = 24, PI = 6	1		
515.6	1 2	0.5 S	27
SILTY CLAY - Brown and gray, med-stiff	1		
	2 2	0.6 B	26
	1		
	2 4	0.6 B	27
	-10		
becomes brown, w/ some organics	2		
	2 2	0.4 B	24
	1		
becomes stiff	2 2	1.3 B	25
	-15		
	1		
	2 2	1.0 B	23
	-20		
becomes dark gray, w/ gravel and sand, wet	WH		
500.6	1 2	0.3 S	18

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

MODEL: SHOEI\NAME2
FILE NAME: g:\projects\soil borings\volkert\soil borings\I-64 Widening and Reconstruction\CADD\CAD Sheets\B376K74-SH-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/12/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTHS	BLOW COUNTS	UNCONSOLIDATED QUANTITY	MOISTURE	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-52						
Station	865+98.34						
Offset	91.0 ft LT						
Ground Surface Elev.	519.30	ft	(ft)	(/6")	(tsf)	(%)	
TOPSOIL - 1"							
SILTY CLAY - Brown, med-stiff, w/ some organics							
becomes Brown and gray							
CLAYEY SILT - Dark gray, stiff							
becomes Brown and gray, w/ gravelly sand, med-dense							
SILTY CLAY - Brown and gray, very stiff							
Gravel - 0.6%, Sand - 29.4%, Fines - 70.0%							
SILTY SAND - Gray, med-stiff							
End of Boring							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/12/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTHS	BLOW COUNTS	UNCONSOLIDATED QUANTITY	MOISTURE	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-53						
Station	867+97.82						
Offset	91.0 ft LT						
Ground Surface Elev.	522.28	ft	(ft)	(/6")	(tsf)	(%)	
CLAYEY SILT - Gray and brown, med-stiff							
becomes Brown, w/ some organics							
SILTY CLAY - Brown and gray, med-stiff, poor recovery							
End of Boring							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/12/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPTHS	BLOW COUNTS	UNCONSOLIDATED QUANTITY	MOISTURE	Surface Water Elev.	Stream Bed Elev.
BORING NO.	NWB-54						
Station	869+97.30						
Offset	91.0 ft LT						
Ground Surface Elev.	522.57	ft	(ft)	(/6")	(tsf)	(%)	
TOPSOIL - 1"							
SILTY CLAY - Brown, med-stiff							
CLAYEY SILT - Dark gray, med-stiff, w/ some organics LL = 37, PL = 24, PI = 13							
SILTY CLAY - Brown and gray, med-stiff, w/ some organics							
CLAYEY SILT - Brown and gray, med-stiff							
SILTY CLAY - Brown, med-stiff							
becomes Brown and gray, w/ some pebbles							
CLAYEY SILT - Brown and gray, med-stiff, w/ gravel and pebbles							
End of Boring							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



USER NAME	=	DESIGNED	- SJN	REVISED	-
PLOT SCALE	= 0.16666633' / in.	DRAWN	- MAM	REVISED	-
PLOT DATE	= 5/2/2024	CHECKED	- JLS	REVISED	-
		DATE	- 9-10-24	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 7
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 35 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	454
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: SHOE\NAMEZ
FILE NAME: g:\projects\valley\valley\new\Documents\Project\116901 - PTB - 135-456 - Lea Widening and Reconstruction\CADD\CAD Sheets\B376K74-ASH-Noise Wall-Soil Borings.dgn



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/12/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT	BL	UC	MOIST	Surface Water Elev.	Stream Bed Elev.	DEPT	BL	UC	MOIST
BORING NO.	NWB-55	H	S	Qu	T	Groundwater Elev.:		H	S	Qu	T
Station	872+10.99					First Encounter					
Offset	91.0 ft LT					Upon Completion					
Ground Surface Elev.	524.01	ft	(ft)	(/6")	(tsf)	(%)	ft	(ft)	(/6")	(tsf)	(%)
SILTY CLAY - Dark Gray and brown, med-stiff											
			2				503.0		2		
			3	1.1	22				3	0.4	15
			6	B			501.5		4	S	
End of Boring											
becomes Gray											
			2								
			4	0.8	23						
			6	B							
CLAY - Dark Gray, med-stiff											
			1								
			1	0.7	26						
			3	B							
SILTY CLAY - Brown and gray, med-stiff											
			1	WH							
			1	0.6	27						
			1	B							
CLAYEY SILT - Brown and gray, med-stiff											
			1								
			2	0.8	23						
			2	B							
SILTY CLAY - Brown and gray, med-stiff, w/ pebbles and gravel											
			1								
			2	1.1	22						
			3	B							
CLAYEY SILT - Gray, med-stiff											
			1								
			2	0.8	24						
			1	B							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/9/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT	BL	UC	MOIST	Surface Water Elev.	Stream Bed Elev.	DEPT	BL	UC	MOIST
BORING NO.	NWB-56	H	S	Qu	T	Groundwater Elev.:		H	S	Qu	T
Station	874+10.47					First Encounter					
Offset	91.0 ft LT					Upon Completion					
Ground Surface Elev.	525.93	ft	(ft)	(/6")	(tsf)	(%)	ft	(ft)	(/6")	(tsf)	(%)
CLAYEY SILT - Gray, med-stiff											
			3								
			5	1.1	22						
			3	B							
becomes Brown											
			2								
			1	0.8	27						
			2	B							
SILTY CLAY - Gray and brown, med-stiff											
			1								
			2	0.6	28						
			1	B							
CLAYEY SILT - Brown, med-stiff											
			2								
			3	0.6	27						
			2	B							
SILTY CLAY - Brown, med-stiff											
			2								
			2	0.7	26						
			2	B							
CLAYEY SILT - Gray and brown, med-stiff, w/ gravel											
			2								
			2	0.6	24						
			4	B							
SILTY CLAY - Brown and gray, med-stiff											
			1								
			2	0.7	26						
			3	B							

End of Boring
The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



Illinois Department
of Transportation
Division of Highways

SOIL BORING LOG

Page 1 of 1

Date 12/9/22

ROUTE F.A.I. RTE. 64 DESCRIPTION I-64 from West of Green Mount Rd to West of IL 158 LOGGED BY KEG

SECTION 87-7WRS-2 LOCATION

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO.	Station	DEPT	BL	UC	MOIST	Surface Water Elev.	Stream Bed Elev.	DEPT	BL	UC	MOIST
BORING NO.	NWB-57	H	S	Qu	T	Groundwater Elev.:		H	S	Qu	T
Station	876+09.95					First Encounter					
Offset	91.0 ft LT					Upon Completion					
Ground Surface Elev.	527.26	ft	(ft)	(/6")	(tsf)	(%)	ft	(ft)	(/6")	(tsf)	(%)
TOPSOIL - 1"											
			526.4								
CLAYEY SILT - Brown, med-stiff											
			2								
			4	0.4	22						
			3	B							
End of Boring											
			504.8								
SILTY CLAY - Gray, med-stiff											
			2								
			2	0.5	24						
			3	B							
CLAY - Brown, med-stiff											
			1								
			2	0.6	26						
			3	B							
w/ some organics											
			1								
			2	0.6	25						
			4	B							
SILTY CLAY - Brown and gray, med-stiff											
			2								
			2	0.6	22						
			2	B							
becomes Dark Brown and gray											
			1								
			2	1.0	24						
			3	B							
CLAYEY SILT - Brown, med-stiff, moist, w/ some organics											
			1								
			2	0.8	24						
			2	B							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)
BBS, form 137 (Rev. 8-99)



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 7
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A SHEET 36 OF 38 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	455
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

Page 1 of 1

Date 12/9/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

STRUCT. NO. _____	D	B	U	M	Surface Water Elev. _____ ft
Station _____	E	L	C	O	Stream Bed Elev. _____ ft
	P	O	S	I	
BORING NO. _____	T	W	Q	T	Groundwater Elev.: _____
Station <u>878+09.43</u>	H	S			First Encounter <u>511.5</u> ft
Offset <u>90.6 ft LT</u>					Upon Completion _____ ft
Ground Surface Elev. <u>527.53</u> ft	(ft)	(ft)	(tsf)	(%)	After Hrs. _____ ft

Soil Description	Depth (ft)	Soil Type	Moisture (%)	Notes
TOPSOIL - 1"	527.4			
SILTY CLAY - Brown, med-stiff		1		
		1	0.7	21
		1	B	
	524.0			
CLAY - Brown, med-stiff, w/ organics		1		
		1	0.5	25
		2	S	
	521.5			
SILTY CLAY - Brown, med-stiff		1		
		1	0.4	23
		2	B	
	519.0			
CLAY - Brown, med-stiff LL = 35, PL = 20, PI = 15		1		
		2	0.6	20
		2	B	
	-10			
w/ some organics		1		
		1	0.6	24
		2	B	
	514.0			
CLAYEY SILT - Brown and gray, med-stiff, w/ organics		2		
		2	1.1	25
		3	B	
	-15			
becomes wet, poor recovery		WH		
		WH	0.4	24
		WH	S	
	509.0			
SANDY SILT - Light brown, soft to med-stiff		WH		
		2	-	25
		3		
	507.5			

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)



USER NAME =	DESIGNED - SJN	REVISED -
	DRAWN - MAM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - JLS	REVISED -
PLOT DATE = 5/2/2024	DATE - 9-10-24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING LOGS - NOISE WALL 7

SCALE: N/A	SHEET 37	OF 38	SHEETS	STA. N/A	TO STA. N/A
------------	----------	-------	--------	----------	-------------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	456
		CONTRACT NO. 76K74		
ILLINOIS		FED. AID PROJECT		



Page 1 of 1

Date 12/9/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

End of Boring

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

Page 1 of 1

Date 12/19/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY St. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

[illegible]

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

Page 1 of 1

Date 12/19/22

ROUTE	F.A.I. RTE. 64	DESCRIPTION	158	LOGGED BY	KEG
-------	----------------	-------------	-----	-----------	-----

SECTION 87-7WRS-2 LOCATION _____

COUNTY Sl. Clair DRILLING METHOD AUTO HAMMER TYPE HSA 2 1/4"

	1992	1993	1994
--	------	------	------

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

VOLKERT

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


SOIL BORING LOGS - NOISE WALL 8
I-64 WIDENING AND RECONSTRUCTION

SCALE: N/A	SHEET 38	OF 38	SHEETS	STA. N/A	TO STA. N/A
------------	----------	-------	--------	----------	-------------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7HB-1	ST. CLAIR	691	457
		CONTRACT NO. 76K74		
ILLINOIS		FED. AID PROJECT		

Existing Structure: S.N. 082-0181 was constructed in 1971 as Section 82-7HB-1. In 2005, the concrete deck received crack sealing, repairs, and a microsilica concrete overlay. The parapets were extended and bearings replaced at the pier and both abutments, including adding cap extensions at each bearing location. The structure consists of vaulted abutments supported by spread footings with driven H-Piles, and a multiple column hammerhead pier supported by a spread footing with driven H-Piles. The back-to-back of approach bents length measures 257'-1", the out-to-out of deck width measures 46'-0". The span lengths are both 95'-6". The structure is skewed 24°07'35" left forward. One lane of bi-directional traffic will be maintained utilizing stage construction for daytime closures.

No Salvage.




ELEVATION
(Looking East, Projected from
Local Tangent @ Sta. 40+03.48)

EXISTING CURVE DATA
S. LINCOLN AVE. (C.H. 43)

Δ = 17°13'49" (LT)
D = 2°00'00"
R = 2,864.79'
T = 434.03'
L = 861.51'
E = 32.69'
P.C. Sta. = 37+35.57
P.I. Sta. = 41+69.60
P.T. Sta. = 45+97.08
S.E. = 2.5%

NOTE:
See Signing Plans for any modifications
required to the bridge mounted sign
structures, and for replacement signs.



PLAN

*Existing shoulder drains to be cleaned in
accordance with the special provisions.
Paid for as Cleaning Existing Inlets.

DESIGN SPECIFICATIONS
2002 AASHTO Standard Specifications
for Highway Bridges

EXISTING DESIGN STRESSES

FIELD UNITS (1969):

f'c = 3,000 psi (Deck)
f'c = 3,500 psi (Curb, Parapet, Substructure)
fy = 40,000 psi (Reinforcement)
fy = 36,000 psi (Structural Steel)

PRECAST PRESTRESSED UNITS (1969):

f'c = 5,000 psi
f'ci = 4,000 psi
fs' = 248,000 psi (Strands)
fsi = 173,600 psi (Strands)

PROPOSED DESIGN STRESSES

FIELD UNITS:


f'c = 3,500 psi
f'c = 4,000 psi (Superstructure)
fy = 60,000 psi (Reinforcement)

LOADING HS 20-44

No allowance for future wearing surface.

SCOPE OF WORK


- 1.) Traffic will be maintained utilizing stage construction for daytime closures.
- 2.) Repair the concrete deck and approach slabs.
- 3.) Remove and replace existing Silicone Joint Seals at the expansion joints.
- 4.) Remove and replace rectangular floor drains with 6" ø Floor Drains and Drainage Scuppers, DS-11.
- 5.) Pier crashwall modifications and median barrier transitions.
- 6.) Substructure repairs.
- 7.) Reconfigure slope walls, including gutter removal and replacement.



LOCATION SKETCH

INDEX OF SHEETS

SHEET NO.	TITLE
1	GENERAL PLAN AND ELEVATION
2	GENERAL DATA AND MISCELLANEOUS DETAILS
3	STAGE CONSTRUCTION DETAILS
4	DECK AND APPROACH SLAB REPAIRS
5	DRAINAGE SCUPPERS, DS-11
6	NORTH ABUTMENT REPAIRS
7	SOUTH ABUTMENT REPAIRS
8	PIER CRASHWALL EXTENSION
9	BARRIER TRANSITION DETAILS
10	PIER REPAIRS
11	SLOPE WALL MODIFICATION DETAILS



Vincent P. Tabor 03/19/2025

Vincent P. Tabor Date
Licensed Structural Engineer
State of Illinois No. 081-007047
Expires 11/30/2026

SOUTH LINCOLN AVENUE (C.H. 43)
OVER I-64
F.A.I. RTE. 64 - SEC. 82-7WRS-2
ST. CLAIR COUNTY
STATION 40+03.48
STRUCTURE NO. 082-0181



DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
DATE - 09/12/2024	CHECKED - VPT
	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN AND ELEVATION

SHEET NO. 1 OF 11 SHEETS



F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	458
CONTRACT NO. 76K74				ILLINOIS

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	13.5
Floor Drains	Each	3
Concrete Structures	Cu. Yd.	21.4
Protective Coat	Sq. Yd.	14
Reinforcement Bars, Epoxy Coated	Pound	1,590
Slope Wall 4 Inch	Sq. Yd.	106
Concrete Sealer	Sq. Ft.	14,861
Epoxy Crack Injection	Foot	553
Approach Slab Repair (Partial Depth)	Sq. Yd.	2
Cleaning Existing Inlets	Each	2
Structural Repair Of Concrete (Depth Equal To Or Less Than 5 Inches)	Sq. Ft.	47
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	5
Deck Slab Repair (Partial)	Sq. Yd.	2
Drainage Scuppers, DS-11	Each	3
Silicone Joint Sealer, 1.5"	Foot	100
Polymer Concrete	Cu. Ft.	15


GENERAL NOTES:

- 1.) Reinforcement bars designated (E) shall be epoxy coated.
- 2.) Plan dimensions and details relative to the existing structure have been taken from existing plans and are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
- 3.) A protective coat shall be applied to new concrete adjacent to the expansion joints; and to the finished surfaces of all deck, approach slab, and inside face of parapet repairs.
- 4.) The deck surface shall have its final finish tined according to Article 420.09(e)(1) of the Standard Specifications. This final finish will not be measured for payment, but shall be included in the contract unit price for the associated work.
- 5.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to the entire existing top surface of the bridge deck and approach slabs; the existing top and inside vertical faces of the parapets, end posts, and wings; all exposed faces of the abutment, wingwall, and pier repairs; new concrete on pier crashwalls and barrier transitions; and also on the traffic face of the existing abutment and pier surfaces.
- 6.) All new structural steel shall be hot-dip galvanized. See Special Provisions for Hot Dip Galvanizing for Structural Steel.
- 7.) Stationing shown along South Lincoln Ave. has been taken from the 1969 existing plans.
- 8.) The Contractor may request copies of existing construction plans that are currently on file with the Department. The request shall be in writing with the understanding that any reproduction cost will be at the Contractor's expense at no additional cost to the Department.








SILICONE JOINT SEALER DETAIL

Removal of existing Silicone Joint Sealer and backer rod will not be paid for separately, but shall be included in the cost of Silicone Joint Sealer. See the Special Provisions.



OFFSET SKETCH




Notes:

Fiberglass pipe shall conform to ASTM D2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum.


The exterior surfaces of the floor drains shall be painted according to Article 506 with the finish coat as specified. The exterior surfaces of the drains shall be cleaned according to the Society of Protective Coatings Spec. SSPC-SP1 prior to painting.

The top portion of aluminum floor drains shall be coated to minimize reaction with wet concrete.


The clamping device shall be galvanized according to AASHTO M 232. Cost of clamping device included with Floor Drains.



EXISTING CROSS SECTION
(Looking South)
Horizontal dimensions are radial.



STAGE I TRAFFIC AND CONSTRUCTION
(Looking South)
Horizontal dimensions are radial.



STAGE II TRAFFIC AND CONSTRUCTION
(Looking South)
Horizontal dimensions are radial.

NOTES:

- 1.) One lane of bi-directional traffic will be maintained utilizing stage construction for daytime closures.
- 2.) See Maintenance of Traffic plans and special provisions for additional daytime closure details and requirements.





DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**


**STAGE CONSTRUCTION DETAILS
STRUCTURE NO. 082-0181**

SHEET NO. 3 OF 11 SHEETS


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	460
				CONTRACT NO. 76K74
ILLINOIS				




PLAN




PLAN




PLAN




PLAN




SECTION A-A



SECTION B-B



SECTION C-C



SECTION D-D

- LEGEND**



 Concrete Removal for Scupper or Floor Drain Placement	 Approach Slab Repair (Partial Depth)
 Deck Slab Repair (Full Depth, Type I)	 Deck Slab Repair (Partial)
 L.F.	
Epoxy Crack Injection	

NOTES:


- 1.) Any repairs to the driving surface that cannot be completed and fully cured by the end of a daytime closure shall be protected by a steel plate that has been secured through the deck by threaded rods or bolts. All exposed edges of the plates, rods, bolts, and nuts that extend above the driving surface shall be ground smooth. Holes drilled through the deck for purpose of securing the steel plate shall be repaired with an Epoxy Bonding Compound in accordance with Section 590 of the Standard Specifications. All costs associated with protection of incomplete repairs will not be paid for separately, but shall be included in the cost of the work for which is required.
- 2.) The area of Approach Slab Repair (Partial Depth) shown at the North approach slab is estimated based on a field inspection conducted in September 2023. All other repair areas shown are estimated based on field inspections conducted in November 2022. The actual repair areas required shall be verified according to the special provisions.
- 3.) Full depth deck slab repair areas shown at existing floor drains shall include removal of the existing floor drains, plus any deteriorated concrete surrounding the drains. Removal of the floor drains and deteriorated concrete surrounding them shall be included in the cost of Deck Slab Repair (Full Depth, Type I).
- 4.) ***Quantities displayed in the Bill of Material with units of Sq. Yd. have been increased beyond the areas indicated in the Plan views and Sections shown on this sheet in order to provide a minimum combined total of 5 Sq. Yd. between S.N. 082-0181 and S.N. 082-0344.
- 5.) Work on the bridge deck shall be coordinated with lane closures under the bridge on I-64, in order to eliminate exposure of traffic to falling debris. All costs associated with protection of traffic below the bridge will not be paid for separately, but shall be included in the cost of the work for which it is required.
- 6.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to the entire existing top surface of the bridge deck and approach slabs; and the existing top and inside vertical faces of the parapets, end posts, and wings.

BILL OF MATERIAL


	ITEM	UNIT	TOTAL
	Concrete Removal	Cu. Yd.	1.1
	Epoxy Crack Injection	Foot	465
***	Approach Slab Repair (Partial Depth)	Sq. Yd.	2
***	Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	5
***	Deck Slab Repair (Partial)	Sq. Yd.	2




SECTION A-A
See sheet 4 of 11 for scupper location relative to parapet.




VANE GRATE DETAIL




GRATE BOLT HOLE DETAIL



SECTION B-B



DOWNSPOUT



ANCHOR ROD DETAIL

Notes:

All cast iron parts shall be gray iron conforming to the requirements of AASHTO M105, Class 35B and AASHTO M306.

Bolts, anchor rods, nuts and washers shall be according to ASTM A307 and shall be galvanized according to AASHTO M232. As an alternate stainless steel may be used.

Stainless steel hardware shall be according to Article 1006.29(d) of the Standard Specifications.

Structural steel weldments of equal sections and of the same configuration may be substituted for the cast iron scupper frames and downspouts; however, the scupper grates shall remain cast iron. Fillet or full penetration welds shall be used for the weldments. Details shall be submitted to the Engineer for approval.

Structural steel scupper frames and downspouts, when utilized, shall be galvanized according to AASHTO M111.

As an alternate, fiberglass may be used for downspouts according to ASTM D2996 with a short-time rupture strength hoop tensile stress of 30,000 psi min. in lieu of the cast iron or structural steel.

Exterior surfaces of downspouts and exterior exposed surfaces of the scupper frame below deck shall be treated as specified on sheet 2 of 11.

The Contractor shall take appropriate measures to assure that Protective Coat is not applied to the scupper.

Cost of the grate, frame, downspout, anchor rods, nuts and washers including complete installation of the scupper shall be paid for at the contract unit price for Drainage Scuppers, DS-11.

BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Drainage Scuppers, DS-11	Each	3

DS-11 2-1-2023




DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED
DATE - 09/12/2024	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DRAINAGE SCUPPERS, DS-11
STRUCTURE NO. 082-0181

SHEET NO. 5 OF 11 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	462
ILLINOIS			CONTRACT NO. 76K74	




NORTH ABUTMENT ELEVATION
(Looking North)

BILL OF MATERIAL


ITEM	UNIT	TOTAL
Concrete Sealer	Sq. Ft.	525
Epoxy Crack Injection	Foot	26
Structural Repair Of Concrete (Depth Equal To Or Less Than 5 Inches)	Sq. Ft.	27

LEGEND

-  Structural Repair of Concrete (Depth Equal to or Less than 5 Inches)
-  Epoxy Crack Injection




WEST CURTAIN WALL ELEVATION
(Looking East)



EAST CURTAIN WALL ELEVATION
(Looking West)

NOTES:

- 1.) The repair areas shown are estimated based on field inspections conducted in November 2022. The actual repair areas required shall be verified according to the special provisions.
- 2.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to exposed surface of proposed concrete repairs on the abutment and wingwalls, and the traffic face of the existing abutment surface.




SOUTH ABUTMENT ELEVATION
(Looking South)

BILL OF MATERIAL


ITEM	UNIT	TOTAL
Concrete Sealer	Sq. Ft.	573
Epoxy Crack Injection	Foot	55
Structural Repair Of Concrete (Depth Equal To Or Less Than 5 Inches)	Sq. Ft.	9

LEGEND

-  Structural Repair of Concrete (Depth Equal to or Less than 5 Inches)
-  Epoxy Crack Injection





EAST CURTAIN WALL ELEVATION
(Looking West)



WEST CURTAIN WALL ELEVATION
(Looking East)

NOTES:


- 1.) The repair areas shown are estimated based on field inspections conducted in November 2022. The actual repair areas required shall be verified according to the special provisions.
- 2.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to exposed surface of proposed concrete repairs on the abutment and wingwalls, and the traffic face of the existing abutment surface.
- 3.) Existing junction box and electrical conduit shall be removed, if necessary, to perform concrete repairs, and reinstalled. Cost included with Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches).



SECTION B-B


BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h(E)	34	#5	10'-8"	—
n(E)	100	#5	2'-5"	⌋
s(E)	24	#5	18'-5"	□
Item			Unit	Quantity
Concrete Structures			Cu. Yd.	13.5
Reinforcement Bars, Epoxy Coated			Pound	1,100
Concrete Sealer			Sq. Ft.	277




NOTES:


- 1.) Drill & epoxy grout #5 n(E) bars 9" min. into existing concrete according to Section 584 of the Standard Specifications.
- 2.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to exposed surface of proposed pier crashwall extensions.
- 3.) E.F. denotes Each Face and E.E. denotes Each End.




ELEVATION




PLAN




DETAIL A - EXPANSION JOINT
(See Std. 637006)




SECTION C-C
(See Std. 637006)




SECTION D-D




SECTION E-E




BAR s1(E)



BAR v1(E)



HOOK BAR DETAIL
(See Std. 637006)



FIELD CUTTING DIAGRAM

Order v(E) bars full length. Cut as shown and use remainder of bars in opposite face.

NOTES:

- 1.) Drill & epoxy grout #4 h2(E) bars 9" min. into existing concrete according to Article 584 of the Standard Specifications.
- 2.) The cost of the expansion joint shall be included with Concrete Structures.
- 3.) The cost of the hook bars shall be included with Concrete Structures.
- 4.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to exposed surface of proposed barrier transitions.
- 5.) E.F. denotes Each Face and E.E. denotes Each End.
- 6.) See Sheet 1 of 11 for location of Barrier Transitions.

BILL OF MATERIAL
(Two Barrier Transitions)

Bar	No.	Size	Length	Shape
h1(E)	26	#5	9'-9"	—
h2(E)	24	#4	1'-9"	—
s1(E)	20	#4	2'-7"	└
v(E)	20	#4	9'-4"	┌
v1(E)	8	#4	5'-5"	┌
Item			Unit	Quantity
Concrete Structures			Cu. Yd.	7.9
Reinforcement Bars, Epoxy Coated			Pound	490
Concrete Sealer			Sq. Ft.	216



DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BARRIER TRANSITION DETAILS
STRUCTURE NO. 082-0181


SHEET NO. 9 OF 11 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	466
			CONTRACT NO. 76K74	

ILLINOIS



PARTIAL PIER ELEVATION
(Looking South)



PARTIAL PIER ELEVATION
(Looking North)

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Sealer	Sq. Ft.	710
Structural Repair Of Concrete (Depth Equal To Or Less Than 5 Inches)	Sq. Ft.	11

NOTES:

- 1.) The repair areas shown are estimated based on field inspections conducted in November 2022. The actual repair areas required shall be verified according to the special provisions.
- 2.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to all exposed faces of the pier repairs, and also on the traffic faces of the existing pier surfaces.

LEGEND



Structural Repair of Concrete (Depth Equal to or Less than 5 Inches)





DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PIER REPAIRS
STRUCTURE NO. 082-0181

SHEET NO. 10 OF 11 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	467
ILLINOIS			CONTRACT NO. 76K74	



SECTION C-C

BILL OF MATERIAL


ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	12.4
Slope Wall 4 Inch	Sq. Yd.	106
Epoxy Crack Injection	Foot	7

LEGEND

	Concrete Removal for Slope Wall
	Epoxy Crack Injection


NOTES:

- 1.) The repair areas shown are estimated based on field inspections conducted in November 2022. The actual repair areas required shall be verified according to the special provisions.
- 2.) Slope wall shall be reinforced with welded wire fabric, 6 in. x 6 in. - W4.0 x W4.0, weighing 58 lbs. per 100 sq. ft.



SECTION A-A

*Match Exist. Slope Wall Elevation, typ.



SECTION B-B

*Match Exist. Slope Wall Elevation, typ.



DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED
DATE - 09/12/2024	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


SLOPE WALL MODIFICATION DETAILS
STRUCTURE NO. 082-0181

SHEET NO. 11 OF 11 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	468
				CONTRACT NO. 76K74
ILLINOIS				

Existing Structure: S.N. 082-0344 was constructed in 2001 as Section 82-7HB. The superstructure consists of a two-span continuous composite steel plate girder with a 7½" cast-in-place concrete deck, with a full length raised concrete median. The substructure consists of reinforced concrete spill-thru abutments supported by concrete piles and a multiple column hammerhead pier supported by a spread footing with driven H-Piles. The back-to-back of abutments length measures 280'-2¼" and the out-to-out of deck width measures 68'-6⅞". The span lengths are both 136'-1⅞". The structure is skewed 26°31'40" left forward. The structure will be closed to traffic for construction, using weekend closures.

No Salvage.



ELEVATION
(Looking East)

EXISTING CURVE DATA


F.A.I. 64 (I-64)

Δ = 61°53'09" (LT)
D = 1°15'00"
R = 4,583.66'
T = 2,747.93'
L = 4,950.87'
E = 760.59'
e = Existing
T.R. = Existing
P.C. Sta. = 733+43.81
P.I. Sta. = 760+91.74
P.T. Sta. = 782+94.67
S.E. = 3.5%

NOTE:

See Signing Plans for any modifications required to the bridge mounted sign structures, and for replacement signs.

SHEET NO.	TITLE
1	GENERAL PLAN AND ELEVATION
2	GENERAL DATA AND MISCELLANEOUS DETAILS
3	DECK AND APPROACH SLAB REPAIRS
4	BEAM STRAIGHTENING DETAILS
5	ABUTMENT REPAIRS
6	PIER CRASHWALL EXTENSION
7	BARRIER TRANSITION DETAILS
8	PIER REPAIRS
9	SLOPE WALL MODIFICATION DETAILS



PLAN

DESIGN SPECIFICATIONS

2002 AASHTO Standard Specifications
for Highway Bridges

EXISTING DESIGN STRESSES

FIELD UNITS (2000):

f'c = 3,500 psi
fy = 60,000 psi (Reinforcement)
fy = 36,000 psi (Structural Steel)
fy = 50,000 psi (Structural Steel)

PROPOSED DESIGN STRESSES

FIELD UNITS:


f'c = 3,500 psi
f'c = 4,000 psi (Superstructure)
fy = 60,000 psi (Reinforcement)

LOADING HS20-44

Allow 50#/sq. ft. for
future wearing surface.

SCOPE OF WORK


- 1.) The structure will be closed to traffic for construction, using weekend closures.
- 2.) Replace the existing expansion joints with Preformed Joint Seal.
- 3.) Repair the concrete deck and approach slab.
- 4.) Pier crashwall modifications and median barrier transitions.
- 5.) Substructure repairs.
- 6.) Reconfigure slope walls, including gutter removal and replacement.
- 7.) Beam straightening at location of exterior beam strike.
- 8.) Paint beam ends (including bearings and end diaphragms).



LOCATION SKETCH

LEGEND

Limits of Protective Shield



Vincent P. Tabor

03/19/2025

Vincent P. Tabor
Licensed Structural Engineer
State of Illinois No. 081-007047
Expires 11/30/2026

NORTH GREEN MOUNT ROAD OVER I-64

F.A.I. RTE. 64 - SEC. 82-7WRS-2

ST. CLAIR COUNTY

STATION 40+19.80

STRUCTURE NO. 082-0344



DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN AND ELEVATION

SHEET NO. 1 OF 9 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	469
				CONTRACT NO. 76K74


TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	18.3
Protective Shield	Sq. Yd.	988
Concrete Structures	Cu. Yd.	45.1
Protective Coat	Sq. Yd.	14
Reinforcement Bars, Epoxy Coated	Pound	3,280
Slope Wall 4 Inch	Sq. Yd.	119
Preformed Joint Seal 3"	Foot	152
Concrete Sealer	Sq. Ft.	27,405
Epoxy Crack Injection	Foot	290
Containment And Disposal Of Non-Lead Paint Cleaning Residues No. 1	L. Sum	1
Approach Slab Repair (Partial Depth)	Sq. Yd.	3
Beam Straightening	L. Sum	1
Cleaning And Painting Steel Bridge No. 1	L. Sum	1
Cleaning Existing Inlets	Each	4
Structural Repair Of Concrete (Depth Equal To Or Less Than 5 Inches)	Sq. Ft.	7
Deck Slab Repair (Partial)	Sq. Yd.	3
Polymer Concrete	Cu. Ft.	15


GENERAL NOTES:

- 1.) Reinforcement bars designated (E) shall be epoxy coated.
- 2.) Plan dimensions and details relative to the existing structure have been taken from existing plans and are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
- 3.) A protective coat shall be applied to new concrete adjacent to the expansion joints; and to the finished surfaces of all deck, approach slab, median, and inside face of parapet repairs.
- 4.) The deck surface shall have its final finish tined according to Article 420.09(e)(1) of the Standard Specifications. This final finish will not be measured for payment, but shall be included in the contract unit price for the associated work.
- 5.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to the entire existing top surface of the bridge deck and approach slabs; the existing top and inside vertical faces of the parapets, end posts, and wings; the top and vertical faces of the median; all exposed faces of the abutment, wingwall, and pier repairs; new concrete on pier crashwalls and barrier transitions; and also on the traffic face of the existing abutment and pier surfaces.
- 6.) Cleaning and painting of the existing structural steel shall be as specified in the special provisions for Cleaning and Painting Existing Steel Structures. All beams, bearings and other structural steel within 5'-0" (measured along the beam) of either side of deck joints shall be cleaned per Near White Blast Cleaning (SSPC-SP10). The exterior surfaces and bottom of the bottom flange of the fascia beams shall be cleaned per Commercial Grade Power Tool Cleaning (SSPC-SP15).
- 7.) The designated areas cleaned per Near White Blast Cleaning (SSPC-SP10) and per Commercial Grade Power Tool Cleaning (SSPC-SP10) and per Commercial Grade Power Tool Cleaning (SSPC-SP15) shall be painted according to the requirements of Epoxy Mastic Primer/Epoxy Mastic Intermediate Coat/Acrylic Topcoat (EM/EM/AC). The color of the final finish coat shall be Gray, Munsell No. 5B 7/1.
- 8.) Containment of cleaning residue is required to control nuisance dust. See special provisions.
- 9.) SSPC QP1 Certification is required for this Contract.
- 10.) Existing plans were drawn using Metric units. All dimensions in these plans have been converted to U.S. Survey Feet. Existing stationing was placed using Metric units. Proposed stationing is using U.S. Survey Feet. Centerline of Structure Station 11+004.152 (Metric) = Station 40+19.80 (U.S. Survey Feet).
- 11.) The Contractor may request copies of existing construction plans that are currently on file with the Department. The request shall be in writing with the understanding that any reproduction cost will be at the Contractor's expense at no additional cost to the Department.
- 12.) The structure will be closed to traffic for construction. Multiple weekend closures may be required in order to complete the work affecting traffic on North Green Mount Road. See the special provision for Traffic Control and Protection (Special), and the Traffic Control plans for additional details.

LEGEND




MEDIAN JOINT CONCRETE REMOVAL




MEDIAN JOINT CONCRETE REPLACEMENT

NOTE:


Cost of removal of existing joint materials, including but not limited to steel reinforced elastomeric anchor blocks, steel plates, elastomeric membrane, and sealant, will not be paid for separately, but shall be considered as included in the contract unit price for the associated work.




DECK JOINT CONCRETE REMOVAL



DECK JOINT CONCRETE REPLACEMENT



ELEVATION - INSIDE FACE
OF PARAPET AT JOINT




ELEVATION AT ABUTMENTS

SECTION A-A


EXISTING TYPE I ELASTOMERIC EXP. BRG.

For information only, for Cleaning and Painting Steel Bridge.




EXISTING END DIAPHRAGM

For information only, for Cleaning and Painting Steel Bridge.



EXISTING SIDE RETAINER

For information only, for Cleaning and Painting Steel Bridge.



PLAN

LEGEND

- Approach Slab Repair (Partial Depth)
- Deck Slab Repair (Partial)
- L.F. Epoxy Crack Injection

NOTES:

- The repair areas shown are estimated based on field inspections conducted in November 2022. The actual repair areas required shall be verified according to the special provisions.
- *Quantities displayed in the Bill of Material with units of Sq. Yd. have been increased beyond the areas indicated in the Plan view shown on this sheet in order to provide a minimum combined total of 5 Sq. Yd. between S.N. 082-0181 and S.N. 082-0344.
- Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to the entire existing top surface of the bridge deck and approach slabs; the existing top and inside vertical faces of the parapets, end posts, and wings; and the top and vertical faces of the median.
- Quantity shown for Epoxy Crack Injection includes repair of the parapet identified on Sheet 1 of 9.

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Epoxy Crack Injection	Foot	225
* Approach Slab Repair (Partial Depth)	Sq. Yd.	3
* Deck Slab Repair (Partial)	Sq. Yd.	3




DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED
DATE - 09/12/2024	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DECK AND APPROACH SLAB REPAIRS
STRUCTURE NO. 082-0344


SHEET NO. 3 OF 9 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	471
ILLINOIS				CONTRACT NO. 76K74




PARTIAL PLANS SUGGESTED BEAM STRAIGHTENING METHODS


Straightening force shall be maintained on all load transfer blocking during beam straightening.




SECTION A-A



SECTION B-B




SUGGESTED VERTICAL STRAIGHTENING DETAIL (To correct flange rotation.)



SUGGESTED VERTICAL STRAIGHTENING DETAIL (To correct localized vertical flange deformations.)


* Edge of plate shall line up with edge of deformation.

Note:
Braces and jack assembly shall be placed on same side of web.
Bent bottom flange shall be straightened before starting any horizontal straightening operations.



GRINDING DETAIL

Grind existing nicks, gouges and shallow cracks in the damaged beams as detailed. Ground surfaces shall be inspected for cracks using dye penetrant or magnetic particle testing prior to initiating any beam straightening operations. Any cracks that cannot be removed by grinding approximately 1/4" deep shall be identified and reported to the Bureau of Bridges and Structures for further disposition. Ground surfaces shall be spot cleaned and painted with an aluminum epoxy mastic primer followed by a finish coat to match the color of the existing beam. Cost of grinding, testing and spot painting included with Beam Straightening.



**EXISTING DEFORMATION
TO BE STRAIGHTENED**
(Looking North along Beam No. 11)
(Approximate max. deflections)
Deflected length of beam to be straightened is approximately 10'-0".

REP-1 8-16-2018




DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED
DATE - 09/12/2024	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


BEAM STRAIGHTENING DETAILS
STRUCTURE NO. 082-0344

SHEET NO. 4 OF 9 SHEETS


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	472
				CONTRACT NO. 76K74
ILLINOIS				



NORTH ABUTMENT ELEVATION
(Looking North)



NORTHWEST WINGWALL ELEVATION
(Looking East)



NORTHEAST WINGWALL ELEVATION
(Looking West)

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Sealer	Sq. Ft.	244
Epoxy Crack Injection	Foot	3
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	5


LEGEND




Structural Repair of Concrete (Depth
Equal to or Less than 5 Inches)

L.F.


Epoxy Crack Injection



SOUTH ABUTMENT ELEVATION
(Looking South)




SOUTHEAST WINGWALL ELEVATION
(Looking West)




SOUTHWEST WINGWALL ELEVATION
(Looking East)

NOTES:

- 1.) The repair areas shown are estimated based on field inspections conducted in November 2022. The actual repair areas required shall be verified according to the special provisions.
- 2.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to exposed surface of proposed concrete repairs on the abutment and wingwalls, and the traffic face of the existing abutment surface.




ELEVATION
(Looking South)



SECTION B-B

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h10(E)	48	#5	9'-10"	—
n10(E)	144	#5	2'-5"	⌋
s10(E)	44	#5	13'-7"	□
Item		Unit	Quantity	
Concrete Structures		Cu. Yd.	19.0	
Reinforcement Bars, Epoxy Coated		Pound	1,480	
Concrete Sealer		Sq. Ft.	468	



NOTES:

- 1.) Drill & epoxy grout #5 n10(E) bars 9" min. into existing concrete according to Section 584 of the Standard Specifications.
- 2.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to exposed surface of proposed pier crashwall extensions.
- 3.) E.F. denotes Each Face and E.E. denotes Each End.




DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED
DATE - 09/12/2024	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


PIER CRASHWALL EXTENSION
STRUCTURE NO. 082-0344

SHEET NO. 6 OF 9 SHEETS


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	474
CONTRACT NO. 76K74				
ILLINOIS				




ELEVATION




PLAN




DETAIL A - EXPANSION JOINT
(See Std. 637006)




SECTION C-C
(See Std. 637006)
*1:48 batter permitted



SECTION D-D




SECTION E-E




HOOK BAR DETAIL
(See Std. 637006)

BILL OF MATERIAL (Two Barrier Transitions)				
Bar	No.	Size	Length	Shape
h11(E)	40	#5	22'-11"	
h12(E)	36	#4	1'-9"	
s11(E)	44	#4	2'-7"	
s12(E)	28	#4	3'-3"	
v10(E)	44	#5	13'-0"	
v11(E)	4	#5	7'-3"	
v12(E)	8	#5	4'-3"	
Item			Unit	Quantity
Concrete Structures			Cu. Yd.	26.1
Reinforcement Bars, Epoxy Coated			Pound	1,800
Concrete Sealer			Sq. Ft.	591




FIELD CUTTING DIAGRAM
Order v10(E) bars full length. Cut as shown and use remainder of bars in opposite face.

- NOTES:
- 1.) Drill & epoxy grout #4 h12(E) bars 9" min. into existing concrete according to Article 584 of the Standard Specifications.
 - 2.) The cost of the expansion joint shall be included with Concrete Structures.
 - 3.) The cost of the hook bars shall be included with Concrete Structures.
 - 4.) Concrete Sealer shall be applied according to Section 587 of the Standard Specifications to exposed surface of proposed barrier transitions.
 - 5.) E.F. denotes Each Face and E.E. denotes Each End.
 - 6.) See Sheet 1 of 9 for location of Barrier Transitions.



PLAN




SECTION A-A

*Match Exist. Slope Wall Elevation, typ.

SECTION B-B

*Match Exist. Slope Wall Elevation, typ.




SECTION C-C

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	18.1
Slope Wall 4 Inch	Sq. Yd.	119

LEGEND



NOTE:

Slope wall shall be reinforced with welded wire fabric, 6 in. x 6 in. - W4.0 x W4.0, weighing 58 lbs. per 100 sq. ft.



DESIGNED - DJM	REVISED
CHECKED - VPT	REVISED
DRAWN - DJM	REVISED
CHECKED - VPT	REVISED
DATE - 09/12/2024	


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SLOPE WALL MODIFICATION DETAILS
STRUCTURE NO. 082-0344

SHEET NO. 9 OF 9 SHEETS



F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	477
CONTRACT NO. 76K74				ILLINOIS

No Salvage.



PROPOSED CURVE DATA RAMP A

$\Delta = 23^{\circ}13'53''$ (LT)
 $D = 07^{\circ}53'31''$
 $R = 726.00'$
 $T = 149.23'$
 $L = 294.37'$
 $E = 15.18'$
 $e = 6.10\%$
 P.C. Sta. = 17+39.93
 P.I. Sta. = 18+89.16
 P.T. Sta. = 20+34.29




Vincent P. Tabor
09/12/2024

Vincent P. Tabor
Licensed Structural Engineer
State of Illinois No. 081-007047
Expires 11/30/2024

Date

SECTION A-A




DESIGN SPECIFICATIONS

2020 AASHTO LRFD Bridge
Design Specifications,
Customary U.S. Units, 9th Edition

DESIGN STRESSES

FIELD UNITS:
 $f'c = 5,000$ psi (14-day)
 $f_y = 60,000$ psi (Reinforcement)
 $f_y = 65,000$ psi (Welded Wire Fabric)

LOCATION SKETCH

I-64 RAMP A
F.A.I. RTE. 64 - SEC. 82-7WRS-2
ST. CLAIR COUNTY
STATION 18+08.12

<u>INDEX OF SHEETS</u>	
<u>SHEET NO.</u>	<u>TITLE</u>
1	GENERAL PLAN AND ELEVATION
2	GENERAL DATA AND MISCELLANEOUS DETAILS
3	CULVERT REMOVAL DETAILS
4-5	CULVERT END SECTION DETAILS

	DESIGNED - DJM	REVISED
	CHECKED - VPT	REVISED
	DRAWN - DJM	REVISED
DATE - 09/12/2024	CHECKED - VPT	REVISED


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	478
		CONTRACT NO. 76K74		
ILLINOIS				

TOTAL BILL OF MATERIAL


ITEM	UNIT	TOTAL
Porous Granular Embankment	Cu. Yd.	61
Stone Riprap, Class A4	Sq. Yd.	208
Filter Fabric	Sq. Yd.	208
Concrete Removal	Cu. Yd.	24.3
Pipe Culvert Removal	Foot	32
Temporary Soil Retention System	Sq. Ft.	841
Cast-In-Place Reinforced Concrete End Sections 78"	Each	2
Pipe Culverts, Class C, Type 2 78"	Foot	75

GENERAL NOTES:

- 1.) Cast-in-place concrete exposed edges shall be beveled 3/4 in.
- 2.) Structural seal is for cast-in-place portion of structure only.
- 3.) Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
- 4.) The Contractor may request copies of existing construction plans that are currently on file with the Department. The request shall be in writing with the understanding that any reproduction cost will be at the Contractor's expense at no additional cost to the Department.
- 5.) Cast-in-Place Reinforced Concrete End Sections shall be constructed according to the requirements of Section 542 of the Standard Specifications except as modified herein. End sections will be paid for at the contract unit price per each for Cast-in-Place Reinforced Concrete End Sections. Cost of end sections shall include all labor, materials, tools, equipment, and other incidentals necessary that are not otherwise indicated to be paid for separately in these Plans.
- 6.) Shop drawings that detail slab thickness and reinforcement layout for the Cast-in-Place Reinforced Concrete End Sections shall be provided to the Engineer for review and approval. Reinforcement not detailed herein shall be detailed with a clear distance at the end of the reinforcement not less than 1/2" nor more than 2".
- 7.) The Contractor may use reinforcement bars in lieu of welded wire reinforcement (WWR). Reinforcement bars shall be limited to the sizes of #3 through #5 bars, a maximum spacing of the lesser of 8" or the member thickness, and shall result in an area of reinforcement equal to or greater than that provided by the WWR. Minimum lap lengths detailed herein are applicable to WWR and reinforcement bars.
- 8.) Channel excavation, earth excavation, and structure excavation will not be paid for separately; but shall be included in the cost of Stone Riprap, Class A4. See the Special Provision for Channel Excavation.
- 9.) Proposed 78" ø Reinforced Concrete Pipe (RCP) ends shall mate with the existing 78" ø RCP ends that will remain, so as to provide a bell to spigot connection.



SECTION THROUGH WINGWALL



TEMPORARY SOIL RETENTION SYSTEM

(Upstream end looking South, downstream end similar)

A cantilevered sheet piling design does not appear feasible and additional members or other retention systems may be necessary. The Contractor shall submit a temporary soil retention system design including plan details and calculations for review and acceptance by the Engineer.

*Bottom of excavation elevations allow for ±2'-0" additional overexcavation below the bottom of the existing pipe culvert. Depth of any required overexcavation shall be determined in the field at the time of construction.




	DESIGNED - DJM	REVISED
	CHECKED - VPT	REVISED
	DRAWN - DJM	REVISED
DATE - 09/12/2024	CHECKED - VPT	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL DATA AND MISCELLANEOUS DETAILS

SHEET NO. 2 OF 5 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	479
CONTRACT NO. 76K74				ILLINOIS



REMOVAL PLAN

LEGEND




Concrete Removal



Pipe Culvert Removal

BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	24.3
Pipe Culvert Removal	Foot	32



SECTION A-A

NOTE:

*Remove existing 78" ø Reinforced Concrete Pipe (RCP) from the first joint to the end of the pipe. Verify length of pipe segment in the field.




	DESIGNED - DJM	REVISED
	CHECKED - VPT	REVISED
	DRAWN - DJM	REVISED
DATE - 09/12/2024	CHECKED - VPT	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


CULVERT REMOVAL DETAILS

SHEET NO. 3 OF 5 SHEETS


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	480
CONTRACT NO. 76K74				ILLINOIS




SECTION B-B



SECTION D-D



SECTION C-C




SECTION E-E


TWO END SECTIONS BILL OF MATERIAL

(For information only)


Bar	No.	Size	Length	Shape
h	4	#7	20'-0"	—
h1	40	#5	2'-8"	—
h2	40	#5	4'-0"	└
h3	32	#5	17'-3"	└
h4	96	#5	5'-9"	—
h5	8	#5	19'-0"	—
s	40	#4	5'-3"	□
v	16	#5	9'-5"	—
ITEM			UNIT	TOTAL
Welded Wire Reinforcement			Sq. Yd.	189
Concrete Structures			Cu. Yd.	40.2
Reinforcement Bars			Pound	2,050



BAR h2



BAR h3




BAR s

NOTES:

- 1.) F.F. denotes Front Face and B.F. denotes Back Face.
- 2.) See Sheet 4 of 5 for locations of Sections B-B, C-C, D-D, and E-E.

POINT	A	B	C	D	E	F		
STATION	LEFT (W.B.) SHOULDER ELEVATION	TOP OF BARRIER ELEVATION	RIGHT (E.B.) SHOULDER ELEVATION	RIGHT (E.B.) SHOULDER BREAK ELEVATION	TOP OF FOOTING ELEVATION	TOP OF FOOTING ELEVATION AT BREAK	LEFT (W.B.) HEIGHT (FT)	RIGHT (E.B.) HEIGHT (FT)
733+75.00	551.49	555.16	548.68	549.06	548.33	548.71	3.67	6.83
734+00.00	551.58	555.25	548.54	548.88	548.19	548.53	3.67	7.06
734+03.81	551.69	555.36	548.62	548.85	548.27	548.49	3.67	7.09
734+26.91	551.55	555.21	548.39	548.65	548.04	548.30	3.67	7.18
734+50.00	551.40	555.07	548.27	548.52	547.92	548.17	3.67	7.15
734+75.00	551.30	554.96	548.13	548.39	547.78	548.03	3.67	7.19
735+00.00	551.19	554.86	547.99	548.25	547.64	547.90	3.67	7.22
735+25.00	551.06	554.73	547.85	548.10	547.49	547.74	3.67	7.24
735+50.00	550.93	554.60	547.70	547.94	547.35	547.59	3.67	7.25
735+75.00	550.80	554.47	547.56	547.80	547.20	547.44	3.67	7.27
736+00.00	550.67	554.34	547.41	547.65	547.06	547.30	3.67	7.28
736+25.00	550.54	554.21	547.27	547.51	546.92	547.16	3.67	7.29
736+50.00	550.41	554.08	547.13	547.37	546.78	547.02	3.67	7.30
736+75.00	550.25	553.91	547.02	547.25	546.66	546.90	3.67	7.25
737+00.00	550.08	553.75	546.90	547.13	546.55	546.78	3.67	7.20
737+25.00	549.92	553.58	546.78	547.01	546.42	546.65	3.67	7.16
737+50.00	549.75	553.42	546.65	546.88	546.30	546.53	3.67	7.12
737+75.00	549.58	553.25	546.49	546.72	546.13	546.36	3.67	7.12
738+00.00	549.41	553.08	546.32	546.55	545.97	546.20	3.67	7.11
738+25.00	549.25	552.91	546.16	546.39	545.81	546.04	3.67	7.11
738+50.00	549.08	552.75	546.00	546.23	545.65	545.88	3.67	7.10
738+75.00	548.92	552.58	545.84	546.07	545.48	545.72	3.67	7.10
739+00.00	548.75	552.42	545.67	545.91	545.32	545.56	3.67	7.10
739+25.00	548.60	552.26	545.51	545.75	545.16	545.40	3.67	7.11
739+50.00	548.44	552.11	545.35	545.59	545.00	545.24	3.67	7.11
739+75.00	548.27	551.94	545.20	545.44	544.85	545.08	3.67	7.09
740+00.00	548.10	551.77	545.05	545.28	544.70	544.93	3.67	7.07
740+25.00	547.94	551.60	544.87	545.10	544.52	544.75	3.67	7.09
740+50.00	547.77	551.44	544.69	544.92	544.34	544.57	3.67	7.10

Note: See Typical Section on Sheet 1 of 2 for locations of elevations A thru F.



REINFORCEMENT AROUND DRAINAGE STRUCTURES

POINT	A	B	C	D	E	F		
STATION	LEFT (W.B.) SHOULDER ELEVATION	TOP OF BARRIER ELEVATION	RIGHT (E.B.) SHOULDER ELEVATION	RIGHT (E.B.) SHOULDER BREAK ELEVATION	TOP OF FOOTING ELEVATION	TOP OF FOOTING ELEVATION AT BREAK	LEFT (W.B.) HEIGHT (FT)	RIGHT (E.B.) HEIGHT (FT)
740+75.00	547.61	551.27	544.52	544.75	544.16	544.40	3.67	7.11
741+00.00	547.44	551.11	544.34	544.58	543.99	544.23	3.67	7.12
741+25.00	547.31	550.97	544.20	544.44	543.84	544.08	3.67	7.13
741+50.00	547.17	550.84	544.05	544.29	543.70	543.94	3.67	7.14
741+75.00	547.04	550.70	543.90	544.13	543.54	543.78	3.67	7.16
742+00.00	546.90	550.57	543.74	543.97	543.39	543.62	3.67	7.18
742+25.00	546.75	550.41	543.60	543.83	543.25	543.48	3.67	7.17
742+50.00	546.59	550.26	543.46	543.69	543.11	543.34	3.67	7.15
742+75.00	546.43	550.10	543.30	543.53	542.95	543.18	3.67	7.15
743+00.00	546.27	549.94	543.14	543.37	542.79	543.02	3.67	7.15
743+25.00	546.12	549.78	542.99	543.21	542.63	542.86	3.67	7.15
743+50.00	545.96	549.63	542.83	543.05	542.48	542.70	3.67	7.15
743+75.00	545.80	549.47	542.68	542.90	542.32	542.55	3.67	7.15
744+00.00	545.64	549.31	542.52	542.75	542.17	542.40	3.67	7.14
744+15.00	545.56	549.23	542.40	542.66	542.05	542.31	3.67	7.18
744+32.50	545.40	549.07	542.29	542.55	541.93	542.19	3.67	7.14
744+50.00	545.24	548.91	542.17	542.43	541.82	542.08	3.67	7.09
744+75.00	545.05	548.72	542.01	542.27	541.65	541.91	3.67	7.07
745+00.00	544.86	548.53	541.84	542.10	541.49	541.75	3.67	7.04
745+25.00	544.65	548.32	541.68	541.94	541.32	541.58	3.67	7.00
745+50.00	544.44	548.11	541.51	541.77	541.16	541.42	3.67	6.95
745+75.00	544.20	547.87	541.34	541.60	540.99	541.25	3.67	6.88
752+75.00	542.23	545.90	539.25	539.51	538.89	539.15	3.67	7.01
753+00.00	542.34	546.01	539.26	539.52	538.91	539.17	3.67	7.10
753+25.00	542.46	546.12	539.40	539.66	539.04	539.30	3.67	7.08
753+50.00	542.57	546.24	539.53	539.79	539.18	539.44	3.67	7.06
753+75.00	542.66	546.33	539.68	539.94	539.33	539.59	3.67	7.00

Note: See Typical Section on Sheet 1 of 2 for locations of elevations A thru F.

DIFFERENTIAL HEIGHT MEDIAN
BARRIER BILL OF MATERIAL
(For Information Only)

Bar	No.	Size	Length	Shape
d(E)	2,600	#4	8'-1"	
d1(E)	2,600	#4	5'-2"	
d2(E)	2,600	#4	6'-1"	
d3(E)	2,600	#4	7'-1"	
e(E)	994	#4	31'-10"	
t(E)	5,304	#6	15'-8"	
t1(E)	208	#5	5'-0"	
w(E)	1,573	#5	32'-4"	
Item			Unit	Quantity
Concrete Structures (Retaining Wall)			Cu. Yd.	1,941
Reinforcement Bars, Epoxy Coated			Pound	245,970
Protective Coat			Sq. Yd.	1,789
Pipe Underdrains for Structures 4"			Foot	1,300




	DESIGNED - DJM	REVISED
	CHECKED - VPT	REVISED
	DRAWN - DJM	REVISED
DATE - 09/12/2024	CHECKED - VPT	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DIFFERENTIAL HEIGHT MEDIAN BARRIER DETAILS

SHEET NO. 2 OF 2 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	484
			CONTRACT NO. 76K74	
		ILLINOIS		




1. ALL CONNECTIONS BETWEEN SENSORS AND LEAD CABLES ARE DONE IN HANDHOLE AND ARE SOLDERED THEN SEALED FOR WATERPROOFING. NUMBER AND PLACEMENT OF HANDHOLES NOT SHOWN.
2. POWER CABLES MUST BE RUN IN SEPARATE CONDUITS / HANDHOLES FROM SIGNAL CABLES.
3. SENSOR SPACING SHOWN IS TYPICAL SPACING REQUIREMENT. ACTUAL SENSOR SPACING MAY BE ALTERED TO SUIT SITE CONDITIONS BY THE MFR FIELD REPRESENTATIVE.
4. SITE CONDITIONS MUST MEET CURRENT ASTM E1318 REQUIREMENTS TO ACHIEVE OPTIMAL WIM SYSTEM PERFORMANCE.
5. CABLES MUST BE PROTECTED BY PVC SLEEVES WHERE THEY CROSS PAVEMENT JOINTS/CRACKS.
6. ADDITIONAL DRAINAGE MAY BE REQUIRED DEPENDING ON SLOPE OF ROADWAY. DRAINAGE CONSISTS OF 1-1/2" ABS PIPE SLOPED TO RIP RAP DRAINAGE PIT IN DITCH.
7. TEMPERATURE SENSOR MUST BE INSTALLED AS SHOWN IN DRAWING.
8. MFR RECOMMENDS THAT HANDHOLES BE NO FURTHER THAN 200' APART. MFR RECOMMENDS THE MINIMUM SIZE FOR HANDHOLES IS 18" X 18" X 12".
9. SEPARATE CONDUITS AND HANDHOLES MUST BE USED FOR AC POWER AND LOW VOLTAGE SIGNAL / FIBER OPTIC CABLES.
10. EXACT ROUTING OF CONDUIT TO BE DETERMINED ON SITE. CONDUITS ARE LABELED LEFT TO RIGHT, TOP TO BOTTOM.
11. SENSORS SHALL BE PLACED ON THE FINAL BITUMINOUS SURFACE LIFT.
12. SENSORS SHALL ONLY BE PLACED IN THE DRIVING LANES (LANE 1)
13. THE CONTRACTOR SHALL ADHERE TO BDE SPEC SURFACE TESTING OF PAVEMENTS-IRI FOR 200' ON EACH SIDE OF THE WIM SENSORS.
14. DRAWING NOT TO SCALE.
15. THE PROPOSED WEIGH IN MOTION LOOPS SHALL BE INSTALLED AT APPROXIMATELY THE SAME LOCATION AS EXISTING, AS DETERMINED BY THE ENGINEER.

- A** CABINET WITH WIM ELECTRONICS.
- B** CABINET BASE.
- C** PAVEMENT ON EITHER SIDE OF EACH SENSOR MUST BE FREE OF JOINTS AND CRACKS FOR 2'.
- D** CONDUIT SHALL BE PLACED USING BORING, JACKING OR ALTERNATIVE METHOD THAT DOES NOT REQUIRE THE SURFACE OF THE ROAD TO BE CUT.


L - INDUCTIVE LOOP
Q - LINEAS * QUARTZ WIM SENSOR BY KISTLER
T - TEMPERATURE SENSOR

MODEL: detail0 (Sheet)
FILE NAME: 3032020200688.10 - DDT D&PTB 106 Item 561-64 Widening04 Drawings\GN\CAD_Sheets\7-2 Weigh In Motion\DT76K74-WeighInMotion.dgn


CABLE ROUTING DETAILS




OCTAGONAL LOOP DIMENSION DETAIL




SQUARE LOOP DIMENSION DETAIL




SECTION A-A



SECTION B-B



DETAIL A



NOTES:






- 1 LOOP SIZE AS SPECIFIED ON SITE LAYOUT.
- 2 NUMBER OF TURNS AS SPECIFIED ON SITE LAYOUT.
- 3 USE CAULKING GUN PER MANUFACTURER'S SPECIFICATIONS
- 4 LOOP INSTALLATION PER MANUFACTURER'S MANUALS - PERMANENT OCTAGON LOOPS
- 5 IF THE LOOP IS INSTALLED OVER REBAR, THERE MUST BE A MINIMUM OF 2 INCHES OF CONCRETE BELOW AND A MINIMUM OF 1 INCH OF FILL ABOVE THE WIRES.
- 6 CORE DRILL OR CUT NOTCH IN PAVED SHOULDER FOR SWEEP. PLUG SWEEP OPENING, COVER WITH LOOP SEALANT.
- 7 NON-METALLIC FLEX OR PVC CONDUIT.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WEIGH IN MOTION
DETAIL

SCALE: N.T.S. SHEET 2 OF 4 SHEETS STA. ____+____ TO STA. ____+____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	486
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				




1. FOR INSTALLATION PROCESS REFER TO MANUFACTURERS INSTALLATION MANUAL.
2. SLOT LENGTH IS 6 [152] LONGER THAN SENSOR.
3. SET SENSOR FLUSH WITH OR SLIGHTLY HIGHER THAN ROAD SURFACE USING INCLUDED LEVELING BEAMS.
4. CHECK THE RESISTANCE OF THE SENSOR BY PLACING A DIGITAL MULTIMETER ACROSS THE CENTER CONDUCTOR OF THE BNC CONNECTOR AND THE OUTER BODY. THE READING SHOULD BE INFINITY.
5. CHECK THE VOLTAGE OUTPUT OF THE SENSOR BY MONITORING THE METER WHEN A TRUCK PASSES OVER THE SENSOR INSTALLED IN THE ROADWAY. AS THE TRUCK PASSES OVER THE SENSOR, VOLTAGE DEFLECTION SHOULD BE OBSERVED.
6. CRACKS OR SAW CUTS IN THE ROADWAY MUST NOT BE LOCATED CLOSER THAN 18 [450] UPSTREAM AND 18 [450] DOWNSTREAM OF THE SENSOR.
7. SENSOR MUST BE GROUND FLUSH WITH ROAD SURFACE AFTER GROUT HAS CURED.
8. IF SIGNIFICANT NOISE SOURCES ARE IDENTIFIED, OVERHEAD POWER SOURCES ETC., CONNECT OPTIONAL GROUND WIRE AS PER 690359 SECTION 4.5. OTHER END OF GROUND WIRE CONNECTS TO CABINET GROUND BUSBAR.
9. CORE DRILL OR CUT NOTCH IN PAVED SHOULDER FOR SWEEP. PLUG SWEEP OPENING, COVER WITH LOOP SEALANT.

MODEL: Detail 3 (Sheet)
FILE NAME: 30202020698.10 - DDT D&PTB 106 Rev 56 454 Widening04 Drawings\GNCA\CD_Sheets\7-2 Weigh In Motion\DWG76K74-HighWeightMotion.dgn


	USER NAME = rstakey		DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WEIGH IN MOTION DETAIL			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN -		REVIS	REVIS					64	82-7WRS-2	ST. CLAIR	691	487
	PLOT SCALE = 0.16666633" / in.		CHECKED -	REVIS		SCALE: N.T.S.			CONTRACT NO. 76K74				
	PLOT DATE = 8/27/2024		DATE -	REVIS		SHEET 3	OF 4 SHEETS	STA. ____+____ TO STA. ____+____	ILLINOIS FED. AID PROJECT				

INSTALLATION DETAILS - IN ROAD TEMPERATURE SENSOR


PLAN VIEW - SENSOR INSTALLATION




CABLE ROUTING DETAILS




SENSOR P/N 170471
SECTION A-A




SENSOR P/N 170695-XX
SECTION A-A




SECTION B-B



SECTION B-B



SECTION C-C




- 1 CRACKS OR SAW CUTS IN THE ROADWAY MUST NOT BE LOCATED CLOSER THAN 18" UPSTREAM AND 18" DOWNSTREAM OF THE TEMPERATURE SENSOR.
- 2 SLOT LENGTH IS 4" LONGER THAN SENSOR.
- 3 SET THE SENSOR AT THE CORRECT DEPTH.
- 4 PLACE A BRACKET AT EACH END OF THE SENSOR,
- 5 LOCATE SENSOR IN SAME PAVEMENT AND WITHIN 6" OF THE TEMPERATURE COMPENSATED DEVICE. AVOID PLACING IN WHEEL PATH.
- 6 WEDGE SENSOR AGAINST FLOOR OF CUT UNDER "W" CLIP (P/N 480275).
- 7 SPACE THREE BRACKETS (P/N 480275) EVENLY OVER THE LENGTH OF THE SENSOR.
- 8 USE GROUT OF SAME TYPE AS THAT OF SENSOR BEING COMPENSATED:
PIEZO - USE AS475 (340028) OR PU200 (IT2000285)
KISTLER - USE KISTLER GROUT (340139) OR FLEXOLITH (340082)
- 9 CORE DRILL OR CUT NOTCH IN PAVED SHOULDER FOR SWEEP. PLUG SWEEP OPENING, COVER WITH LOOP SEALANT.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


WEIGH IN MOTION
DETAIL

SCALE: N.T.S. SHEET 4 OF 4 SHEETS STA. ____+____ TO STA. ____+____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST. CLAIR	691	488
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				




NOTE:
CONCRETE BARRIER TRANSITION BASE TO BE
PAID FOR AS CONCRETE BARRIER BASE PAY ITEM.



SECTION A-A

PLAN VIEW

20' TRANSITION



SECTION B-B

CONCRETE BARRIER TRANSITION FROM
CONCRETE BARRIER WALL (SPECIAL) TO EXISTING CONCRETE BARRIER

(N.T.S.)

MODEL: Details: 1 (1-24)
FILE NAME: J:\2020\20200608.10 - IDOT DB&PTB 196 Item 56.544 Widening\04 Drawings\DWG\CAD Sheets\20 Misc Details\0876K74-shcdetail 01-MedianBarrierTransition STA 744+15.dgn




USER NAME	= rstaley	DESIGNED	- RWS	REVISED	-
DRAWN	- RWS	REVISION	-	REVISION	-
PLOT SCALE	= 0.16666633 1/ in.	CHECKED	- ERB	REVISION	-
PLOT DATE	= 10/15/2024	DATE	- 10/15/24	REVISION	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 64 (I-64) MISCELLANEOUS DETAILS			
SCALE:	N.T.S.	SHEET	1 OF 2 SHEETS
STA.	___+___	TO STA.	___+___


F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	489
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				




NOTE:
CONCRETE BARRIER TRANSITION BASE TO BE
PAID FOR AS CONCRETE BARRIER BASE PAY ITEM.

PLAN VIEW


20' TRANSITION



SECTION A-A



SECTION B-B



SECTION C-C

**CONCRETE BARRIER TRANSITION FROM
DOUBLE FACE 44 INCH HEIGHT TO DOUBLE FACE 42 INCH HEIGHT**

(N.T.S.)

MODEL: Details: 1 (1-16-21)
FILE NAME: J:\2020\20200608.10 - IDOT DB&PTB 196 Item 56.544 Widening\04 Drawings\DWG\CAD Sheets\20 Misc Details\076K74-shp-detail 02-MedianBarrierTransition STA 855+34.dgn




USER NAME	= rstaley	DESIGNED -	RWS	REVISED -	
DRAWN -	RWS	REVISED -			
PLOT SCALE	= 0.16666633 1/1 in.	CHECKED -	ERB	REVISED -	
PLOT DATE	= 10/15/2024	DATE -	10/15/24	REVISED -	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**


F.A.I. ROUTE 64 (I-64) MISCELLANEOUS DETAILS					
SCALE: N.T.S.	SHEET 2	OF 2	SHEETS	STA. 726+72.10	TO STA. 868+92.73

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	490
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



DRAINAGE STRUCTURE, TYPE 5 (SPECIAL)
SECTION A-A

STA. - 750+39.00
STA. - 750+49.00



DRAINAGE STRUCTURE, TYPE 5 (SPECIAL)
PLAN

MODEL: Detail - 15 (Sheet)
FILE NAME: J:\2020\2020068.10 - IDOT DB&PTB 196 Item 56.644 Widening\04 Drawings\DWG\CAD Sheets\20 Misc Details\0876K74-shp-detail 03-DrainageStructures\TA750-39.dgn




USER NAME	= rstaley	DESIGNED -	WLB	REVISED -	
		DRAWN -	WLB	REVISED -	
PLOT SCALE	= 0.16666633 1/ in.	CHECKED -	ERB	REVISED -	
PLOT DATE	= 10/15/2024	DATE -	10/15/24	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


F.A.I ROUTE 64 (I-64)
MISCELLANEOUS DETAILS

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. 726+72.10 TO STA. 868+92.73


F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	491
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				




PLAN VIEW



PIPE UNDERDRAIN DETAIL
(USE WHEN PGL IS LESS THAN 0.4%)




SECTION A-A



SECTION C-C

APPROXIMATE OUTLET PROTECTOR QUANTITIES FOR EACH OUTLET PROTECTOR	
CONCRETE, CLASS SI	1.5 CU YD
REINFORCING STEEL	35.6 LB



- NOTES**
- SEE STANDARD 601101 FOR DETAILS OF RODENT SHIELDS.
 - THE OUTLET PIPE OR PIPES SHALL BE LOCATED AS CLOSE AS POSSIBLE TO THE CENTER OF THE OUTLET PROTECTOR.
 - THE LAST 10 FEET OF OUTLET PIPE SHALL BE SCHEDULE 40 PVC.
 - REINFORCEMENT BARS MAY BE CUT OR RELOCATED TO ACCOMMODATE PIPE.
 - CUT OUTLET PIPE ON A BEVE TO MATCH FINISHED SURFACE OF SURROUNDING PCC.
 - SEEDING CLASS 2 SHALL BE CONSIDERED INCLUDED IN THE COST OF THE PAY ITEMS.

CONCRETE HEADWALL SPECIAL

DETAILS
OUTLET PROTECTOR

MODEL: Detail - 16 (Sheet)
FILE NAME: J:\2020\20200608.10 - IDOT DB&PTB 196 Item 56.544 Widening\04 Drawings\DWG\CAD Sheets\20 Misc Details\076K74-shc-detail 05-Concrete Headwall Special.dgn




USER NAME = rstaley	DESIGNED - WLB	REVISED -
	DRAWN - WLB	REVISED -
PLOT SCALE = 0.16666633 1/16 in.	CHECKED - ERB	REVISED -
PLOT DATE = 10/15/2024	DATE - 10/15/24	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


F.A.I ROUTE 64 (I-64)
MISCELLANEOUS DETAILS

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. 726+72.10 TO STA. 868+92.73


F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	492
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				



JACK AND BORE PIPE CROSSING PLAN




SPACING DETAIL



SECTION A-A

ENCASEMENT SPACER DETAILS
FOR RCP IRON PIPE



SECTION B-B

JACK AND BORE PIPE CROSSING SECTION

MODEL: Detail: 1 (1-64)
FILE NAME: J:\2020\06068.10 - IDOT DB&PB 196 Item 56.44 Widening\04 Drawings\DWG\CAD Sheets\20 Misc Details\076K74-shcdetail 04-Jack and Bore Detail.dgn




USER NAME	= rstaley	DESIGNED -	RWS	REVISED -	
		DRAWN -	RWS	REVISED -	
PLOT SCALE	= 0.16666633 1/16 in.	CHECKED -	ERB	REVISED -	
PLOT DATE	= 10/15/2024	DATE -	10/15/24	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


F.A.I. ROUTE 64 (I-64)
MISCELLANEOUS DETAILS

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. ____+____ TO STA. ____+____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	493
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				




**ALUMINUM CAP DESIGN DETAIL
FOR RIGHT-OF-WAY AND
PERMANENT EASEMENT CORNERS**





TYPICAL UNDERDRAIN HEADWALL MARKER DETAIL

NOTE:
PROVIDE WHITE TRIANGLE IN SHOULDER TO MARK LOCATION OF EACH UNDERDRAIN OUTLET PIPE. TRIANGULAR PAVEMENT MARKINGS SHALL BE PAID FOR AS PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LETTERS AND SYMBOLS. SEE SCHEDULE OF QUANTITIES FOR LOCATIONS OF UNDERDRAIN OUTLETS.



CONCRETE COLLAR DETAIL



CONCRETE CURB AND GUTTER OUTLET
N.T.S.



USER NAME	= rstaley	DESIGNED -	WLB	REVISED -	
DRAWN	-	WLB		REVISED -	
PLOT SCALE	= 0.16666633 1/ in.	CHECKED -	ERB	REVISED -	
PLOT DATE	= 10/15/2024	DATE	-	10/15/24	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**F.A.I ROUTE 64 (I-64)
MISCELLANEOUS DETAILS**


SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. ____+____ TO STA. ____+____

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	494
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

MODEL: Detail- 16 (Sheet)
FILE NAME: J:\2020\20200698.10 - IDOT DB&PTB 196 Item 56.644 Widening\04_Drawings\IGN\CAD_Sheets\20 Misc Details\0676K74-shcd-detail 06-ROW Aluminum Cap.dgn


SLOPE STEPS BENCHING DETAIL

TYPICAL CROSS SECTION EMBANKMENT
AND FURNISHED EXCAVATION CONSTRUCTION
ON SIDEHILL OR SLOPE



- GENERAL NOTES:
- SLOPE STEPS WILL BE REQUIRED FOR ALL 12" MINIMUM THICKNESS "SLIVER FILLS" AND ON ALL FILLS WITH A HEIGHT OF 10 FEET OR GREATER.
 - THE STEP WIDTH SHALL BE TYPICALLY TWICE THE STEP DEPTH.
 - ALL WORK DUE TO EXCAVATION OF SLOPE STEPS, EMBANKMENT WITHIN SLOPE STEPS, AND ADDITIONAL EXCAVATION FOR BENCHING SHALL NOT BE MEASURED AND PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

REPLACEMENT MATERIAL:

 SEE NOTE #3 ON THIS SHEET.

MODEL: Detail- 16 (Sheet)
FILE NAME: J:\2020\2020068.10 - IDOT DB&PTB 196 Item 56.644 Widening\04 Drawings\DWG\CAD Sheets\20 Misc Details\0876K74-shd-detail 08-Slope Steps Benching.dgn



USER NAME	= rstaley	DESIGNED -	RWS	REVISED -	
		DRAWN -	RWS	REVISED -	
PLOT SCALE	= 0.16666633 ' / in.	CHECKED -	ERB	REVISED -	
PLOT DATE	= 10/15/2024	DATE -	10/15/24	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


F.A.I ROUTE 64 (I-64)
MISCELLANEOUS DETAILS

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. 726+72.10 TO STA. 868+92.73

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	495
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

ORIGINAL SURVEY	SURVEYED _____	BY _____	DATE _____
NOTE BOOK	PLOTTED _____		
	TEMPLATE _____		
	AREAS _____		
NO.	AREAS CHECKED _____		




MODEL: 164WEST - 726+50.00



FINAL SURVEY	DATE
	BY
	SURVEYED
	PLOTTED
	TEMPLATE
NOTE BOOK	AREAS
	CHECKED
NO.	

ORIGINAL SURVEY	DATE
	BY
	SURVEYED
	PLOTTED
	TEMPLATE
NOTE BOOK	AREAS
	CHECKED
NO.	

MODEL: I64WEST - 727+50.00
FILE NAME: C:\Users\jmain\OneDrive - Farnsworth Group\Working Project Files\64\IGND876K7\64sho\64 West-1.dgn



USER NAME = jmain	DESIGNED - JJO	REVISED -
	DRAWN - JRM	REVISED -
PLOT SCALE = 0.16666633" / in.	CHECKED - ERB	REVISED -
PLOT DATE = 10/16/2024	DATE - 10/15/2024	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 64 (I-64)
CROSS SECTIONS




SCALE: 1:10H / 1:5V SHEET 2 OF 151 SHEETS STA. 727+50.00 TO STA. 728+50.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	497
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

DATE	BY	SURVEYED	PLOTTED	TEMPLATE	AREAS	CHECKED
NO.		FINAL	SURVEY	NOTE BOOK		

DATE	BY	SURVEYED	PLOTTED	TEMPLATE	AREAS	CHECKED
NO.		ORIGINAL	SURVEY	NOTE BOOK		

MODEL: 164WEST - 729+00.00
FILE NAME: C:\Users\jmain\OneDrive - Farnsworth Group\164\Working Project Files\164\GND\876K7\164sbs\164 West-1.dgn



USER NAME = jmain	DESIGNED - JJO	REVISED -
	DRAWN - JRM	REVISED -
PLOT SCALE = 0.16666633" / 1.	CHECKED - ERB	REVISED -
PLOT DATE = 10/16/2024	DATE - 10/15/2024	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 64 (I-64)
CROSS SECTIONS


SCALE: 1:10H / 1:5V SHEET 3 OF 151 SHEETS STA. 729+00.00 TO STA. 729+50.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	498
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				


FINAL SURVEY	BY	DATE	SURVEYED	PLOTTER	TEMPLATE	AREAS CHECKED
NO.	NOTE BOOK	NO.	NO.	NO.	NO.	NO.

ORIGINAL SURVEY	BY	DATE	SURVEYED	PLOTTER	TEMPLATE	AREAS CHECKED
NO.	NOTE BOOK	NO.	NO.	NO.	NO.	NO.


MODEL: I64WEST - 730+00.00
FILE NAME: C:\Users\jmarin\OneDrive - Farnsworth Group\In\Drawings\Working Project Files\I64\GND876K7\I64West\I64West.dgn



STA 731+00.00



STA 730+50.00



STA 730+00.00



USER NAME = jmarin	DESIGNED - JJO	REVISED -
PLOT SCALE = 0.16666633' / in.	DRAWN - JRM	REVISED -
PLOT DATE = 10/16/2024	CHECKED - ERB	REVISED -
	DATE - 10/15/2024	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 64 (I-64)
CROSS SECTIONS

SCALE: 1:10H / 1:5V SHEET 4 OF 151 SHEETS STA. 730+00.00 TO STA. 731+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-7WRS-2	ST CLAIR	691	499
CONTRACT NO. 76K74				
ILLINOIS FED. AID PROJECT				

FINAL	DATE
SURVEY	BY
NOTED	
PLOTTED	
TEMPLATE	
AREAS	
CHECKED	
NO.	

ORIGINAL	DATE
SURVEY	BY
NOTED	
PLOTTED	
TEMPLATE	
AREAS	
CHECKED	
NO.	

MODEL: I64WEST - 731+50.00
FILE NAME: C:\Users\jmain\OneDrive - Farnsworth Group\InDesktop\Working Project Files\I64\GND876K7\I64h3x06 West-1.dgn

