

				CONSTRUCTION CODE	
				90% FED 10% STATE	90% FED 10% STATE
				ROADWAY	LIGHTING
				0004	0021
CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
X1400190	REMOVAL OF HIGH MAST LUMINAIRES, SALVAGE	EACH	54	-	54
X1400341	REMOVAL OF LUMINAIRE, SALVAGE	EACH	91		91
X1400402	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200AMP (DUAL), RADIO SCADA, FIBER OPTIC	EACH	1	-	1
X2511630	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	2,103	2,103	-
X6700407	ENGINEER'S FIELD OFFICE, TYPE A (D1)	CAL MO	18	18	-
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
X8210007	LUMINAIRE, LED, ROADWAY, REPLACEMENT, OUTPUT DESIGNATION H	EACH	90	-	90
X8420111	REMOVAL OF UNDERPASS LIGHTING UNIT, NO SALVAGE	EACH	12	-	12
X8420502	REMOVAL OF LIGHT TOWER, NO SALVAGE	EACH	13	-	13
X8420510	REMOVAL OF TOWER FOUNDATION	EACH	13	-	13
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-
X7200061	TEMPORARY INFORMATION SIGNING	SQ FT	206	206	-
Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	128	-	128
X8000003	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	12	-	12

MODEL: Default
FILE NAME: J:\0225\0304_CADD\CADD_Sheet\0162W15-sh-iso-03.dgn



USER NAME = vnunez	DESIGNED - MG	REVISED -
	DRAWN - VN	REVISED -
PLOT SCALE = 2' / in.	CHECKED - RPYVG	REVISED -
PLOT DATE = 3/19/2025	DATE - 03/14/2025	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

 REVISED SHEET 6/2/2025

S00-03

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	FAI 80 23 LIGHTING	WILL	49	6
CONTRACT NO. 62W15				
ILLINOIS FED. AID PROJECT				