242

Letting June 13, 2025

Notice to Bidders, Specifications and Proposal



Contract No. 61K96 LAKE County Section 21-00020-00-RS (Riverwoods) Route FAU 2416 (Saunders Road) Project JFPC-674 () District 1 Construction Funds

F



NOTICE TO BIDDERS

- 1. TIME AND PLACE OF OPENING BIDS. Electronic bids are to be submitted to the electronic bidding system (iCX-Integrated Contractors Exchange). All bids must be submitted to the iCX system prior to 12:00 p.m. June 13, 2025 at which time the bids will be publicly opened from the iCX SecureVault.
- 2. DESCRIPTION OF WORK. The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

Contract No. 61K96 LAKE County Section 21-00020-00-RS (Riverwoods) Project JFPC-674 () Route FAU 2416 (Saunders Road) District 1 Construction Funds

HMA resurfacing and shoulder widening on Saunders Road from Duffy Lane to Riverwoods Road in Riverwoods.

- **3. INSTRUCTIONS TO BIDDERS.** (a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
 - (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to re-advertise the proposed improvement, and to waive technicalities.

By Order of the Illinois Department of Transportation

Gia Biagi, Acting Secretary

CONTRACT 61K96

INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

Adopted January 1, 2025

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS, frequently used RECURRING SPECIAL PROVISIONS, and LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction

(Adopted 1-1-22) (Revised 1-1-25)

SUPPLEMENTAL SPECIFICATIONS

Std. Spe	ec. Sec.	Page No.
202	Earth and Rock Excavation	1
204	Borrow and Furnished Excavation	
207	Porous Granular Embankment	3
211	Topsoil and Compost	
406	Hot-Mix Asphalt Binder and Surface Course	5
407	Hot-Mix Asphalt Pavement (Full-Depth)	
420	Portland Cement Concrete Pavement	8
502	Excavation for Structures	9
509	Metal Railings	10
540	Box Culverts	11
542	Pipe Culverts	31
550	Storm Sewers	
586	Granular Backfill for Structures	
630	Steel Plate Beam Guardrail	
632	Guardrail and Cable Road Guard Removal	49
644	High Tension Cable Median Barrier	
665	Woven Wire Fence	51
701	Work Zone Traffic Control and Protection	52
781	Raised Reflective Pavement Markers	
782	Reflectors	55
801	Electrical Requirements	
821	Roadway Luminaires	
1003	Fine Aggregates	
1004	Coarse Aggregates	
1010	Finely Divided Minerals	63
1020	Portland Cement Concrete	
1030	Hot-Mix Asphalt	
1040	Drain Pipe, Tile, and Wall Drain	
1061	Waterproofing Membrane System	
1067	Luminaire	
1097	Reflectors	
1102	Hot-Mix Asphalt Equipment	78

RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

CHEC	CK S⊢	IEET #	PAGE NO.
1	\boxtimes	Additional State Requirements for Federal-Aid Construction Contracts	79
2	\boxtimes	Subletting of Contracts (Federal-Aid Contracts)	82
3	\boxtimes	EEO	83
4		Specific EEO Responsibilities Non Federal-Aid Contracts	93
5		Required Provisions - State Contracts	
6		Asbestos Bearing Pad Removal	
7		Asbestos Waterproofing Membrane and Asbestos HMA Surface Removal	105
8		Temporary Stream Crossings and In-Stream Work Pads	
9	\boxtimes	Construction Layout Stakes	
10		Use of Geotextile Fabric for Railroad Crossing	
11		Subsealing of Concrete Pavements	112
12		Hot-Mix Asphalt Surface Correction	116
13	\boxtimes	Pavement and Shoulder Resurfacing	118
14		Patching with Hot-Mix Asphalt Overlay Removal	119
15		Polymer Concrete	
16		Reserved	123
17		Bicycle Racks	124
18		Temporary Portable Bridge Traffic Signals	126
19		Nighttime Inspection of Roadway Lighting	128
20		English Substitution of Metric Bolts	
21		Calcium Chloride Accelerator for Portland Cement Concrete	130
22		Quality Control of Concrete Mixtures at the Plant	131
23	\boxtimes	Quality Control/Quality Assurance of Concrete Mixtures	139
24		Reserved	155
25		Reserved	156
26		Temporary Raised Pavement Markers	157
27		Restoring Bridge Approach Pavements Using High-Density Foam	158
28		Portland Cement Concrete Inlay or Overlay	161
29		Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	165
30		Longitudinal Joint and Crack Patching	
31		Concrete Mix Design – Department Provided	170
32		Station Numbers in Pavements or Overlays	171

LOCAL ROADS AND STREETS RECURRING SPECIAL PROVISIONS

Table of Contents

<u>CHECK S</u>	HEET	<u> </u>	PAGE NO.
LRS 1		Reserved	173
LRS 2		Furnished Excavation	174
LRS 3	\boxtimes	Work Zone Traffic Control Surveillance	175
LRS 4		Flaggers in Work Zones	176
LRS 5		Contract Claims	177
LRS 6		Bidding Requirements and Conditions for Contract Proposals	178
LRS 7		Bidding Requirements and Conditions for Material Proposals	184
LRS 8		Reserved	190
LRS 9		Bituminous Surface Treatments	
LRS 10		Reserved	195
LRS 11		Employment Practices	
LRS 12		Wages of Employees on Public Works	198
LRS 13		Selection of Labor	
LRS 14		Paving Brick and Concrete Paver Pavements and Sidewalks	201
LRS 15		Partial Payments	204
LRS 16		Protests on Local Lettings	205
LRS 17		Substance Abuse Prevention Program	206
LRS 18		Multigrade Cold Mix Asphalt	207
LRS 19		Reflective Crack Control Treatment	208

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D1)	2
TRAFFIC CONTROL PLAN (D1)	2
PUBLIC CONVENIENCE AND SAFETY (D1)	3
STATUS OF UTILITIES (D1)	3
ADJUSTMENTS AND RECONSTRUCTIONS (D1)	8
AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS (D1)	9
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (D1)	10
FRICTION AGGREGATE (D1)	12
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	15
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1)	22
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	23
RECLAIMED ASPHALT PAVEMENT FOR NON-POROUS EMBANKMENT AND BACKFILL	. ,
TEMPORARY INFORMATION SIGNING	
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	25
CLEARING AND GRUBBING	26
DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED OR RECONSTRUCTED	26
DRAINAGE STRUCTURE TO BE REMOVED	27
EXPOSED AGGREGATE SURFACE	27
FIRE HYDRANTS TO BE ADJUSTED	28
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	28
HOT-MIX ASPHALT DRIVEWAY PAVEMENT	28
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	29
MAILBOX REMOVE AND REPLACE	29
PROTECTION OF EXISTING TREES	30

RAISED REFLECTIVE PAVEMENT MARKER	33
REMOVE AND REINSTALL BRICK PAVER	34
REMOVE AND RELOCATE SIGN PANEL	34
REMOVING AND RESETTING STREET SIGNS	35
STORM SEWERS, WATER MAIN QUALITY	35
STUMP REMOVAL	38
SUPPLEMENTAL WATERING	38
TIMBER RETAINING WALL REMOVAL	39
WATER VALVES TO BE ADJUSTED	40
AVAILABLE REPORTS (D1 LR)	40
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION .	41
LR107-4 INSURANCE	43
LR1030-2 LOCAL QUALITY ASSURANCE/QUALITY MANAGEMENT QC/QA	44
LPC-663 FORM	46
SWPPP	48
LCSMC PERMIT	56
USACE NATIONWIDE PERMIT 14 AUTHORIZATION LETTER	59
USACE NATIONWIDE PERMIT 14 GENERAL CONDITIONS	64

BDE SPECIAL PROVISIONS

The following special provisions indicated by an "X" are applicable to this contract. An * indicates a new or revised special provision for the letting.

	<u>File</u> Name	<u>Pg.</u>		Special Provision Title	Effective	<u>Revised</u>
	80099			Accessible Pedestrian Signals (APS)	April 1, 2003	Jan. 1, 2022
	80274	90	\boxtimes	Aggregate Subgrade Improvement	April 1, 2012	April 1, 2022
	80192			Automated Flagger Assistance Device	Jan. 1, 2008	April 1, 2023
	80173	93	\boxtimes	Bituminous Materials Cost Adjustments	Nov. 2, 2006	Aug. 1, 2017
	80426			Bituminous Surface Treatment with Fog Seal	Jan. 1, 2020	Jan. 1, 2022
	80241			Bridge Demolition Debris	July 1, 2009	
	50531		Ц	Building Removal	Sept. 1, 1990	Aug. 1, 2022
	50261	05		Building Removal with Asbestos Abatement	Sept. 1, 1990	Aug. 1, 2022
	80460	95 100		Cement, Finely Divided Minerals, Admixtures, Concrete, and Mortar	Jan. 1, 2025	Amil 1 0010
	80384 80198	106	\square	Compensable Delay Costs Completion Date (via calendar days)	June 2, 2017	April 1, 2019
	80198		H	Completion Date (via calendar days)	April 1, 2008 April 1, 2008	
	80461		H	Concrete Barrier	Jan. 1, 2000	
	80453		H	Concrete Sealer	Nov. 1, 2023	
	80261	110	\boxtimes	Construction Air Quality – Diesel Retrofit	June 1, 2010	Jan. 1, 2025
*	80029	112		Disadvantaged Business Enterprise Participation	Sept. 1, 2000	Jan. 2, 2025
	80229		\Box	Fuel Cost Adjustment	April 1, 2009	Aug. 1, 2017
	80452			Full Lane Sealant Waterproofing System	Nov. 1, 2023	U
	80447			Grading and Shaping Ditches	Jan 1, 2023	
	80433			Green Preformed Thermoplastic Pavement Markings	Jan. 1, 2021	Jan. 1, 2022
	80456			Hot-Mix Asphalt	Jan. 1, 2024	Jan. 1, 2025
	80446		Ц	Hot-Mix Asphalt – Longitudinal Joint Sealant	Nov. 1, 2022	Aug. 1, 2023
	80438		Ц	Illinois Works Apprenticeship Initiative – State Funded Contracts	June 2, 2021	April 2, 2024
*	80450	445		Mechanically Stabilized Earth Retaining Walls	Aug. 1, 2023	
	80464 80441	115 116	\boxtimes	Pavement Marking Inspection	April 1, 2025 Jan 1, 2023	
	80459	110	\square	Performance Graded Asphalt Binder Preformed Plastic Pavement Marking	June 2, 2023	
	3426I		H	Railroad Protective Liability Insurance	Dec. 1, 1986	Jan. 1, 2022
	80455	121	\boxtimes	Removal and Disposal of Regulated Substances	Jan. 1, 2024	April 1, 2024
	80445	123	\square	Seeding	Nov. 1, 2022	·
	80457	129	\boxtimes	Short Term and Temporary Pavement Markings	April 1, 2024	April 2, 2024
*	80462	133	\boxtimes	Sign Panels and Appurtenances	Jan. 1, 2025	April 1, 2025
	80448	134	\boxtimes	Source of Supply and Quality Requirements	Jan. 2, 2023	
	80340			Speed Display Trailer	April 2, 2014	Jan. 1, 2022
	80127			Steel Cost Adjustment	April 2, 2004	Jan. 1, 2022
	80397	135		Subcontractor and DBE Payment Reporting	April 2, 2018	
*	80391	136		Subcontractor Mobilization Payments	Nov. 2, 2017	April 1, 2019
	80463	137 138		Submission of Bidders List Information	Jan. 2, 2025	Mar. 2, 2025
	80437 80435	130		Submission of Payroll Records Surface Testing of Pavements – IRI	April 1, 2021 Jan. 1, 2021	Nov. 2, 2023 Jan. 1, 2023
*	80465	140	\square	Surveying Services	April 1, 2025	Jan. 1, 2025
*	80466	140	Ħ	Temporary Rumble Strips	April 1, 2025	
	20338	141	\square	Training Special Provisions	Oct. 15, 1975	Sept. 2, 2021
	80429		Ħ	Ultra-Thin Bonded Wearing Course	April 1, 2020	Jan. 1, 2022
	80439	144	\boxtimes	Vehicle and Equipment Warning Lights	Nov. 1, 2021	Nov. 1, 2022
	80458			Waterproofing Membrane System	Aug. 1, 2024	
*	80302	145	\square	Weekly DBE Trucking Reports	June 2, 2012	Jan. 2, 2025
	80454			Wood Sign Support	Nov. 1, 2023	
	80427	146	\square	Work Zone Traffic Control Devices	Mar. 2, 2020	Jan. 1, 2025
	80071	148	\boxtimes	Working Days	Jan. 1, 2002	

Saunders Road Improvements Section No.: 21-00020-00-RS Contract: 61K96

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1 2022, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of Contract 61K96, Project JFPC(674), Section 21-00020-00-RS, FAU 2416, Lake County and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

FAU 2416 Saunders Road Section 21-00020-00-RS Project JFPC(674) Job: C-91-241-24 Lake County Contract 61K96

LOCATION OF PROJECT

The project begins at Station 1+00.00, a point on the centerline of Saunders Road and extending to the north approximately 7,612.92 feet to Station 77+12.92. The project is located in the Village of Riverwoods, Lake County. Total Gross/Net length of the project is 7,612.92 feet (1.442 miles).

DESCRIPTION OF PROJECT

This project includes shoulder widening and resurfacing of Saunders Road. The improvements include earth excavation, HMA pavement, aggregate base course, HMA surface removal, storm sewer, pavement markings, and final restoration, as well as all incidental and collateral work necessary to complete the project, as shown on the plans or as described herein.

MAINTENANCE OF ROADWAYS (D1)

Effective: September 30, 1985 Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

TRAFFIC CONTROL PLAN (D1)

Effective: September 30, 1985 Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS:

701001-02, 701006-05, 701011-04, 701301-04, 701311-03, 701501-06, 701701-10, 701901-10, 780001-05

DETAILS:

TC-10 Traffic Control and Protection for Side Roads, Intersections, and Driveways TC-13 District One Typical Pavement Marking TC-16 Short-Term Pavement Marking Letters & Symbols TC-22 Arterial Road Information Sign

SPECIAL PROVISIONS:

Maintenance of Roadways (D1) Temporary Information Signing Public Convenience and Safety (D1) Short Term and Temporary Pavement Markings (BDE) Work Zone Traffic Control Devices (BDE) Vehicle and Equipment Warning Lights (BDE) Pavement and Shoulder Resurfacing (Recurring CS #13) Sign Panels and Appurtenances (BDE) Keeping Arterial Roadways Open to Traffic (D1) Pavement Marking Inspection (BDE)

PUBLIC CONVENIENCE AND SAFETY (D1)

Effective: May 1, 2012 Revised: July 15, 2012

Add the following to the end of the fourth paragraph of Article 107.09:

"If the holiday is on a Saturday or Sunday, and is legally observed on a Friday or Monday, the length of Holiday Period for Monday or Friday shall apply."

Add the following sentence after the Holiday Period table in the fourth paragraph of Article 107.09:

"The Length of Holiday Period for Thanksgiving shall be from 5:00 AM the Wednesday prior to 11:59 PM the Sunday After"

Delete the fifth paragraph of Article 107.09 of the Standard Specifications:

"On weekends, excluding holidays, roadways with Average Daily Traffic of 25,000 or greater, all lanes shall be open to traffic from 3:00 P.M. Friday to midnight Sunday except where structure construction or major rehabilitation makes it impractical."

STATUS OF UTILITIES (D1)

Effective: June 1, 2016 Revised: January 1, 2020

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information regarding their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department's contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

UTILITIES TO BE ADJUSTED

Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain the necessary permits to complete their work; in some instances, resolution will be a function of the construction staging. The responsible agency must relocate, or complete new installations as noted below; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

<u>Stage 1</u>

STAGE / LOCATION	ТҮРЕ	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME
Sta. 5+05	Electric Cable	Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.	ComEd	30 days
Sta. 8+70, 26' LT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 10+54, 27' LT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 15+30, 29' LT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 15+30, 22' RT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 19+30	Electric Cable	Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.	ComEd	30 days
Sta. 21+26, 35' LT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days

Sta. 23+26, 35' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 24+62, 33' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadwayComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadwayComEd30 daysSta. 32+85Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower Pole <t< th=""><th>Sta. 23+26, 35' LT Power Pole conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Electric conflict with the roadway ComEd 30 days Sta. 25+80 Electric Cable Electric cable will need to be relocated. ComEd 30 days Sta. 32+85 Electric Cable Comflict with the roadway ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need to be relocated ComEd 30 days Sta. 41+55, 30' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 41+55, 30' LT Power Pole Electric cable will need to be relocated. ComEd 30 days Sta. 41+55, 30' LT Power Pole Power pole will need to be relocated. ComEd 30 days Sta. 41+55, 30' LT Power pole will need to be relocated. ComEd 30 days Sta. 43+16 Electric cable will need to be relocated. ComEd 30 days Sta. 43+53, 29' LT Power pole is in conflict with the roadway</th><th></th><th></th><th></th><th></th><th></th></t<>	Sta. 23+26, 35' LT Power Pole conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Electric conflict with the roadway ComEd 30 days Sta. 25+80 Electric Cable Electric cable will need to be relocated. ComEd 30 days Sta. 32+85 Electric Cable Comflict with the roadway ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need to be relocated ComEd 30 days Sta. 41+55, 30' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 41+55, 30' LT Power Pole Electric cable will need to be relocated. ComEd 30 days Sta. 41+55, 30' LT Power Pole Power pole will need to be relocated. ComEd 30 days Sta. 41+55, 30' LT Power pole will need to be relocated. ComEd 30 days Sta. 43+16 Electric cable will need to be relocated. ComEd 30 days Sta. 43+53, 29' LT Power pole is in conflict with the roadway					
Sta. 23+26, 35' LT Power Pole roadway improvements on Saunders Road. Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Electric conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated. ComEd 30 days Sta. 25+60 Electric Cable Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated ComEd 30 days Sta. 32+85 Electric Cable Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated ComEd 30 days Sta. 41+55, 30' LT Power Pole Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated. ComEd 30 days Sta. 41+55, 30' LT Power Pole Electric cable will need to be relocated. ComEd 30 days Sta. 43+16 Electric Cable Electric cable will need to be relocated. ComEd 30 days Sta. 43+53, 29' LT Power Pole Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated. ComEd 30 days Sta. 50+31, 28' LT Power Pole Power pole is in confl	Sta. 23+26, 35' LT Power Pole roadway improvements on Saunders Road. Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 25+80 Electric Cable Electric conflict with the roadway ComEd 30 days Sta. 25+80 Electric Cable Electric cable will need to be relocated ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need to be relocated ComEd 30 days Sta. 41+55, 30' LT Power Pole Electric Cable Saunders Road. Electric cable will need to be relocated ComEd 30 days Sta. 41+55, 30' LT Power Pole Fower pole is in conflict with the roadway ComEd 30 days Sta. 41+55, 30' LT Power Pole Electric Cable Electric cable will need to be relocated ComEd 30 days Sta. 43+16 Electric Cable Electric cable will need to be relocated ComEd 30 days Sta. 43+53, 29' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 50+31, 28' LT Power Pole Power pole is in conflict with the roadway ComEd <td></td> <td></td> <td>Power pole is in</td> <td></td> <td></td>			Power pole is in		
Sta. 23+26, 35° LTPower Poleimprovements on Saunders Road. Power pole is in conflict with the roadway improvements onComEd30 daysSta. 24+62, 33° LTPower PolePower pole is in conflict with the roadway improvements onComEd30 daysSta. 24+62, 33° LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 24+62, 33° LTPower PoleElectric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadwayComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 41+55, 30° LTPower PoleElectric cablePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 41+55, 30° LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the <b< td=""><td>Sta. 23+26, 35' LT Power Pole improvements on Saunders Road. Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Electric cable is in conflict with the roadway ComEd 30 days Sta. 25+80 Electric Cable Electric cable will need ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need 30 days Sta. 41+55, 30' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 41+55, 30' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 43+16 Electric Cable Electric cable will need to be relocated. ComEd 30 days Sta. 43+16 Electric Cable Electric cable will need to be relocated. 30 days Sta. 48+53, 29' LT Power Pole Power pole is in roadway inprovements on Saunders Road. Electric cable will need to be relocated. ComEd 30 days Sta. 50+31, 28' LT Power Pole Pow</td><td></td><td></td><td></td><td></td><td></td></b<>	Sta. 23+26, 35' LT Power Pole improvements on Saunders Road. Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 24+62, 33' LT Power Pole Power pole will need to be relocated. ComEd 30 days Sta. 24+62, 33' LT Power Pole Electric cable is in conflict with the roadway ComEd 30 days Sta. 25+80 Electric Cable Electric cable will need ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need 30 days Sta. 41+55, 30' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 41+55, 30' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 43+16 Electric Cable Electric cable will need to be relocated. ComEd 30 days Sta. 43+16 Electric Cable Electric cable will need to be relocated. 30 days Sta. 48+53, 29' LT Power Pole Power pole is in roadway inprovements on Saunders Road. Electric cable will need to be relocated. ComEd 30 days Sta. 50+31, 28' LT Power Pole Pow					
Sanders Road Power pole will need to be relocated.Annual Power pole is in conflict with the roadway improvements on Sanders Road Power pole will need to be relocated.ComEd30 daysSta. 24+62, 33' LTPower PolePower pole is in conflict with the roadway improvements on Sanders Road Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Sanders Road Electric cable is in conflict with the roadway improvements on Sanders Road Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Sanders Road Electric cable is in conflict with the roadwaySanders Road sanders Road Electric cable is in conflict with the roadwaySta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Sanders Road <b< td=""><td>Size 24+62, 33' LTPower PoleSaunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 24+62, 33' LTPower PoleElectric conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocated Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocated Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole will need to be relocated to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComE</td><td></td><td></td><td></td><td></td><td></td></b<>	Size 24+62, 33' LTPower PoleSaunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 24+62, 33' LTPower PoleElectric conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocated Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocated Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole will need to be relocated to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComE					
Sta. 24+62, 33' LTPower PolePower pole is in conflict with the roadway improvements on Sauders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Sauders Road. Electric cable is in conflict with the roadway improvements on Sauders Road. <	Sta. 24+62, 33' LTPower PolePower pole is in conflict with the roadway improvements on conflict with the roadwayComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with	Sta. 23+26, 35' LT	Power Pole		ComEd	30 days
Sta. 24+62, 33' LTPower PoleTower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric will need to be relocatedComEd30 daysSta. 25+80Electric CableElectric will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower Pole Electric CablePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 41+55, 30' LTPower Pole Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+16Electric CableElectric will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower Pole Power PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower Pole iPower pole is in conflict with the roadway improvements on Saunders Road.Power pole is in conflict with the roadwaySaunders Road.Sta. 50+31, 28' LT<	Sta. 24+62, 33' LTPower PoleIt to be relocated. conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric will need to be relocatedComEd30 daysSta. 25+80Electric CableElectric will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric will need to be relocatedSta30 daysSta. 41+55, 30' LTPower PoleImprovements on conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+16Electric CableElectric will need to be relocated.ComEd30 daysSta. 43+53, 29' LTPower PoleElectric will need to be relocated.Sta 30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.Sta 30 days					
Sta. 24+62, 33' LT Power Pole Power Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated. ComEd 30 days Sta. 25+80 Electric Cable Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated. ComEd 30 days Sta. 25+80 Electric Cable Electric cable will need to be relocated. ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need to be relocated. ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need to be relocated. ComEd 30 days Sta. 41+55, 30' LT Power Pole Power Pole is in conflict with the roadway improvements on Saunders Road. ComEd 30 days Sta. 41+55, 30' LT Power Pole Electric cable is in conflict with the roadway improvements on Saunders Road. ComEd 30 days Sta. 43+16 Electric Cable is in conflict with the roadway improvements on Saunders Road. ComEd 30 days Sta. 43+16 Electric Cable is in conflict with the roadway improvements on Saunders Road. ComEd 30 days Sta. 43+16 Electric cable is in conflict with the roadway improvements on Saunders Road. ComEd 30 days Sta. 43+5	Sta. 24+62, 33' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 32+85Electric CableElectric cable will need to be relocated30 daysSta. 41+55, 30' LTPower Pole Saunders Road. Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in comflict with the 					
Sta. 24+62, 33' LTPower Poleconflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower Pole Power Pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower Pole Power Pole improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower Pole improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 days	Sta. 24+62, 33° LTPower Poleconflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 32+85Electric CableElectric cable will need to be relocated to be relocated30 daysSta. 41+55, 30° LTPower Pole Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadwayComEd30 daysSta. 41+55, 30° LTPower Pole Electric Cable is in conflict with the roadwayComEd30 daysSta. 41+55, 30° LTPower Pole Electric cable is in conflict with the roadwayComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadwayComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadwayComEd30 daysSta. 48+53, 29° LTPower Pole Power pole is in roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power p					
Sta. 24+62, 33' LTPower Poleroadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 43+16Electric CableElectric cable will need to be relocated to be relocatedComEd30 daysSta. 43+53, 29' LTPower Pole Power pole is in conflict with the roadway improvements on proveme	Sta. 24+62, 33' LTPower Poleroadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will needComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will needComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power p					
Sta. 24+62, 33' LTPower Poleimprovements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 25+80Electric CableElectric cable will need to be relocatedComEd30 daysSta. 25+80Electric CableElectric cable will need improvements on Saunders Road. Electric cable will needComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower Pole CablePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwaySta. 50+31, 28' LTPower PoleSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improve	Sta. 24+62, 33' LTPower Poleimprovements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Power pole is					
Sta. 25+80Similar Standers Road. Power pole will need to be relocated.ComEdSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableFelectric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 41+55, 30' LTPower PoleElectric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on <td>Sta. 25+80Electric CableSaunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower Pole Power Pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower Pole Power Pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower Pole Power Pole is in conflict with the roadway improvements on Saunders Road. Power pole is in co</br></td> <td></td> <td></td> <td></td> <td></td> <td></td>	Sta. 25+80Electric CableSaunders Road. Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric 					
Sta. 25+80Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableElectric cable is in roadway improvements on Saunders Road.ComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedSta. 41+55, 30' LTSta. 41+55, 30' LTPower Pole Power Pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable will need to be relocatedSta. 43+16Sta. 43+16Electric cable will need to be relocated.Sta. 43+16Electric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+16Power pole will need to be relocatedFower pole will need to be relocatedSta. 43+1630 daysSta. 43+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole i	Sta. 25+80Power pole will need to be relocated.ComEd30 daysSta. 25+80Electric CableSaunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocated to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocated to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocated to be relocatedComEd30 daysSta. 41+55, 30' LTPower Pole Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 43+16Electric CableElectric cable will need to be relocatedComEd30 daysSta. 43+53, 29' LTPower Pole Power Pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower Pole Power Pole improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. P	Sta. 24+62, 33' LT	Power Pole		ComEd	30 days
Sta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower Pole Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 41+55, 30' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 43+16Electric CableElectric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 43+16Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on S	Sta. 25+80Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CablePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 41+55, 30' LTPower PolePower pole will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable will need to be relocated.30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 48+53, 29' LTPower Pole Power pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower Pole Power pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower Pole Power pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower pole pole will need to be relocated.ComEd<					
Sta. 25+80 Electric Cable Electric cable is in conflict with the saunders Road. Electric cable will need to be relocated ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need to be relocated ComEd 30 days Sta. 32+85 Electric Cable Electric cable will need to be relocated ComEd 30 days Sta. 32+85 Electric Cable Flectric cable will need to be relocated ComEd 30 days Sta. 41+55, 30' LT Power Pole Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated ComEd 30 days Sta. 43+16 Electric Cable Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated ComEd 30 days Sta. 43+16 Electric Cable Electric cable is in conflict with the roadway improvements on Saunders Road. Electric will need to be relocated ComEd 30 days Sta. 48+53, 29' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 50+31, 28' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days	Sta. 25+80Electric CableElectric conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 50+31, 28' LTPower PolePower pole will need improvements on Saunders Road. Power pole will need to be relocatedSome daysSta. 50+31, 28' LTPower PolePower pole will					
Sta. 25+80Electric Cableconflict with the radway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the radway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunde	Sta. 25+80Electric Cableconflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 43+16Electric CableElectric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadway power pole will need to be relocated					
Sta. 25+80Electric Cableroadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable si in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole si in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocatedComEd30 daysSta. 43+16Power PoleElectric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements onComEd30 daysSta. 50+31, 28' LTPower PolePower pole will need to be relocated.ComEd30 days	Sta. 25+80Electric Cableroadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 48+53, 29' LTPower Pole Power Pole improvements on Saunders Road. Power pole will need to prelo					
Sta. 25+80Electric Cableimprovements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower Pole Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower Pole Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower Pole improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway30 daysSta. 48+53, 29' LTPower Pole improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower Pole improvements on comflict with the roadwayPower Pole 	Sta. 25+80Electric Cableimprovements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Electric Cableconflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict wit					
Sta. 25+80Cableimprovements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CableElectric cable will need to be relocatedComEd30 daysSta. 32+85Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Electric Cable is in conflict with the roadwayComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadwayComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole improvements on conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with t	Sta. 25+80Cableimprovements on Saunders Road. Electric cable sin conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower Pole Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower Pole Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 days	01.05.00	Electric			00.1
Sta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable will need to be relocated.30 daysSta. 43+16Power Pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 48+53, 29' LTPower Pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improveme	Saturders Road. Electric cable will need to be relocatedElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 32+85Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.ComEd30 daysSta. 43+16Power Poleimprovements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway <b< td=""><td>Sta. 25+80</td><td></td><td></td><td>ComEd</td><td>30 days</td></b<>	Sta. 25+80			ComEd	30 days
Sta. 32+85Telectric CableElectric cableElectric roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.ComEd30 daysSta. 43+16Power Pole Electric CableElectric cable will need to be relocated.Sta. 43+1630 daysSta. 48+53, 29' LTPower Pole Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Sau	Sta. 32+85Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadwayComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadwayComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadwayComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwaySomEd30 daysSta. 50+31, 28' LTPower PolePower po					
Sta. 32+85Electric CableElectric code is in conflict with the modway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the modway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on comdway improvements on comdway roadwayComEd30 days	Sta. 32+85Electric CableElectric conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PolePower PoleStanders Road. electric Cable will need to be relocated.30 daysSta. 41+55, 30' LTPower PoleElectric comparents on Saunders Road. Electric Cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocated.30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 days					
Sta. 32+85Electric Cableconflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on comets on saunders Road. Power pole is in conflict with the roadway improvements on comet on saunders Road. <b< td=""><td>Sta. 32+85Electric Cableconflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will ne</td><td></td><td></td><td></td><td></td><td></td></b<>	Sta. 32+85Electric Cableconflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will ne					
Sta. 32+85Electric Cableroadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadwayComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements onComEd30 days	Sta. 32+85Electric Cableroadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PolePower Pole sumprovements on conflict with the roadway improvements on conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocatedComEd30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 days					
Sta. 32+85Electric Cableimprovements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PolePower PoleStaunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cableComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwaySta 50+31, 28' LTPower Pole	Sta. 32+85Lefectric Cableimprovements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict will need bower pole will need vower pole will need bower pole will needComEd30 days <td></td> <td></td> <td></td> <td></td> <td></td>					
CableSaunders Road. Electric cable will need to be relocatedSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEdSta. 41+55, 30' LTPower PoleSaunders Road. Power pole will need to be relocated.ComEdSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 43+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwayComEd30 days	CableSaunders Road. Electric cable will need to be relocatedSta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEdSta. 41+55, 30' LTPower PolePower PoleSta. 41+55, 30' LTPower PolePower PoleSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower Pole in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower Pole improvements on Saunders Road. Power pole will need to be relocated.30 days	Cto 20105	Electric		ComEd	
Sta. 41+55, 30' LTPower PoleElectric cable will need to be relocatedComEd30 daysSta. 41+55, 30' LTPower Poleimprovements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwayComEd30 days	Sta. 41+55, 30' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric with the roadway improvements on Saunders Road. Electric with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 days	Sia. 32+85	Cable			30 days
Image: sta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 41+55, 30' LTPower PoleElectric cable is in conflict with the roadwayComEd30 daysSta. 41+55, 30' LTElectric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 43+16Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on30 days	Sta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated.30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway30 daysSta. 50+31, 28' LTPower PolePower Pole improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need30 days					
Sta. 41+55, 30' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power pole will need to be relocated.Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road.30 days	Sta. 41+55, 30' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Ference Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 days					
Sta. 41+55, 30' LTPower Poleconflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power Pole improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower Pole Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower Pole improvements on conflict with the roadway improvements onComEd30 days	Sta. 41+55, 30' LTPower Poleconflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower pole will need roadway improvements on Saunders Road. Power pole will need to be relocated.30 days					
Sta. 41+55, 30' LTPower Poleroadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadway improvements onComEd30 days	Sta. 41+55, 30' LTPower Poleroadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableComEd30 daysSta. 43+16Felectric CableComEd30 daysSta. 43+16Felectric cableComEd30 daysSta. 43+16Felectric cableSaunders Road. Electric cable will need to be relocated30 daysSta. 43+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 days					
Sta. 41+55, 30' LTPower Poleimprovements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CablePower pole will need to be relocated.ComEd30 daysSta. 43+16Power Pole roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower Pole Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower Poleimprovements on comflict with the roadway improvements onComEd30 days	Sta. 41+55, 30' LTPower Poleimprovements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CableElectric cable will need to be relocatedComEd30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 days					
Sta. 43+16Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power pole is in conflict with the roadway Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower Poleimprovements on roadway improvements onComEd30 days	Sta. 43+16Saunders Road. Power pole will need to be relocated.Sta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEdSta. 43+16Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadway improvements on Saunders Road. Power pole will need improvements on Saunders Road. Power pole will need30 days	Sta 41+55 30' LT	Power Pole		ComEd	30 dave
Sta. 43+16Power pole will need to be relocated.Power pole will need to be relocated.Sta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power pole is in conflict with the roadway improvements on conflict with the roadwayComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower Poleimprovements on conflict with the roadway improvements onComEd30 days	Sta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Electric CablePower pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.So daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.So daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need improvements on Saunders Road. Power pole will needSo days	Old. 71, 50, 50 L1	Power Pole		Comed	30 days
Sta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements onComEd30 daysSta. 50+31, 28' LTPower Poleimprovements on improvements onComEd30 days	Sta. 43+16Electric CableElectric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Flectric CablePower pole is in conflict with the roadway improvements on ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 days					
Sta. 43+16Electric CableElectric roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Sta. 43+16Power pole is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements onComEd30 daysSta. 50+31, 28' LTPower Poleimprovements on improvements onComEd30 days	Sta. 43+16Electric CableElectric conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Sta. 43+16Electric CableSaunders Road. Electric cable will need to be relocated30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower Poleimprovements on saunders Road. Power pole will need to be relocated.Sta. 50+31, 28' LTPower Pole					
Sta. 43+16Electric Cableconflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadwayComEd30 daysSta. 48+53, 29' LTPower PolePower pole will need to be relocated.Stal Sol 431, 28' LT30 days	Sta. 43+16Electric Cableconflict with the roadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need improvements on Saunders Road. Power pole will need30 days					
Sta. 43+16Electric Cableroadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power pole is in conflict with the roadway improvements on Saunders Road. Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower Poleimprovements on conflict with the roadway improvements onComEd30 days	Sta. 43+16Electric Cableroadway improvements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power cable will need to be relocatedPower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower Pole improvements on conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 50+31, 28' LTPower Poleimprovements on Saunders Road. Power pole will need improvements on Saunders Road. Power pole will need30 days					
Sta. 43+16Electric Cableimprovements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 43+16Power pole is in conflict with the roadway improvements on Saunders Road. Power PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.30 daysSta. 48+53, 29' LTPower PolePower Pole improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower Poleimprovements on conflict with the roadway improvements onComEd30 days	Sta. 43+16Electric Cableimprovements on Saunders Road. Electric cable will need to be relocatedComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 48+53, 29' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower PolePower pole is in conflict with the roadway improvements on Saunders Road. Power pole is in conflict with the roadwayComEd30 daysSta. 50+31, 28' LTPower Poleimprovements on Saunders Road. Power pole will need to power pole will needComEd30 days		_			
Cable Saunders Road. Electric cable will need Electric cable will need to be relocated Power pole is in Conflict with the roadway Sta. 48+53, 29' LT Power Pole improvements on ComEd Saunders Road. Power pole will need Power pole will need Power pole will need to be relocated. Power pole is in Conflict with the ComEd Sta. 50+31, 28' LT Power Pole improvements on ComEd Sta. 50+31, 28' LT Power Pole	Saunders Road. Electric cable will need to be relocated Sta. 48+53, 29' LT Power Pole Power Pole Power pole is in conflict with the roadway Sta. 48+53, 29' LT Power Pole Sta. 48+53, 29' LT Power Pole Sta. 48+53, 29' LT Power Pole Sta. 50+31, 28' LT Power Pole Saunders Road. Power pole will need Sounders Road. Power pole will need	Sta. 43+16		,	ComEd	30 davs
Electric cable will need to be relocatedElectric cable will need to be relocatedImage: Complex set of the set of	Electric cable will need to be relocatedImage: Power pole is in conflict with the roadwayImage: Power pole is in conflict with the roadwaySta. 48+53, 29' LTPower PolePower pole is in conflict with the roadwayImage: Power pole is in conflict with the roadwayImage: Power pole is in conflict with the roadwayImage: Power pole is in conflict with the roadwaySta. 50+31, 28' LTPower PolePower Pole is in conflict with the roadwayImage: Power pole is in conflict with the roadwayImage: Power pole is in conflict with the roadwayImage: Power PoleSta. 50+31, 28' LTPower PoleImage: Power pole will needImage: Power pole will needSta. 50+31, 28' LTPower PoleImage: Power pole will needImage: Power pole will needSta. 50+31, 28' LTPower PoleImage: Power pole will needImage: Power pole will need		Cable		Somea	
to be relocatedPower pole is in conflict with the roadwaySta. 48+53, 29' LTPower PolePower Poleimprovements on Saunders Road. Power pole will need to be relocated.Power pole si in conflict with the roadwaySta. 50+31, 28' LTPower Poleimprovements on roadwaySta. 50+31, 28' LTPower PoleSta. 50+31, 28' LTPower Pole <t< td=""><td>Image: Sta. 48+53, 29' LTPower Poleto be relocatedImage: Sta. 48+53, 29' LTPower PolePower PoleImage: Sta. 48+53, 29' LTPower PolePower PoleImage: Sta. 48+53, 29' LTPower PoleImage: Sta. 48+53, 29' LTPower PoleImage: Sta. 50+31, 28' LTPower PolePower PoleSta. 50+31, 28' LTPower PoleImage: Sta. 50+31, 28' LTPower Pole<td></td><td></td><td></td><td></td><td></td></td></t<>	Image: Sta. 48+53, 29' LTPower Poleto be relocatedImage: Sta. 48+53, 29' LTPower PolePower PoleImage: Sta. 48+53, 29' LTPower PolePower PoleImage: Sta. 48+53, 29' LTPower PoleImage: Sta. 48+53, 29' LTPower PoleImage: Sta. 50+31, 28' LTPower PolePower PoleSta. 50+31, 28' LTPower PoleImage: Sta. 50+31, 28' LTPower Pole <td></td> <td></td> <td></td> <td></td> <td></td>					
Sta. 48+53, 29' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 48+53, 29' LT Power Pole improvements on Saunders Road. ComEd 30 days Power pole will need to be relocated. Power pole is in conflict with the roadway 30 days 30 days Sta. 50+31, 28' LT Power Pole improvements on ComEd 30 days	Sta. 48+53, 29' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 48+53, 29' LT Power Pole improvements on Saunders Road. ComEd 30 days Sta. 48+53, 29' LT Power Pole Power pole will need to be relocated. ComEd 30 days Sta. 50+31, 28' LT Power Pole Power pole is in conflict with the roadway ComEd 30 days Sta. 50+31, 28' LT Power Pole improvements on Saunders Road. ComEd 30 days					
Sta. 48+53, 29' LTPower Poleconflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.ComEd30 daysSta. 50+31, 28' LTPower Poleimprovements on saunders Road. Power pole is in conflict with the roadwayComEd30 days	Sta. 48+53, 29' LT Power Pole improvements on Saunders Road. ComEd 30 days Sta. 48+53, 29' LT Power Pole improvements on Saunders Road. Power pole will need to be relocated. 30 days Sta. 50+31, 28' LT Power Pole Power Pole is in conflict with the roadway Saunders Road. Anticipation of the second					
Sta. 48+53, 29' LT Power Pole improvements on improvements on Saunders Road. ComEd 30 days Power pole improvements on Saunders Road. Power pole will need to be relocated.	Sta. 48+53, 29' LT Power Pole improvements on Saunders Road. Power pole will need to be relocated. ComEd 30 days Sta. 50+31, 28' LT Power Pole Power pole is in conflict with the roadway Four pole is in conflict with the roadway August be an and the power pole Sta. 50+31, 28' LT Power Pole Improvements on Saunders Road. Power pole will need ComEd 30 days					
Sta. 48+53, 29' LT Power Pole improvements on Saunders Road. ComEd 30 days Power pole will need to be relocated. Power pole will need to be relocated. 1000000000000000000000000000000000000	Sta. 48+53, 29' LT Power Pole improvements on Saunders Road. ComEd 30 days Power pole will need to be relocated. Power pole will need 1000000000000000000000000000000000000					
Saunders Road. Power pole will need to be relocated. Power pole is in conflict with the roadway Power Pole Sta. 50+31, 28' LT Power Pole	Saunders Road. Power pole will need to be relocated. Power pole is in conflict with the roadway Power Pole is in conflict with the roadway Sta. 50+31, 28' LT Power Pole improvements on Saunders Road. Power pole will need Staunders Road. 30 days	Sta. 48+53, 29' LT	Power Pole		ComEd	30 days
Power pole will need to be relocated. Power pole is in conflict with the roadway Power pole is in Sta. 50+31, 28' LT Power Pole improvements on ComEd 30 days	Power pole will need to be relocated. Power pole is in conflict with the roadway Power pole is in conflict with the roadway Sta. 50+31, 28' LT Power Pole improvements on Saunders Road. Power pole will need ComEd 30 days					,
to be relocated. Power pole is in conflict with the roadway Sta. 50+31, 28' LT Power Pole improvements on ComEd 30 days	to be relocated. Power pole is in conflict with the roadway Sta. 50+31, 28' LT Power Pole improvements on Saunders Road. Power pole will need					
sta. 50+31, 28' LT Power Pole improvements on ComEd 30 days	Sta. 50+31, 28' LT Power Pole improvements on Saunders Road. ComEd 30 days					
Sta. 50+31, 28' LTPower PoleroadwaySta. 50+31, 28' LTPower Poleimprovements onComEd30 days	Sta. 50+31, 28' LT Power Pole improvements on Saunders Road. Power pole will need ComEd 30 days			Power pole is in		
Sta. 50+31, 28' LT Power Pole improvements on ComEd 30 days	Sta. 50+31, 28' LT Power Pole improvements on Saunders Road. ComEd 30 days Power pole will need Staunders Road. Staunders Road. Staunders Road. Staunders Road.			conflict with the		
	Saunders Road. Power pole will need			roadway		
Saunders Road.	Power pole will need	Sta. 50+31, 28' LT	Power Pole		ComEd	30 days
	to be relocated					
to be relocated				to be relocated.		

Sta. 52+04, 28' LT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 57+62, 31' LT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 63+72, 27' LT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 63+88, 20' RT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 65+76, 38' LT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days
Sta. 66+00, 25' Rt to Sta. 69+50, 20' RT	Electric Cable	Electric cable is in conflict with the roadway improvements on Saunders Road. Electric cable will need to be relocated	ComEd	30 days
Sta. 77+00, 39' RT	Power Pole	Power pole is in conflict with the roadway improvements on Saunders Road. Power pole will need to be relocated.	ComEd	30 days

Stage 1: <u>30</u> Days Total Installation

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Company Responsible to Resolve Conflict	Name of contact	Phone	E-mail address
AT&T	Janet Ahern	630-573-6414	G05256@att.com
ComEd	Vincent Mazzaferro	630-437-4855	Vincent.MazzaferroPE@ComEd.com
Comcast	Martha Gieras	224-229-5862	martha.gieras@comcast.com
Lake County Public Works	Brittany Sloan	847-377-7133	pwengineeringgroup@lakecountyil.gov
North Shore Gas	Jay Hammer	847-263-4678	jay.hammer@northshoregasdelivery.com

UTILITIES TO BE WATCHED AND PROTECTED

The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances, the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owner's part can be secured.

Stage 1

STAGE / LOCATION	TYPE	DESCRIPTION	OWNER
West side of Saunders Road	Power poles/Electric	The contractor is alerted there are power poles and aerial lines within the project limits. There are no conflicts to report.	ComEd
West side of Saunders Road	Power poles /Telephone	The contractor is alerted there are power poles and aerial lines within the project limits. There are no conflicts to report.	Comcast
East and West side of Saunders Road	Gas	The contractor is alerted there are underground gas mains within the project limits. There are no conflicts to report.	North Shore Gas
East side of Saunders Road	Sanitary	The contractor is alerted there are underground force mains within the project limits. There are no conflicts to report.	Lake County Public Works
East and West side of Saunders Road	Water	The contractor is alerted there are underground water mains within the project limits. There are no conflicts to report.	Lake County Public Works
East side of Saunders Road	Cable	The contractor is alerted there are underground cable lines within the project limits. There are no conflicts to report.	AT&T

The following contact information is what was used during the preparation of the plans as provided by the owner of the facility.

Agency/Company Responsible to Resolve Conflict	Name of contact	Phone	E-mail address
AT&T	Janet Ahern	630-573-6414	G05256@att.com
ComEd	Vincent Mazzaferro	630-437-4855	Vincent.MazzaferroPE@ComEd.com
Comcast	Martha Gieras	224-229-5862	martha.gieras@comcast.com
Lake County Public Works	Brittany Sloan	847-377-7133	pwengineeringgroup@lakecountyil.gov
North Shore Gas	Jay Hammer	847-263-4678	jay.hammer@northshoregasdelivery.com

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be considered in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided above for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation duration must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor and the utility companies when necessary. The Department's contractor is responsible for contacting J.U.L.I.E. prior to all excavation work.

ADJUSTMENTS AND RECONSTRUCTIONS (D1)

Effective: March 15, 2011 Revised: October 1, 2021

Revise the first paragraph of Article 602.04 to read:

"602.04 Concrete. Cast-in-place concrete for structures shall be constructed of Class SI concrete according to the applicable portions of Section 503. Cast-in-place concrete for pavement patching around adjustments and reconstructions shall be constructed of Class PP-2 concrete, unless otherwise noted in the plans, according to the applicable portions of Section 1020."

Revise the third, fourth and fifth sentences of the second paragraph of Article 602.11(c) to read:

"Castings shall be set to the finished pavement elevation so that no subsequent adjustment will be necessary, and the space around the casting shall be filled with Class PP-2 concrete, unless otherwise noted in the plans, to the elevation of the surface of the base course or binder course. HMA surface or binder course material shall not be allowed. The pavement may be opened to traffic according to Article 701.17(e)(3)b."

Revise Article 603.05 to read:

"603.05 Replacement of Existing Flexible Pavement. After the castings have been adjusted, the surrounding space shall be filled with Class PP-2 concrete, unless otherwise noted in the plans, to the elevation of the surface of the base course or binder course. HMA surface or binder course material shall not be allowed. The pavement may be opened to traffic according to Article 701.17(e)(3)b."

Revise Article 603.06 to read:

"603.06 Replacement of Existing Rigid Pavement. After the castings have been adjusted, the pavement and HMA that was removed, shall be replaced with Class PP-2 concrete, unless otherwise noted in the plans, not less than 9 in. (225 mm) thick. The pavement may be opened to traffic according to Article 701.17(e)(3)b.

The surface of the Class PP concrete shall be constructed flush with the adjacent surface."

Revise the first sentence of Article 603.07 to read:

"603.07 Protection Under Traffic. After the casting has been adjusted and the Class PP concrete has been placed, the work shall be protected by a barricade and two lights according to Article 701.17(e)(3)b."

AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS (D1)

Effective: April 1, 2001 Revised: January 2, 2007

Revise Article 402.10 of the Standard Specifications to read:

"402.10 For Temporary Access. The contractor shall construct and maintain aggregate surface course for temporary access to private entrances, commercial entrances and roads according to Article 402.07 and as directed by the Engineer.

The aggregate surface course shall be constructed to the dimensions and grades specified below, except as modified by the plans or as directed by the Engineer.

- (a) Private Entrance. The minimum width shall be 12 ft (3.6 m). The minimum compacted thickness shall be 6 in. (150 mm). The maximum grade shall be eight percent, except as required to match the existing grade.
- (b) Commercial Entrance. The minimum width shall be 24 ft (7.2 m). The minimum compacted thickness shall be 9 in. (230 mm). The maximum grade shall be six percent, except as required to match the existing grade.
- (c) Road. The minimum width shall be 24 ft (7.2 m). The minimum compacted thickness shall be 9 in. (230 mm). The grade and elevation shall be the same as the removed pavement, except as required to meet the grade of any new pavement constructed.

Maintaining the temporary access shall include relocating and/or regrading the aggregate surface coarse for any operation that may disturb or remove the temporary access. The same type and gradation of material used to construct the temporary access shall be used to maintain it.

When use of the temporary access is discontinued, the aggregate shall be removed and utilized in the permanent construction or disposed of according to Article 202.03."

Add the following to Article 402.12 of the Standard Specifications:

"Aggregate surface course for temporary access will be measured for payment as each for every private entrance, commercial entrance or road constructed for the purpose of temporary access. If a residential drive, commercial entrance, or road is to be constructed under multiple stages, the aggregate needed to construct the second or subsequent stages will not be measured for payment but shall be included in the cost per each of the type specified."

Revise the second paragraph of Article 402.13 of the Standard Specifications to read:

"Aggregate surface course for temporary access will be paid for at the contract unit price per each for TEMPORARY ACCESS (PRIVATE ENTRANCE), TEMPORARY ACCESS (COMMERCIAL ENTRANCE) or TEMPORARY ACCESS (ROAD).

Partial payment of the each amount bid for temporary access, of the type specified, will be paid according to the following schedule:

- (a) Upon construction of the temporary access, sixty percent of the contract unit price per each, of the type constructed, will be paid.
- (b) Subject to the approval of the Engineer for the adequate maintenance and removal of the temporary access, the remaining forty percent of the pay item will be paid upon the permanent removal of the temporary access."

DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (D1)

Effective: April 1, 2011 Revised: April 2, 2011

Add the following to Article 603.02 of the Standard Specifications:

- (i) Temporary Hot-Mix Asphalt (HMA) Ramp (Note 1)1030
- (j) Temporary Rubber Ramps (Note 2)

Note 1. The HMA shall have maximum aggregate size of 3/8 in. (95 mm).

Note 2. The rubber material shall be according to the following.

Property	Test Method	Requirement
Durometer Hardness, Shore A	ASTM D 2240	75 ±15
Tensile Strength, psi (kPa)	ASTM D 412	300 (2000) min
Elongation, percent	ASTM D 412	90 min
Specific Gravity	ASTM D 792	1.0 - 1.3
Brittleness, °F (°C)	ASTM D 746	-40 (-40)"

Revise Article 603.07 of the Standard Specifications to read:

"603.07 Protection Under Traffic. After the casting has been adjusted and the Class PP concrete has been placed, the work shall be protected by a barricade and two lights according to Article 701.17(e)(3)b.

When castings are under traffic before the final surfacing operation has been started, properly sized temporary ramps shall be placed around the drainage and/or utility castings according to the following methods.

- (a) Temporary Asphalt Ramps. Temporary hot-mix asphalt ramps shall be placed around the casting, flush with its surface and decreasing to a featheredge in a distance of 2 ft (600 mm) around the entire surface of the casting.
- (b) Temporary Rubber Ramps. Temporary rubber ramps shall only be used on roadways with permanent posted speeds of 40 mph or less and when the height of the casting to be protected meets the proper sizing requirements for the rubber ramps as shown below.

Dimension	Requirement
Inside Opening	Outside dimensions of casting + 1 in. (25 mm)
Thickness at inside	Height of casting \pm 1/4 in. (6 mm)
edge	
Thickness at	1/4 in. (6 mm) max.
outside edge	
Width, measured	8 1/2 in. (215 mm) min
from inside opening	
to outside edge	

Placement shall be according to the manufacturer's specifications.

Temporary ramps for castings shall remain in place until surfacing operations are undertaken within the immediate area of the structure. Prior to placing the surface course, the temporary ramp shall be removed. Excess material shall be disposed of according to Article 202.03."

FRICTION AGGREGATE (D1)

Effective: January 1, 2011 Revised: December 1, 2021

Revise Article 1004.03(a) of the Standard Specifications to read:

"1004.03 Coarse Aggregate for Hot-Mix Asphalt (HMA). The aggregate shall be according to Article 1004.01 and the following.

(a) Description. The coarse aggregate for HMA shall be according to the following table.

Use	Mixture	Aggregates Allowed
Class A	Seal or Cover	Allowed Alone or in Combination 5/:
		Gravel Crushed Gravel Carbonate Crushed Stone Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag Crushed Concrete
HMA	Stabilized Subbase	Allowed Alone or in Combination ^{5/} :
Low ESAL	or Shoulders	Gravel Crushed Gravel Carbonate Crushed Stone Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag ^{1/} Crushed Concrete
HMA	Binder	Allowed Alone or in Combination ^{5/6/} :
High ESAL Low ESAL	IL-19.0 or IL-19.0L SMA Binder	Crushed Gravel Carbonate Crushed Stone ^{2/} Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Concrete ^{3/}
HMA	C Surface and Binder IL-9.5	Allowed Alone or in Combination ^{5/} :
High ESAL Low ESAL	IL-9.5FG or IL-9.5L	Crushed Gravel Carbonate Crushed Stone ^{2/} Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag ^{4/} Crushed Concrete ^{3/}

Use	Mixture	Aggregates Allow	ed		
HMA High ESAL	D Surface and Binder IL-9.5 or IL-9.5FG	Allowed Alone or in Combination ^{5/} : Crushed Gravel Carbonate Crushed Stone (other the Limestone) ^{2/} Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel Slag ^{4/}			
		Other Combinatio	ns Allowed:		
		Up to	With		
		25% Limestone	Dolomite		
		50% Limestone	Any Mixture D aggregate other than Dolomite		
		75% Limestone	Crushed Slag (ACBF) or Crushed Sandstone		
НМА	E Surface	Allowed Alone or in Combination ^{5/6/} :			
High ESAL	IL-9.5Crushed Gravel Crystalline Crushed Stone Crushed Sandstone Crushed Slag (ACBF) Crushed Steel SlagNo Limestone.				
		Other Combinatio	ns Allowed:		
		Up to	With		
		50% Dolomite ^{2/}	Any Mixture E aggregate		
		75% Dolomite ^{2/}	Crushed Sandstone, Crushed Slag (ACBF), Crushed Steel Slag, or Crystalline Crushed Stone		
		75% Crushed Gravel ^{2/}	Crushed Sandstone, Crystalline Crushed Stone, Crushed Slag (ACBF), or Crushed Steel Slag		

Use	Mixture	Aggregates Allowed			
HMA High ESAL	F Surface IL-9.5 SMA Ndesign 80 Surface	Allowed Alone or Crystalline Crush Crushed Sandsto Crushed Slag (AC Crushed Steel Sla No Limestone. Other Combinatio Up to 50% Crushed Gravel ^{2/} or Dolomite ^{2/}	ne CBF) ag <u>ons Allowed</u> : <u><i>With</i> Crushed Sandstone,</u>		

- 1/ Crushed steel slag allowed in shoulder surface only.
- Carbonate crushed stone (limestone) and/or crushed gravel shall not be used in SMA Ndesign 80.
- 3/ Crushed concrete will not be permitted in SMA mixes.
- 4/ Crushed steel slag shall not be used as binder.
- 5/ When combinations of aggregates are used, the blend percent measurements shall be by volume."
- 6/ Combining different types of aggregate will not be permitted in SMA Ndesign 80."

HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)

Effective: November 1, 2019 Revised: January 1, 2025

Revise Article 1004.03(c) to read:

"(c) Gradation. The coarse aggregate gradations shall be as listed in the following table.

Use	Size/Application	Gradation No.
Class A-1, A-2, & A-3	3/8 in. (10 mm) Seal	CA 16 or CA 20
Class A-1	1/2 in. (13 mm) Seal	CA 15
Class A-2 & A-3	Cover Coat	CA 14
	IL-19.0;	CA 11 ^{1/}
	Stabilized Subbase IL-19.0	
	SMA 12.5 ^{2/}	CA 13 ^{4/} , CA 14, or CA 16
HMA High ESAL	SMA 9.5 ^{2/}	CA 13 ^{3/4/} or CA 16 ^{3/}
	IL-9.5	CA 16, CM 13 ^{4/}
	IL-9.5FG	CA 16
	IL-19.0L	CA 11 ^{1/}
HMA Low ESAL	IL-9.5L	CA 16

- 1/ CA 16 or CA 13 may be blended with the CA 11.
- 2/ The coarse aggregates used shall be capable of being combined with the fine aggregates and mineral filler to meet the approved mix design and the mix requirements noted herein.
- 3/ The specified coarse aggregate gradations may be blended.
- 4/ CA 13 shall be 100 percent passing the 1/2 in. (12.5mm) sieve."

Revise Article 1004.03(e) of the Standard Specifications to read:

"(e) Absorption. For SMA the coarse aggregate shall also have water absorption ≤ 2.0 percent."

Revise the "High ESAL" portion of the table in Article 1030.01 to read:

"High ESAL	Binder Courses	IL-19.0, IL-9.5, IL-9.5FG, IL-4.75, SMA 12.5, Stabilized Subbase IL-19.0
	Surface Courses	IL-9.5, IL-9.5FG, SMA 12.5, SMA 9.5"

Revise Note 2. and add Note 6 to Article 1030.02 of the Standard Specifications to read:

"Item	Article/Section
(g)Performance Graded Asphalt Binder (Note 6) (h)Fibers (Note 2)	1032

Note 2. A stabilizing additive such as cellulose or mineral fiber shall be added to the SMA mixture according to Illinois Modified AASHTO M 325. The stabilizing additive shall meet the Fiber Quality Requirements listed in Illinois Modified AASHTO M 325. Prior to approval and use of fibers, the Contractor shall submit a notarized certification by the producer of these materials stating they meet these requirements. Reclaimed Asphalt Shingles (RAS) may be used in Stone Matrix Asphalt (SMA) mixtures designed with an SBA polymer modifier as a fiber additive if the mix design with RAS included meets AASHTO T305 requirements. The RAS shall be from a certified source that produces either Type I or Type 2. Material shall meet requirements noted herein and the actual dosage rate will be determined by the Engineer.

Note 6. The asphalt binder shall be an SBS PG 76-28 when the SMA is used on a full-depth asphalt pavement and SBS PG 76-22 when used as an overlay, except where modified herein. The asphalt binder shall be a SBS PG 76-22 for IL-4.75, except where modified herein.."

	"MIXTURE COMPOSITION (% PASSING) 1/											
Sieve	IL-19	.0 mm	SMA	12.5	SMA	9.5	IL-9.	5mm	IL-9.	5FG	IL-4.7	'5 mm
Size	min	max	min	max	min	max	min	max	min	max	min	max
1 1/2 in (37.5 mm)												
1 in. (25 mm)		100										
3/4 in. (19 mm)	90	100		100								
1/2 in. (12.5 mm)	75	89	80	100		100		100		100		100
3/8 in. (9.5 mm)				65	90	100	90	100	90	100		100
#4 (4.75 mm)	40	60	20	30	36	50	34	69	60	75 ^{6/}	90	100
#8 (2.36 mm)	20	42	16	24 ^{4/}	16	324/	34 5/	52 ^{2/}	45	60 ^{6/}	70	90
#16 (1.18 mm)	15	30					10	32	25	40	50	65
#30 (600 μm)			12	16	12	18			15	30		
#50 (300 μm)	6	15					4	15	8	15	15	30
#100 (150 μm)	4	9					3	10	6	10	10	18
#200 (75 μm)	3.0	6.0	7.0	9.0 ^{3/}	7.5	9.5 ^{3/}	4.0	6.0	4.0	6.5	7.0	9.0 ^{3/}
#635 (20 μm)			≤	3.0	≤ 3	8.0						
Ratio Dust/Asphalt Binder		1.0		1.5		1.5		1.0		1.0		1.0

Revise table in Article 1030.05(a) of the Standard Specifications to read:

- 1/ Based on percent of total aggregate weight.
- 2/ The mixture composition shall not exceed 44 percent passing the #8 (2.36 mm) sieve for surface courses with Ndesign = 90.
- 3/ Additional minus No. 200 (0.075 mm) material required by the mix design shall be mineral filler, unless otherwise approved by the Engineer.
- 4/ When establishing the Adjusted Job Mix Formula (AJMF) the percent passing the #8 (2.36 mm) sieve shall not be adjusted above the percentage stated on the table.
- 5/ When establishing the Adjusted Job Mix Formula (AJMF) the percent passing the #8 (2.36 mm) sieve shall not be adjusted below 34 percent.
- 6/ When the mixture is used as a binder, the maximum shall be increased by 0.5 percent passing."

Revise Article 1030.05(b) of the Standard Specifications to read:

(b) Volumetric Requirements. The target value for the air voids of the HMA shall be 4.0 percent, for IL-4.75 and SMA mixtures it shall be 3.5 percent and for Stabilized Subbase it shall be 3.0 percent at the design number of gyrations. The voids in the mineral aggregate (VMA) and voids filled with asphalt binder (VFA) of the HMA design shall be based on the nominal maximum size of the aggregate in the mix and shall conform to the following requirements.

	Voids in the Mineral Aggregate (VMA), % Minimum for Ndesign						
Mix Design	30	50	70	80	90		
IL-19.0		13.5	13.5		13.5		
IL-9.5		15.0	15.0				
IL-9.5FG		15.0	15.0				
IL-4.75 ^{1/}		18.5					
SMA-12.5 ^{1/2/5/}				17.0 ^{3/} /16.0 ^{4/}			
SMA-9.5 ^{1/2/5/}				17.0 ^{3/} /16.0 ^{4/}			
IL-19.0L	13.5						
IL-9.5L	15.0						

- 1/ Maximum draindown shall be 0.3 percent according to Illinois Modified AASHTO T 305.
- 2/ The draindown shall be determined at the JMF asphalt binder content at the mixing temperature plus 30°F.
- 3/ Applies when specific gravity of coarse aggregate is \geq 2.760.
- 4/ Applies when specific gravity of coarse aggregate is < 2.760.
- 5/ For surface course, the coarse aggregate can be crushed steel slag, crystalline crushed stone or crushed sandstone. For binder course, coarse aggregate shall be crushed stone (dolomite), crushed gravel, crystalline crushed stone, or crushed sandstone"

Revise the last paragraph of Article 1102.01 (a) (5) of the Standard Specifications to read:

"IL-4.75 and Stone Matrix Asphalt (SMA) mixtures which contain aggregate having absorptions greater than or equal to 2.0 percent, or which contain steal slag sand, shall have minimum surge bin storage plus haul time of 1.5 hours."

Revise the first and second paragraphs of Articles 1030.06(c)(2) of the Standard Specifications to read:

"(2) Personnel. The Contractor shall provide a QC Manager who shall have overall responsibility and authority for quality control. This individual shall maintain active certification as a Hot-Mix Asphalt Level II technician.

In addition to the QC Manager, the Contractor shall provide sufficient personnel to perform the required visual inspections, sampling, testing, and documentation in a timely manner. Mix designs shall be developed by personnel with an active certification as a Hot-Mix Asphalt Level III technician. Technicians performing mix design testing and plant sampling/testing shall maintain active certification as a Hot-Mix Asphalt Level I technician. The Contractor may provide a technician trainee who has successfully completed the Department's "Hot-Mix Asphalt Trainee Course" to assist in the activities completed by a Hot-Mix Asphalt Level I technician for a period of one year after the course completion date. The Contractor may also provide a Gradation Technician who has successfully completed the Department's "Gradation Technician Course" to run gradation tests only under the supervision of a Hot-Mix Asphalt Level II Technician. The Contractor shall provide a Hot-Mix Asphalt Density Tester who has successfully completed the Department's "Nuclear Density Testing" course to run all nuclear density tests on the job site."

Add Article 1030.06(d)(3) to the Standard Specifications to read:

"(3) The Contractor shall take possession of any Department unused backup or dispute resolution HMA mixture samples or density specimens upon notification by the Engineer. The Contractor shall collect the HMA mixture samples or density specimens from the location designated by the Engineer. The HMA mixture samples or density specimens may be added to RAP stockpiles according to Section 1031."

Revise the second paragraph of Articles 1030.07(a)(11) and 1030.08(a)(9) of the Standard Specifications to read:

"When establishing the target density, the HMA maximum theoretical specific gravity (Gmm) will be based on the running average of four available Department test results for that project. If less than four Gmm test results are available, an average of all available Department test results for that project will be used. The initial Gmm will be the last available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project.

CONTROL LIMITS								
Parameter	IL-19.0, IL-9.5FG, IL-9	IL-19.0L,	SMA- SMA	-	IL-4.75			
	Individual Test	Moving Avg. of 4	Individual Test	Moving Avg. of 4	Individual Test	Moving Avg. of 4		
% Passing: 1/								
1/2 in. (12.5 mm)	±6%	±4%	±6%	±4%				
3/8 in. (9.5mm)			±4%	±3%				
# 4 (4.75 mm)	±5%	±4%	±5%	±4%				
# 8 (2.36 mm)	±5%	±3%	±4%	±2%				
# 16 (1.18 mm)			±4%	±2%	±4%	±3%		
# 30 (600 µm)	±4%	± 2.5 %	±4%	± 2.5 %				
Total Dust Content # 200 (75 μm)	± 1.5 %	± 1.0 %			± 1.5 %	± 1.0 %		
Asphalt Binder Content	± 0.3 %	± 0.2 %	± 0.2 %	± 0.1 %	± 0.3 %	± 0.2 %		
Air Voids ^{2/}	± 1.2 %	± 1.0 %	± 1.2 %	± 1.0 %	± 1.2 %	± 1.0 %		
Field VMA ^{3/}	-0.7 %	-0.5 %	-0.7 %	-0.5 %	-0.7 %	-0.5 %		

Revise the following table and notes in Article 1030.09 (c) of the Standard Specifications to read:

1/ Based on washed ignition oven or solvent extraction gradation.

2/ The air voids target shall be a value equal to or between 3.2 % and 4.8 %.

3/ Allowable limit below minimum design VMA requirement.

Revise Article 1030.09(g)(2) of the Standard Specifications to read:

"(2)The Contractor shall complete split verification sample tests listed in the Limits of Precision table in Article 1030.09(h)(1)."

In the Supplemental Specifications, replace the revision for the end of the third paragraph of Article 1030.09(h)(2) with the following:

"When establishing the target density, the HMA maximum theoretical specific gravity (Gmm) will be the Department mix design verification test result."

Add after third sentence of Article 1030.09(b) to read:

"If the Contractor and Engineer agree the nuclear density test method is not appropriate for the mixture, cores shall be taken at random locations determined according to the QC/QA document "Determination of Random Density Test Site Locations". Core densities shall be determined using the Illinois Modified AASHTO T 166 or T 275 procedure."

	Breakdown/Intermediate Roller (one of the following)	Final Roller (one or more of the following)	Density Requirement
IL-9.5, IL-9.5FG, IL-19.0 ^{1/}	V_D , P , T_B , 3W, O_T , O_B	$V_{S}, T_{B}, T_{F,}O_{T}$	As specified in Section 1030
IL-4.75 and SMA $_{\rm 3/4/}$	Т _{в,} 3W, О _Т	T _F , 3W	As specified in Section 1030
Mixtures on Bridge Decks ^{2/}	Τ _Β	T _F	As specified in Articles 582.05 and 582.06.

Revise Table 1 and Note 4/ of Table 1 in Article 406.07(a) of the Standard Specifications to read:

"4/ The Contractor shall provide a minimum of two steel-wheeled tandem rollers (T _B), and/or three-wheel (3W) rollers for breakdown, except one of the (T_B) or (3W) rollers shall be 84 inches (2.14 m) wide and a weight of 315 pound per linear inch (PLI) (5.63 kg/mm) and one of the (T_B) or (3W) rollers can be substituted for an oscillatory roller (O_T). T_F rollers shall be a minimum of 280 lb/in. (50 N/mm). The 3W and T_B rollers shall be operated at a uniform speed not to exceed 3 mph (5 km/h), with the drive roll for T_B rollers nearest the paver and maintain an effective rolling distance of not more than 150 ft (45 m) behind the paver."

Add the following after the fourth paragraph of Article 406.13 (b):

"The plan quantities of SMA mixtures shall be adjusted using the actual approved binder and surface Mix Design's G_{mb}."

Revise first paragraph of Article 1030.10 of the Standard Specifications to read:

"A test strip of 300 ton (275 metric tons), except for SMA mixtures it will be 400 ton (363 metric ton), will be required for each mixture on each contract at the beginning of HMA production for each construction year according to the Manual of Test Procedures for Materials "Hot Mix Asphalt Test Strip Procedures". At the request of the Producer, the Engineer may waive the test strip if previous construction during the current construction year has demonstrated the constructability of the mix using Department test results."

Revise fourth paragraph of Article 1030.10 of the Standard Specifications to read:

"When a test strip is constructed, the Contractor shall collect and split the mixture according to the document "Hot-Mix Asphalt Test Strip Procedures". The Engineer, or a representative, shall deliver split sample to the District Laboratory for verification testing. The Contractor shall complete mixture tests stated in Article 1030.09(a). Mixture sampled shall include enough material for the Department to conduct mixture tests detailed in Article 1030.09(a) and in the document "Hot-Mix Asphalt Mixture Design Verification Procedure" Section 3.3. The mixture test results shall meet the requirements of Articles 1030.05(b) and 1030.05(d), except Hamburg wheel tests will only be conducted on High ESAL mixtures during production."

HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1)

Effective: January 1, 2019 Revised: December 1, 2021

Add to Article 1030.05 (d)(3) of the Standard Specifications to read:

" During mixture design, prepared samples shall be submitted to the District laboratory by the Contractor for verification testing. The required testing, and number and size of prepared samples submitted, shall be according to the following tables.

High ESAL – Required Samples for Verification Testing		
Mixture	Hamburg Wheel and I-FIT Testing ^{1/2/}	
Binder	total of 3 - 160 mm tall bricks	
Surface total of 4 - 160 mm tall bricks		

Low ESAL – Required Samples for Verification Testing		
Mixture	I-FIT Testing ^{1/2/}	
Binder	1 - 160 mm tall brick	
Surface	2 - 160 mm tall bricks	

- 1/ The compacted gyratory bricks for Hamburg wheel and I-FIT testing shall be 7.5 ± 0.5 percent air voids.
- 2/ If the Contractor does not possess the equipment to prepare the 160 mm tall brick(s), twice as many 115 mm tall compacted gyratory bricks will be acceptable.

Revise the fourth paragraph of Article 1030.10 of the Standard Specifications to read:

"When a test strip is not required, each HMA mixture shall still be sampled on the first day of production: I-FIT and Hamburg wheel testing for High ESAL; I-FIT testing for Low ESAL. Within two working days after sampling the mixture, the Contractor shall deliver gyratory cylinders to the District laboratory for Department verification testing. The High ESAL mixture test results shall meet the requirements of Articles 1030.05(d)(3) and 1030.05(d)(4). The Low ESAL mixture test results shall meet the requirements of Article 1030.05(d)(4). The required number and size of prepared samples submitted for the Hamburg wheel and I-FIT testing shall be according to the "High ESAL - Required Samples for Verification Testing" table in Article 1030.05(d)(3) above." Add the following to the end of Article 1030.10 of the Standard Specifications to read:

"Mixture sampled during first day of production shall include approximately 60 lb (27 kg) of additional material for the Department to conduct Hamburg wheel testing and approximately 80 lb (36 kg) of additional material for the Department to conduct I-FIT testing. Within two working days after sampling, the Contractor shall deliver prepared samples to the District laboratory for verification testing. The required number and size of prepared samples submitted for the Hamburg wheel and I-FIT testing shall be according to the "High ESAL - Required Samples for Verification Testing" table in Article 1030.05(d)(3) above."

KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)

Effective: January 22, 2003 Revised: August 10, 2017

The Contractor shall provide the necessary traffic control devices to warn the public and to delineate the work zone as required in these Special Provisions, the Standard Specifications, the State Standards, and the District Details.

Arterial lane closures shall be in accordance with the Standard Specifications, Highway Standards, District Details, and the direction of the Engineer. The Contractor shall request and gain approval from the Engineer seventy–two (72) hours in advance of all long-term (24 hrs. or longer) lane closures.

Arterial lane closures not shown in the staging plans will not be permitted during **peak traffic volume hours**.

Peak traffic volume hours are defined as weekdays (Monday through Friday) from 6:00 AM to 8:30 AM and 4:30 PM to 6:00 PM.

Private vehicles shall not be parked in the work zone. Contractor's equipment and/or vehicles shall not be parked on the shoulders or in the median during non-working hours. The parking of equipment and/or vehicles on State right-of-way will only be permitted at locations approved by the Engineer in accordance with Articles 701.08 and 701.11 of the Standard Specifications.

Should the Contractor fail to completely open and keep open all the traffic lanes to traffic in accordance with the limitations specified above, the Contractor shall be liable to the Department for the amount of:

One lane or ramp blocked = \$1,000.00

Two lanes blocked = \$2,500.00

Not as a penalty but as liquidated and ascertained damages for each and every 15 minute interval or a portion thereof that a lane is blocked outside the allowable time limitations. Such damages may be deducted by the Department from any monies due the Contractor. These damages shall apply during the contract time and during any extensions of the contract time.

RECLAIMED ASPHALT PAVEMENT FOR NON-POROUS EMBANKMENT AND BACKFILL (D1)

Effective: April 1, 2001 Revised: January 1, 2007

Add the following sentence to Article 1004.05 (a) of the Standard Specifications:

"Reclaimed Asphalt Pavement (RAP) may be used as aggregate in Non-porous Granular Embankment and Backfill. The RAP material shall be reclaimed asphalt pavement material resulting from the cold milling or crushing of an existing hot-mix bituminous concrete pavement structure, including shoulders. RAP containing contaminants such as earth, brick, concrete, sheet asphalt, sand, or other materials identified by the Department will be unacceptable until the contaminants are thoroughly removed.

Add the following sentence to Article 1004.05 (c)(2) of the Standard Specifications:

"One hundred percent of the RAP when used shall pass the 3 inch (75 mm) sieve. The RAP shall be well graded from coarse to fine. RAP that is gap-graded or single-sized will not be accepted."

TEMPORARY INFORMATION SIGNING

Effective: November 13, 1996 Revised: January 29, 2020

Description.

This work shall consist of furnishing, installing, maintaining, relocating for various states of construction and eventually removing temporary informational signs. Included in this item may be ground mount signs, skid mount signs, truss mount signs, bridge mount signs, and overlay sign panels which cover portions of existing signs.

Materials.

Materials shall be according to the following Articles of Section 1000 - Materials:

	ltem	Article/Section
a.)	Sign Base (Note 1)	1090
b.)	Sign Face (Note 2)	1091
c.)	Sign Legends	1091
d.)	Sign Supports	1093
e.)	Overlay Panels (Note 3)	1090.02

- Note 1. The Contractor may use 5/8 inch (16 mm) instead of 3/4 inch (19 mm) thick plywood.
- Note 2. The sign face material shall be in accordance with the Department's Fabrication of Highway Signs Policy.
- Note 3. The overlay panels shall be 0.08 inch (2 mm) thick.

GENERAL CONSTRUCTION REQUIREMENTS

Installation.

The sign sizes and legend sizes shall be verified by the Contractor prior to fabrication.

Signs which are placed along the roadway and/or within the construction zone shall be installed according to the requirements of Article 701.14 and Article 720.04. The signs shall be 7 ft (2.1 m) above the near edge of the pavement and shall be a minimum of 2 ft (600 mm) beyond the edge of the paved shoulder. A minimum of two (2) posts shall be used.

The attachment of temporary signs to existing bridges, sign structures or sign panels shall be approved by the Engineer. Any damage to the existing signs and/or structures due to the Contractor's operations shall be repaired or signs replaced, as determined by the Engineer, at the Contractor's expense.

Method of Measurement.

This work shall be measured for payment in square feet (square meters) edge to edge (horizontally and vertically).

All hardware, posts or skids, supports, bases for ground mounted signs, connections, which are required for mounting these signs will be included as part of this pay item.

Basis Of Payment.

This work shall be paid for at the contract unit price per square foot (square meter) for TEMPORARY INFORMATION SIGNING.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either "uncontaminated soil", hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Saunders Road:

- All excavation, full width of construction corridor LT and RT of centerline of Saunders Road from Station 6+10 to Station 10+59. This material meets the criteria of Article 669.05(a)(1) and shall be managed in accordance to Article 669.05. Potential contaminants of concern sampling parameters: PNAs, Metals.
- All excavation, full width of construction corridor LT and RT of centerline of Saunders Road from Station 34+75 to Station 39+67. This material meets the criteria of Article 669.05(a)(1) and shall be managed in accordance to Article 669.05. Potential contaminants of concern sampling parameters: Mercury (CWCA).
- All excavation, full width of construction corridor LT and RT of centerline of Saunders Road from Station 60+38 to Station 64+29. This material meets the criteria of Article 669.05(a)(1) and shall be managed in accordance to Article 669.05. Potential contaminants of concern sampling parameters: PNAs, Metals.

 All excavation, full width of construction corridor LT and RT of centerline of Saunders Road from Station 74+72 to the northern limits of construction. This material meets the criteria of Article 669.05(a)(5) and shall be managed in accordance to Article 669.05. Potential contaminants of concern sampling parameters: Naphthalene (CWCA), Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None**

CLEARING AND GRUBBING

This work shall include all labor, material, and equipment necessary to remove and dispose of all obstructions marked by the Engineer in accordance with Section 201 and 202 of the Standard Specifications and as specified herein.

Clearing shall consist of the removal and disposal of all obstructions such as fences, walls, foundations, buildings, accumulations of rubbish of whatever nature and existing structures, the removal of which is not otherwise provided for in Article 501.05; all logs, shrubs, bushes, saplings, grass, weeds, other underbrush vegetation and stumps of a diameter less than 6 in.

All saplings, bushes and roots shall be removed to a depth of not less than 12 in. below the elevation of the subgrade, the finished grade surface, or the ground line, and at least below the bottom of the subbase material.

Materials shall be disposed of off-site according to Article 202.03 of the Standard Specifications.

This work will be measured in place and paid for at the contract unit price per square yard for CLEARING AND GRUBBING, which shall include all labor, material, and equipment required to complete the work as specified herein.

DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED OR RECONSTRUCTED

This work shall consist of adjusting or reconstructing drainage and utility structures to proposed finish grade at locations shown on the Engineering plans or as directed by the Engineer in accordance with Section 602 of the Standard Specifications and as specified herein.

All adjustments or reconstructions shall be made with existing frames and grates or lids unless otherwise specified.

Prior to making the final grade adjustment, all joint surfaces shall be made free of dirt, stones, and debris by wire brushing each surface. Broken concrete or other construction debris shall not be used to shim the adjusting rings or frame. The maximum total height of the adjusting rings shall not exceed eight (8) inches.

When a new precast concrete cone section or flat top slab is required to complete the work, it shall be considered a reconstruction.

No more than two precast concrete adjusting rings with eight-inch maximum height adjustment shall be allowed. A minimum one 2" ring shall be installed on new structures. All adjustment rings less than 2" shall be HDPE rings. Only one HDPE ring may be used within the precast tolerances. Only precast concrete or HDPE adjustment rings are permitted. A ½"x3.5" mastic shall be used between all frames, rings, and structures. Mortar shall be used around rings, but not between them. A bed of mortar can be used on a cone or flat top of a structure.

This work will be measured in place and paid for at the contract unit price per each for DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED or DRAINAGE & UTILITY STRUCTURE TO BE RECONSTRUCTED; regardless to the type of structure or type of frame and lid or grate, which shall include setting or resetting the frame with grate or lid, and excavation and backfill, except excavation in rock. The unit price shall include all labor, material, and equipment required to complete the work as specified herein.

DRAINAGE STRUCTURE TO BE REMOVED

This work shall include all labor, material, and equipment necessary to remove and dispose of existing drainage manholes, catch basins, inlets, and other drainage structures in accordance with Section 602 of the Standard Specifications and as specified herein.

If a new structure is not to be installed at the same location, excavated areas around the structure shall be backfilled with existing spoils on site or from trench backfill. Trench backfill will be paid for separately.

This work will be measured in place for at the contract unit price per each for DRAINAGE STRUCTURE TO BE REMOVED, which shall include all labor, material, and equipment required to complete the work as specified herein.

EXPOSED AGGREGATE SURFACE

This work shall include all labor, material, and equipment necessary to place 6-inch or 8-inch portland cement concrete driveway pavement with exposed aggregate on a compacted subbase. This work shall be performed in accordance with Sections 311 and 423 of the Standard Specifications and as specified herein.

Driveways shall be placed on 4 inches of material conforming to Subbase Granular Material, Type B. Expansion joints ³/₄" thick shall be placed at intervals of not more than 50 feet.

Driveways should be sealed with a 100% pure acrylic low VOC concrete sealer.

The Contractor shall submit a sample aggregate for each respective driveway for approval prior to ordering the concrete mix.

This work will be measured in place for at the contract unit price per square foot for EXPOSED AGGREGATE SURFACE, which shall include all labor, material, and equipment required to complete the work as specified herein.

FIRE HYDRANTS TO BE ADJUSTED

This work shall include all labor, material, and equipment necessary to adjust existing fire hydrants to the proposed ground elevations shown on the plans in accordance with Section 564 of the Standard Specifications and as specified herein. Adjustments of adjacent water valves shall be paid for separately.

This work will be measured in place for at the contract unit price per each for FIRE HYDRANTS TO BE ADJUSTED, which shall include all labor, material, and equipment required to complete the work as specified herein.

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)

This work shall consist of the adjustment of inlets, catch basins, valve vaults and manholes at locations as directed by the Engineer in the field. This work shall be completed in accordance with the applicable portions of Section 602, 603 and 604 of the Standard Specifications as well as the District One Standard Detail BD-8 "Details for Frames and Lids Adjustment with Milling."

The existing pavement around each structure to be adjusted shall be removed by a straight, sawcut joint.

All structures requiring frame and lid adjustment shall be cleaned in accordance with Article 602.15.

After adjustment is complete, the pavement around the structure shall be filled with Class PP-2 concrete to the elevation of the surface of the existing base course or the binder course. The pavement being replaced will not be paid for separately but considered included in the cost of the structure being adjusted.

The work will be paid for at the contract unit price per EACH for FRAMES AND LIDS TO BE ADJUSTED (SPECIAL), which shall include all labor, material, and equipment required to complete the work as specified herein.

HOT-MIX ASPHALT DRIVEWAY PAVEMENT

This work shall consist of placing hot-mix asphalt driveway pavement in accordance with the applicable portions of Section 202, 355 and 406 of the Standard Specifications.

Driveway removal and any excavation required in order to install the driveway to the necessary depth will be done in accordance with the applicable portions of Sections 202 and 440 of the Standard Specifications and will be considered included in the cost of DRIVEWAY PAVEMENT REMOVAL.

The existing aggregate base will be graded and compacted prior to the placement of hotmix asphalt. This work will be considered included in the cost of HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6" and HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8".

The areas noted in the plans for this item shall be restored with 2" Hot-Mix Asphalt Surface Course, IL-9.5, Mix "D", N50 and 4" or 6" of Hot-Mix Asphalt Binder Course, IL-19.0, N50.

When driveways are removed, access to the property shall be maintained with temporary aggregate in accordance with the pay item TEMPORARY ACCESS (PRIVATE OR COMMERCIAL ENTRANCE).

This work will be paid for at the contract unit price per square yard for HOT-MIX ASPHALT DRIVEWAY PAVEMENT, of the thickness specified, which includes all labor, material and equipment to complete this work as shown on the plans and as described herein.

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

This item consists of the removal of the existing hot-mix asphalt surface necessary to provide the profile of the proposed pavement cross section in accordance with Section 440 of Standard Specifications, except as modified herein.

The anticipated typical removed depth is to be 2 ³/₄ inches. However, the removal depth may vary according to the existing conditions encountered and may therefore include full width removal of 3 inches or more if such conditions require.

Milling shall be done in sufficient passes to profile the roadway to the proposed crown slope and elevations. The anticipated milling depth required to achieve the proposed road profile is between zero (0") and six inches (6"). Milling to achieve the proposed profile shall be included in the cost of this item. Sufficient milling or grinding passes shall be made over the existing pavement so that all irregularities and high spots are eliminated from the pavement's surface before it is overlaid with new material. This item shall include the removal of any concrete or stone base that is necessary to achieve the required section and the shaping and compacting of any aggregate base that is exposed during milling operations.

The equipment and construction methods for this item shall conform to Article 440.03 of the Standard Specifications. Hot-Mix Asphalt Surface Removal will be measured in place and the area computed in square yards for the total depth of material removed. The area measured will be paid for only once regardless of the number of passes needed to remove the material.

This work will be paid for at the contract unit price per square yard for HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH, which includes all labor, material and equipment to complete this work as shown on the plans and as described herein.

MAILBOX REMOVE AND REPLACE

This work shall consist of removing and replacing mailboxes at the final locations shown in the plans, relocating during construction, and in accordance with Article 107.20 of the Standard Specifications, and with the following provisions.

The replacement mailbox shall comply with the USPS residential mailbox standard and be installed on a new 4"x4" square or 4 $\frac{1}{2}$ " diameter round treated wood post, a steel U-channel post, or another method approved by the Engineer. The new post shall be embedded into the ground no more than 24", set in portland cement concrete, and shall be mounted at a height of 41" to 45" from finished ground level to the bottom of the mailbox. The face of the mailbox shall be located 6" to 12" from the edge of the roadway shoulder.

The existing post shall be removed and disposed of in Accordance with Article 202.03 of the Standard Specifications. The resulting hole from the removal of the mailbox shall be backfilled with suitable excavated material as approved by the Engineer.

Relocating the mailbox during construction operations to temporary locations will not be paid for separately, but shall be considered as included in the contract. No additional compensation will be allowed as stipulated in Article 107.20 of the Standard Specifications.

This work will be measured in place and paid for at the contract unit price per each for MAILBOX REMOVE AND REPLACE, which shall include all labor, material, and equipment required to complete the work as specified herein.

PROTECTION OF EXISTING TREES

The Contractor shall be responsible for taking measures to minimize damage to the tree limbs, tree trunks, and tree roots at each work site. All such measures shall be included in the contract price for other work except that payment will be made for TEMPORARY FENCE, TREE TRUNK PROTECTION, TREE ROOT PRUNING, and TREE PRUNING.

The Contractor shall coordinate with the Village prior to the start of construction to do a walk through and determine which trees or shrubs are to be protected, method of protection, and determine type of work to minimize damage to the tree.

All work, materials and equipment shall conform to Section 201 and 1081 of the Standard Specifications except as modified herein.

- A. Earth Saw Cut of Tree Roots (Root Pruning):
 - 1. Whenever proposed excavation falls within a drip-line of a tree, the Contractor shall:
 - a. Root prune 6-inches behind and parallel to the proposed edge of trench a neat, clean vertical cut to a minimum depth directed by the Engineer through all affected tree roots.
 - b. Root prune to a maximum width of 4-inches using a reciprocating saw blade for cutting tree roots or similar cutting machine. Trenching machines will not be permitted.
 - c. Exercise care not to cut any existing utilities.
 - d. If during construction it becomes necessary to expose tree roots which have not been precut, the Engineer shall be notified and the Contractor shall provide a clean, vertical cut at the proper root location, nearer the tree trunk, as necessary, by means of hand-digging and trimming with chain saw or hand saw. Ripping, shredding, shearing, chopping, or tearing will not be permitted.
 - e. Top Pruning: When thirty percent (30%) or more of the root zone is pruned, an equivalent amount of the top vegetative growth or the plant material shall be pruned off within one (1) week following root pruning.

- 2. Whenever curb and gutter is removed for replacement, or excavation for removal of or construction of a structure is within the drip line/root zone of a tree, the Contractor shall:
 - a. Root prune 6-inches behind the curbing so as to neatly cut the tree roots.
 - b. Depth of cut shall be 12 inches for curb removal and replacement and 24 inches for structural work. Any roots encountered at a greater depth shall be neatly saw cut at no additional cost.
 - c. Locations where earth saw cutting of tree roots is required will be marked in the field by the Engineer.
- 3. All root pruning work is to be performed through the services of a licensed arborist to be approved by the Engineer.

Root pruning will be paid for at the contract unit price each for TREE ROOT PRUNING, which price shall be payment for all labor, materials, and equipment.

Tree limb pruning will be paid for at the contract unit price per each for TREE PRUNING (1 TO 10 INCH DIAMETER) and/or TREE PRUNING (OVER 10 INCH DIAMETER), which price shall include labor, materials, and equipment.

- B. Temporary Fence:
 - 1. The Contractor shall erect a temporary fence around all trees within the construction area to establish a "tree protection zone" before any work begins or any material is delivered to the jobsite. No work is to be performed (other than root pruning), materials stored, or vehicles driven or parked within the "tree protection zone".
 - 2. The exact location and establishment of the "tree protection zone" fence shall be approved by the Engineer prior to setting the fence.
 - 3. The fence shall be erected on three sides of the tree at the drip-line of the tree or as determined by the Engineer.
 - 4. All work within the "tree protection zone" shall have the Engineer's prior approval. All slopes and other areas not regarded should be avoided so that unnecessary damage is not done to the existing turf, tree root system ground cover.
 - 5. The grade within the "tree protection zone" shall not be changed unless approved by the Engineer prior to making said changes or performing the work.

The fence shall be similar to wood lath snow fence (48 inches high), plastic poly-type or and other type of highly visible barrier approved by the Engineer. This fence shall be properly maintained and shall remain up until final restoration unless the Engineer directs removal otherwise. Tree fence shall be supported using T-Post style fence posts. **Utilizing re-bar as a fence post will not be permitted.**

Temporary fence will be paid for at the contract unit price per foot for TEMPORARY FENCE, which price shall include furnishing, installing, maintaining, and removing.

- C. Tree Trunk Protection:
 - 1. The Contractor shall erect trunk protection around all trees within the construction area to prevent damage to the trunk of the tree when temporary fence is not an option before any work begins or any material is delivered to the jobsite. No work is to be performed (other than root pruning), materials stored, or vehicles driven or parked within the "tree protection zone".
 - 2. The 2 inch x 8 inch x 8 foot boards shall be banded continuously around the trunk of each tree to prevent scarring of the trees shown on the plans or designated by the Engineer.
 - 3. Multi-stem trees, saplings, and shrubs to be protected within the area of construction, temporary fence may be used for trunk protection.

Tree trunk protection will be paid for at the contract unit price per each for TREE TRUNK PROTECTION), which price shall include materials, installation, and removal.

- C. Tree Limb Pruning:
 - 1. The Contractor shall inspect the work site in advance and arrange with the Village to have any tree limbs pruned that might be damaged by equipment operations at least one week prior to the start of construction. Any tree limbs that are broken by construction equipment after the initial pruning must be pruned correctly within 72 hours.
 - 2. Top Pruning: When thirty percent (30%) or more of the root zone of a tree is pruned, an equivalent amount of the top vegetative growth or the plant material shall be pruned off within one (1) week following root pruning.

Tree limb pruning will be paid for at the contract unit price per each for TREE PRUNING (1 TO 10 INCH DIAMETER) and/or TREE PRUNING (OVER 10 INCH DIAMETER), which price shall include labor, materials, and equipment.

- D. Removal of Driveway Pavement and Sidewalk:
 - 1. In order to minimize the potential damage to the tree root system(s), the Contractor will not be allowed to operate any construction equipment or machinery within the "tree protection zone" located between the curb or edge of pavement and the right-of-way property line.
 - 2. Sidewalk to be removed in the areas adjacent to the "tree protection zones" shall be removed with equipment operated from the street pavement. Removal shall be done by excavation equipment, or by hand, or a combination of these methods. The method of removal shall be approved by the Engineer prior to commencing any work.
 - 3. Any pavement or pavement related work that is removed shall be immediately disposed of from the area and shall not be stockpiled or stored within the parkway area under any circumstances.

E. Backfilling:

1. Prior to placing the topsoil and/or sod, in areas outside the protection zone, the existing ground shall be disked to a depth no greater than one (1"), unless otherwise directed by the Engineer. No grading will be allowed within the dripline of any tree unless directed by the Engineer.

F. Damages:

- 1. In the event that a tree not scheduled for removal is injured such that potential irreparable damage may ensure, as determined by the Roadside Development Unit, the Contractor shall be required to remove the damage tree and replace it on a three to one (3:1) basis, at his own expense. The Roadside Development Unit will select replacement trees from the pay items already established in the contract.
- 2. The Contractor shall place extreme importance upon the protection and care of trees and shrubs which are to remain during all times of this improvement. It is of paramount importance that the trees and shrubs which are to remain are adequately protected by the Contractor and made safe from harm and potential damage from the operations and construction of this improvement. If the Contractor is found to be in violation of storage or operations within the "tree protection zone" or construction activities not approved by the Engineer, a penalty shall be levied against the Contractor with the monies being deducted from the contract. The amount of the penalty shall be two hundred fifty dollars (\$250.00) per occurrence per day.

RAISED REFLECTIVE PAVEMENT MARKER

Description: This work shall consist of placing permanent raised reflective pavement markers.

Materials: The materials shall meet the requirements of Article 781.02 of the "Standard Specifications".

General: The work shall be performed according to Section 781 of the "Standard Specifications" and the following: Sawcutting the pavement for the installation of raised pavement markers shall be done by means of dry cutting the pavement. The Contractor shall maintain the pavement and the surrounding area in clean, dry condition and shall vacuum the dust and millings from the pavement surface. The method of cutting the pavement may be altered by the Contractor provided the pavement surface and the surrounding area are cleaned to the satisfaction of the Engineer. Alternate methods of cutting the pavement shall be approved by the Engineer.

Basis of Payment: This work will be paid for at the contract unit price per each for RAISED REFLECTIVE PAVEMENT MARKER. The unit price shall include all costs for sawing and cleaning the pavement, regardless of the sawing method used. The unit price shall also include all equipment, materials and labor required to install the raised reflective pavement markers.

REMOVE AND REINSTALL BRICK PAVER

This work shall include all labor, material, and equipment necessary to remove, store, secure, and reinstall brick pavers as directed by the Engineer and as specified herein.

All references to brick pavers throughout the contract documents shall be understood to mean all specialty materials, including, but not limited to, brick pavers, raised aggregate, slate, flagstone, and all non-portland cement or asphalt sidewalks or driveways.

No additional compensation will be provided to dispose of damaged bricks or to purchase replacement bricks due to damaged or missing bricks. The existing brick pavers that are to be reused shall be carefully removed and securely stored to prevent loss, theft, or damage. At the discretion of the Contractor, bricks can be stored off-site to prevent theft or damage.

At the discretion of the Engineer, the Contractor may salvage the existing brick edging. If the existing brick edging is damaged or considered unacceptable, the Contractor shall furnish and install new edging of sufficient size to prevent the brick pavers from "rolling" or losing their bond. The subbase material shall be compacted with a vibratory compactor and additional aggregate material installed, if required, to ensure positive drainage is achieved prior to resetting the brick pavers.

The contractor shall furnish and install mason and/or polymeric sand, whichever is applicable to match existing materials, after the brick pavers have been set to grade. After a sufficient amount of sand has been applied to the brick paver surface, the area shall be mechanically tamped to ensure a tight bond. The application of sand may need to be repeated until the desired results are achieved to the satisfaction of the Engineer.

The cost of any additional materials and necessary labor required to comply with the above provisions shall be considered as included in the unit bid prices of this item, and no additional compensation shall be allowed.

This work will be measured in place and paid for at the contract unit price per square feet for REMOVE AND REINSTALL BRICK PAVER, which shall include all labor, material, security, storage, and equipment required to complete the work as specified herein.

REMOVE AND RELOCATE SIGN PANEL

This work shall include all labor, material, and equipment necessary to remove, store, and reerect existing regulatory and warning sign panel assembly and posts in accordance with Section 724 of the Standard Specifications and as specified herein.

The Contractor shall store the existing sign panel assembly in a location that won't promote vandalism or theft. The existing post shall be disposed of properly. The Contractor shall replace, at no additional cost to the Owner, any sign panel assembly which has been vandalized, stolen or damaged due to neglect, misconduct or poor workmanship.

A new metal post, type A shall be included in the cost of this item for all signs to be removed and reset. The metal post shall be in accordance with Section 729 of the Standard Specifications. The sign panel assembly and post shall be installed by a method approved by the Engineer and in accordance with application sections of the Manual on Uniform Traffic Control Devices. Construction equipment such as a backhoe or skid steer shall not be used to drive posts into the ground.

This work will be measured in place and paid for at the contract unit price per each for REMOVING AND RESETTING STREET SIGNS, which shall include all labor, material, and equipment required to complete the work as specified herein.

REMOVING AND RESETTING STREET SIGNS

This work shall include all labor, material, and equipment necessary to remove, store, and reerect existing decorative street signs in accordance with Section 724 of the Standard Specifications and as specified herein.

The Contractor shall store the existing street sign in a location that won't promote vandalism or theft. The Contractor shall replace, at no additional cost to the Owner, any street sign which has been vandalized, stolen or damaged due to neglect, misconduct or poor workmanship.

The street sign shall be installed by a method approved by the Engineer and in accordance with application sections of the Manual on Uniform Traffic Control Devices. Construction equipment such as a backhoe or skid steer shall not be used to drive posts into the ground.

This work will be measured in place and paid for at the contract unit price per each for REMOVING AND RESETTING STREET SIGNS, which shall include all labor, material, and equipment required to complete the work as specified herein.

STORM SEWERS, WATER MAIN QUALITY

This work consists of constructing storm sewer to meet water main standards, as required by the IEPA or when otherwise specified. The work shall be performed in accordance withapplicable parts of Section 550 of the Standard Specifications, applicable sections of the currentedition of the IEPA Regulations (Title 35 of the Illinois Administrative Code, Subtitle F, Chapter II, Section 653.119), the applicable sections of the current edition of the "Standard Specifications for Water and Sewer Main Construction in Illinois", and as herein specified.

This provision shall govern the installation of all storm sewers which do not meet IEPA criteria for separation distance between storm sewers and water mains. Separation criteria for storm sewers placed adjacent to water mains and water service lines are as follows:

- (1) Water mains and water service lines shall be located at least 10 feet (3.05 meters) horizontally from any existing or proposed drain, storm sewer, sanitary sewer, or sewer service connections.
- (2) Water mains and water service lines may be located closer than 10 feet (3.05 meters) to a sewer line when:
 - (a) Local conditions prevent a lateral separation of 10 feet (3.05 meters); and

- (b) The water main or water service invert is 18 inches (460 mm) above the crown of the sewer; and
- (c) The water main or water service is either in a separate trench or in the same trenchon an undisturbed earth shelf located to one side of the sewer.
- (3) A water main or water service shall be separated from a sewer so that its invert is a minimum of 18 inches (460 mm) above the crown of the drain or sewer whenever water mains or services cross storm sewers, sanitary sewers or sewer service connections. The vertical separation shall be maintained for that portion of the water main or water services located within 10 feet (3.05 meters) horizontally of any sewer or drain crossed.

When it is impossible to meet (1), (2) or (3) above, the storm sewer shall be constructed of concrete pressure pipe, slip-on or mechanical joints ductile iron pipe, or PVC pipe equivalent to water main standards of construction. Construction shall extend on each side of the crossing until the perpendicular distance from the water main or water service to the sewer or drain line isat least 10 feet (3.05 meters). Storm sewer meeting water main requirements shall be constructed of the following pipe materials:

Concrete Pressure Pipe

Concrete pressure pipe shall conform to the latest ANSI/AWWA C300, C301, C302, orC303.

Joints shall conform to Article 41-2.07B of the "Standard Specifications for Water and Sewer Main Construction in Illinois."

Ductile Iron Pipe

Ductile Iron pipe shall conform to ANSI A 21.51 (AWWA C151), class or thickness designed per ANSI A 21,50 (AWWA C150), tar (seal) coated and/or cement lined per ANSI A 21.4 (AWWA C104), with a mechanical or rubber ring (slip seal or push on) joints.

Joints for ductile iron pipe shall be in accordance with the following applicable specifications.

- 1. Mechanical Joints AWWA C111 and C600
- 2. Push-On Joints AWWA C111 and C600

Plastic Pipe

Plastic pipe shall be marked with the manufacturer's name (or trademark); ASTM or AWWA specification; Schedule Number, Dimension Ratio (DR) Number or Standard Dimension Ratio (SDR) Number; and Cell Class. The pipe and fittings shall also meet NSF Standard 14, and bear the NSF seal of approval. Fittings shall be compatible with the type of pipe used. The plastic pipe options shall be in accordance with the following:

- 1. Polyvinyl Chloride (PVC) conforming to ASTM Standard D 1785. Schedule 80 is theminimum required for all pipe sizes, except when the pipe is to be threaded, and thenit shall be Schedule 120. It shall be made from PVC compound meeting ASTM D 1784, Class 12454.
- 2. Polyvinyl Chloride (PVC) conforming to ASTM D 2241. A minimum wall thickness of SDR 26 is required for all pipe sizes (<u>Note</u>: The lower the SDR number, the higher the wall thickness and pressure rating). It shall be made from PVC compound meeting ASTM D 1784, Class 12454.
- 3. Chlorinated Polyvinyl Chloride (CPVC) conforming to ASTM f 441. A minimum of Schedule 80 is required for all pipe sizes. Threaded joints are not allowed. It shall be made from CPVC compound meeting ASTM D 1784, Class 23447.
- 4. Chlorinated Polyvinyl Chloride (CPVC) conforming to ASTM F 442. A minimum wall thickness of SDR 26 is required for all pipe sizes (<u>Note</u>: The lower the SDR number, the higher the wall thickness and pressure rating). It shall be made from CPVC compound meeting ASTM D 1784.
- 5. Polyvinyl Chloride (PVC) conforming to ANSI/AWWA C900. A minimum of wall thickness of DR 25 is required for all pipe sizes (Note: The lower the DR number, thehigher the wall thickness and pressure rating). It shall be made from PVC compoundmeeting ASTM D 1784, Class 12454.
- 6. Polyvinyl Chloride (PVC) conforming to ANSI/AWWA C905. A minimum of wall thickness of DR 26 is required for all pipe sizes (Note: The lower the DR number, thehigher the wall thickness and pressure rating). It shall be made from PVC compoundmeeting ASTM D 1784, Class 12454.

Joining of plastic pipe shall be by push-on joint, solvent welded joint, heat welded joint, flanged joint, or threaded joint, in accordance with the pipe manufacturer's instructions and industry standards. Special precautions shall be taken to insure clean, dry contact surfaces when making solvent or heat welded joints. Adequate setting time shall be allowed for maximum strength.

Elastotmeric seals (gaskets) used for push-on joints shall comply with ASTM F477.

Solvent cement shall be specific for the plastic pipe material and shall comply with ASTM D 2564 (PVC) or ASTM F 493 (CPVC) and be approved by NSF.

For water-sewer line crossings <u>only</u>, storm sewer meeting water main requirements may also beconstructed of reinforced concrete sewer pipe. The pipe shall conform to ASTM C 76 with a joint and rubber gasket meeting ASTM C 443. The joint shall meet the leakage performance test in ASTM C 443. The pipe manufacturer must demonstrate to Illinois Department of Transportation personnel that the joints pass the leakage performance test prior to installation of the pipe. The pipe class shall meet the requirements of Section 550 of the *Standard Specifications for Road and Bridge Construction*.

This work will be measured and paid for at the contract unit price per foot (meter) for STORM SEWER (WATER MAIN QUALITY PIPE) of the diameter and type specified.

STUMP REMOVAL

This work shall consist of the removal and satisfactory disposal of stumps. All excess chips and debris from this operation shall be removed and disposed of outside the limits of the contract. This work will be done in accordance with Section 201 of the Standard Specifications for tree removal, except that stumps are to be removed a minimum of six (6) inches below the natural surface of the ground.

This work will be measured in place and paid for at the contract unit price per Each for STUMP REMOVAL, which price shall include all labor, material, and equipment required to complete the work as specified herein.

SUPPLEMENTAL WATERING

This work will include watering sod, trees, shrubs, vines, and perennials at the rates specified and as directed by the Engineer.

<u>Schedule:</u> Watering will only begin after the successful completion of all period of establishment requirements. However, if plant material requires additional watering due to extreme weather (drought/high temperatures) supplemental watering may be used to water during the period of establishment.

Water trees, shrubs, and vines every 7 days throughout the growing season (April 1 to November 30). Water perennials, plugs, and sod a minimum of twice a week. The Engineer may direct the Contractor to adjust the watering rate and frequency depending upon weather conditions. Do not overwater.

Watering must be completed in a timely manner. When the Engineer directs the Contractor to do supplemental watering, the Contractor must begin the watering operation within 24 hours of notice. The Contractor shall give an approximate time window of when they will begin at the work location to the Engineer. The Engineer shall be present during the watering operation. A minimum of 10 units of water per day must be applied until the work is complete.

Should the Contractor fail to complete the work on a timely basis or within such extended times as may have been allowed by the Department, the Contractor shall be liable to the Department liquidated damages as outlined in the "Failure to Complete Plant Care and Establishment Work on Time" special provision.

In fixing the damages as set out herein, the desire is to establish a mode of calculation for the work since the Department's actual loss, in the event of delay, cannot be predetermined, would be difficult of ascertainment, and a matter of argument and unprofitable litigation. This said mode is an equitable rule for measurement of the Department's actual loss and fairly takes into account the loss of the trees if the watering is delayed. The Department shall not be required to provide any actual loss in order to recover these liquidated damages provided herein, as said damages are very difficult to ascertain. Furthermore, no provision of this clause shall be construed as a penalty, as such is not the intention of the parties.

A calendar day is every day shown on the calendar and starts at 12:00 midnight and ends at the following 12:00 midnight, twenty-four hours later.

<u>Source of Water</u>: The Contractor shall notify the Engineer of the source of water used and provide written certification that the water does not contain chemicals harmful to plant growth.

<u>Rate of Application</u>: The normal rates of application for watering are as follows. The Engineer will adjust these rates as needed depending upon weather conditions.

35 gallons per tree
25 gallons per large shrub
15 gallons per small shrub
4 gallons per vine
3 gallons per perennial plant (Gallon)
2 gallons per perennial plant (Quart)
2 gallons per perennial plant (Plug)
27 gallons per square yard for Sodded Areas

<u>Method of Application</u>: A spray nozzle that does not damage small plants must be used when watering all vegetation. Water shall be applied at the base of the plant to keep as much water as possible off plant leaves. An open hose may be used to water trees, shrubs, and seedlings if mulch and soil are not displaced by watering. The water shall be applied to individual plants in such a manner that the plant hole shall be saturated without allowing the water to overflow beyond the earthen saucer. Watering of plants in beds shall be applied in such a manner that all plant holes are uniformly saturated without allowing the water flow beyond the periphery of the bed. Water shall slowly infiltrate into soil and completely soak the root zone. The Contractor must supply metering equipment as needed to assure the specified application rate of water.

<u>Method of Measurement</u>: Supplemental watering will be measured in units of 1000 gallons of water applied as directed.

<u>Basis of Payment</u>: This work will be paid for at the contract unit price per unit of SUPPLEMENTAL WATERING, measured as specified. Payment will include the cost of all water, equipment and labor needed to complete the work specified herein and to the satisfaction of the Engineer.

TIMBER RETAINING WALL REMOVAL

This work shall include all labor, material, and equipment necessary for the removal, offsite disposal, and grading of timber retaining walls in accordance with Section 501 of the Standard Specifications, as detailed on the plans and as specified herein.

The existing timber retaining wall designated for removal on the plans shall be removed entirely.

This work will be measured in place for at the contract unit price per foot for TIMBER RETAINING WALL REMOVAL, which shall include all labor, material, and equipment required to complete the work as specified herein.

WATER VALVES TO BE ADJUSTED

This work shall include all labor, material, and equipment necessary to adjust existing water valves to the proposed ground elevations shown on the plans in accordance with Section 564 of the Standard Specifications and as specified herein. Adjustments of adjacent fire hydrants shall be paid for separately.

This work will be measured in place for at the contract unit price per each for WATER VALVES TO BE ADJUSTED, which shall include all labor, material, and equipment required to complete the work as specified herein.

AVAILABLE REPORTS (D1 LR)

Effective: July 1, 2021

□ No project specific reports were prepared.

When applicable, the following checked reports and record information is available for Bidders' reference upon request:

- □ Record structural plans
- □ Preliminary Site Investigation (PSI) (IDOT ROW)
- ☑ Preliminary Site Investigation (PSI) (Local ROW)
- □ Preliminary Environmental Site Assessment (PESA) (IDOT ROW)
- ☑ Preliminary Environmental Site Assessment (PESA) (Local ROW)
- □ Soils/Geotechnical Report
- □ Boring Logs
- □ Pavement Cores
- □ Location Drainage Study (LDS)
- □ Hydraulic Report
- □ Noise Analysis
- □ Other: _____

Those seeking these reports should request access from:

Mark Cobb, P.E. Gewalt Hamilton Associates, Inc. Phone: (847) 478-9700 Email: mcobb@gha-engineers.com

IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION

Effective: August 1, 2012 Revised: February 2, 2017

In addition to the Contractor's equal employment opportunity (EEO) affirmative action efforts undertaken as required by this Contract, the Contractor is encouraged to participate in the incentive program described below to provide additional on-the-job training to certified graduates of the IDOT pre-apprenticeship training program, as outlined in this Special Provision.

IDOT funds, and various Illinois community colleges operate, pre-apprenticeship training programs throughout the State to provide training and skill-improvement opportunities to promote the increased employment of minority groups, disadvantaged persons and women in all aspects of the highway construction industry. The intent of this IDOT Pre-Apprenticeship Training Program Graduate (TPG) special provision (Special Provision) is to place these certified program graduates on the project site for this Contract in order to provide the graduates with meaningful on-the-job training. Pursuant to this Special Provision, the Contractor must make every reasonable effort to recruit and employ certified TPG trainees to the extent such individuals are available within a practicable distance of the project site.

Specifically, participation of the Contractor or its subcontractor in the Program entitles the participant to reimbursement for graduates' hourly wages at \$15.00 per hour per utilized TPG trainee, subject to the terms of this Special Provision. Reimbursement payment will be made even though the Contractor or subcontractor may also receive additional training program funds from other non-IDOT sources for other non-TPG trainees on the Contract, provided such other source does not specifically prohibit the Contractor or subcontractor from receiving reimbursement from another entity through another program, such as IDOT through the TPG program. With regard to any IDOT funded construction training program other than TPG, however, additional reimbursement for other IDOT programs will not be made beyond the TPG Program described in this Special Provision when the TPG Program is utilized.

No payment will be made to the Contractor if the Contractor or subcontractor fails to provide the required on site training to TPG trainees, as solely determined by IDOT. A TPG trainee must begin training on the project as soon as the start of work that utilizes the relevant trade skill and the TPG trainee must remain on the project site through completion of the Contract, so long as training opportunities continue to exist in the relevant work classification. Should a TPG trainee's employment end in advance of the completion of the Contract, the Contractor must promptly notify the IDOT District EEO Officer for the Contract that the TPG's involvement in the Contract has ended. The Contractor must supply a written report for the reason the TPG trainee involvement terminated, the hours completed by the TPG trainee on the Contract, and the number of hours for which the incentive payment provided under this Special Provision will be, or has been claimed for the separated TPG trainee.

Finally, the Contractor must maintain all records it creates as a result of participation in the Program on the Contract, and furnish periodic written reports to the IDOT District EEO Officer that document its contractual performance under and compliance with this Special Provision. Finally, through participation in the Program and reimbursement of wages, the Contractor is not relieved of, and IDOT has not waived, the requirements of any federal or state labor or employment law applicable to TPG workers, including compliance with the Illinois Prevailing Wage Act.

METHOD OF MEASUREMENT: The unit of measurement is in hours.

BASIS OF PAYMENT: This work will be paid for at the contract unit price of \$15.00 per hour for each utilized certified TPG Program trainee (TRAINEES TRAINING PROGRAM GRADUATE).

The estimated total number of hours, unit price, and total price must be included in the schedule of prices for the Contract submitted by Contractor prior to beginning work. The initial number of TPG trainees for which the incentive is available for this contract is $\underline{1}$.

The Department has contracted with several educational institutions to provide screening, tutoring and pre-training to individuals interested in working as a TPG trainee in various areas of common construction trade work. Only individuals who have successfully completed a Pre- Apprenticeship Training Program at these IDOT approved institutions are eligible to be TPG trainees. To obtain a list of institutions that can connect the Contractor with eligible TPG trainees, the Contractor may contact: HCCTP TPG Program Coordinator, Office of Business and Workforce Diversity (IDOT OBWD), Room 319, Illinois Department of Transportation, 2300 S. Dirksen Parkway, Springfield, Illinois 62764. Prior to commencing construction with the utilization of a TPG trainee, the Contractor must submit documentation to the IDOT District EEO Officer for the Contract that provides the names and contact information of the TPG trainee(s) to be trained in each selected work classification, proof that that the TPG trainee(s) has successfully completed a Pre-Apprenticeship Training Program, proof that the TPG is in an Apprenticeship Training Program approved by the U.S. Department of Labor Bureau of Apprenticeship Training, and the start date for training in each of the applicable work classifications.

To receive payment, the Contractor must provide training opportunities aimed at developing a full journey worker in the type of trade or job classification involved. During the course of performance of the Contract, the Contractor may seek approval from the IDOT District EEO Officer to employ additional eligible TPG trainees. In the event the Contractor subcontracts a portion of the contracted work, it must determine how many, if any, of the TPGs will be trained by the subcontractor. Though a subcontractor may conduct training, the Contractor retains the responsibility for meeting all requirements imposed by this Special Provision. The Contracted work performed by a TPG trainee will be passed on to a subcontractor.

Training through the Program is intended to move TPGs toward journeyman status, which is the primary objective of this Special Provision. Accordingly, the Contractor must make every effort to enroll TPG trainees by recruitment through the Program participant educational institutions to the extent eligible TPGs are available within a reasonable geographic area of the project. The Contractor is responsible for demonstrating, through documentation, the recruitment efforts it has undertaken prior to the determination by IDOT whether the Contractor is in compliance with this Special Provision, and therefore, entitled to the Training Program Graduate reimbursement of \$15.00 per hour.

Notwithstanding the on-the-job training requirement of this TPG Special Provision, some minimal off-site training is permissible as long as the offsite training is an integral part of the work of the contract, and does not compromise or conflict with the required on-site training that is central to the purpose of the Program. No individual may be employed as a TPG trainee in any work classification in which he/she has previously successfully completed a training program leading to journeyman status in any trade, or in which he/she has worked at a journeyman level or higher.

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR INSURANCE

Effective: February 1, 2007 Revised: August 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

The Contractor shall name the following entities as additional insured under the Contractor's general liability insurance policy in accordance with Article 107.27:

The entities listed above and their officers, employees, and agents shall be indemnified and held harmless in accordance with Article 107.26.

State of Illinois DEPARTMENT OF TRANSPORTATION Bureau of Local Roads & Streets SPECIAL PROVISION FOR LOCAL QUALITY ASSURANCE/ QUALITY MANAGEMENT QC/QA Effective: January 1, 2022

Replace the first five paragraphs of Article 1030.06 of the Standard Specifications with the following:

"**1030.06 Quality Management Program.** The Quality Management Program (QMP) will be Quality Control / Quality Assurance (QC/QA) according to the following."

Delete Article 1030.06(d)(1) of the Standard Specifications.

Revise Article 1030.09(g)(3) of the Standard Specifications to read:

"(3) If core testing is the density verification method, the Contractor shall provide personnel and equipment to collect density verification cores for the Engineer. Core locations will be determined by the Engineer following the document "Hot-Mix Asphalt QC/QA Procedure for Determining Random Density Locations" at density verification intervals defined in Article 1030.09(b). After the Engineer identifies a density verification location and prior to opening to traffic, the Contractor shall cut a 4 in. (100 mm) diameter core. With the approval of the Engineer, the cores may be cut at a later time."

Revise Article 1030.09(h)(2) of the Standard Specifications to read:

"(2) After final rolling and prior to paving subsequent lifts, the Engineer will identify the random density verification test locations. Cores or nuclear density gauge testing will be used for density verification. The method used for density verification will be as selected below.

Density Verification Method
Cores
Nuclear Density Gauge (Correlated when paving ≥ 3,000 tons per mixture)

Density verification test locations will be determined according to the document "Hot-Mix Asphalt QC/QA Procedure for Determining Random Density Locations". The density testing interval for paving wider than or equal to 3 ft (1 m) will be 0.5 miles (800 m) for lift thicknesses of 3 in. (75 mm) or less and 0.2 miles (320 m) for lift thicknesses greater than 3 in. (75 mm). The density testing interval for paving less than 3 ft (1 m) wide will be 1 mile (1,600 m). If a day's paving will be less than the prescribed density testing interval, the length of the day's paving will be the interval for that day. The density testing interval for mixtures used for patching will be 50 patches with a minimum of one test per mixture per project.

If core testing is the density verification method, the Engineer will witness the Contractor coring, and secure and take possession of all density samples at the density verification locations. The Engineer will test the cores collected by the Contractor for density according to Illinois Modified AASHTO T 166 or AASHTO T 275.

If nuclear density gauge testing is the density verification method, the Engineer will conduct nuclear density gauge tests. The Engineer will follow the density testing procedure detailed in the document "Illinois Modified ASTM D 2950, Standard Test Method for Density of Bituminous Concrete In-Place by Nuclear Method".

A density verification test will be the result of a single core or the average of the nuclear density tests at one location. The results of each density test must be within acceptable limits. The Engineer will promptly notify the Contractor of observed deficiencies."

Revise the seventh paragraph and all subsequent paragraphs in Section D. of the document "Hot-Mix Asphalt QC/QA Initial Daily Plant and Random Samples" to read:

"Mixtures shall be sampled from the truck at the plant by the Contractor following the same procedure used to collect QC mixture samples (Section A). This process will be witnessed by the Engineer who will take custody of the verification sample. Each sample bag with a verification mixture sample will be secured by the Engineer using a locking ID tag. Sample boxes containing the verification mixture sample will be sealed/taped by the Engineer using a security ID label."



Illinois Environmental Protection Agency

1021 North Grand Avenue East • P.O. Box 19276 • Springfield • Illinois • 62794-9276 • (217) 782-3397

Uncontaminated Soil Certification

by Licensed Professional Engineer or Licensed Professional Geologist for Use of Uncontaminated Soil as Fill in a CCDD or Uncontaminated Soil Fill Operation LPC-663

Revised in accordance with 35 III. Adm. Code 1100, as amended by PCB R2012-009 (eff. Aug. 27, 2012)

This certification form is to be used by professional engineers and professional geologists to certify, pursuant to 35 III. Adm. Code 1100.205(a)(1)(B), that soil (i) is uncontaminated soil and (ii) is within a pH range of 6.26 to 9.0. If you have questions about this form, please telephone the Bureau of Land Permit Section at 217/524-3300.

This form may be completed online, saved locally, printed and signed, and submitted to prospective clean construction or demolition debris (CCDD) fill operations or uncontaminated soil fill operations.

I. Source Location Information

(Describe the location	on of the source of the un	contaminated soil)		
Project Name: Saunders Road Reconstruction Project			Office Phone N	umber, if available:
	on (address, including nu ad from Riverwoods Roa			
City: Riverwo	oods	State: IL	Zip Code: 60015	
County: Lake Township: West			Deerfield	
Lat/Long of approxir	nate center of site in dec	imal degrees (DD.	ddddd) to five decimal	places (e.g., 40.67890, -90.12345):
Latitude: 42.18005	Longitude: - (37.88148		
(Decimal Identify how the lat/l	Degrees) (ong data were determine	-Decimal Degrees d:)	
🔾 GPS 🔿 Map	Interpolation O Photo	Interpolation ()	Survey 🕢 Other	
ISGS Public Land S	Survey System. Lat/lon at	ove refer to the ap		
IEPA Site Number(s), if assigned: BOL:			BOW:	BOA:
Approximate Start Date (mm/dd/yyyy):			Approximate End Da	ate (mm/dd/yyyy):
Estimated Volume of	of debris (cu. Yd.):			
	ator Information for	Source Site	Cite On sustain	
Site Owner			Site Operator	
(Name: Village of Riverwoods		Name:	
Street Address: 300 Portwine Rd.		Street Address:		
PO Box:			PO Box:	
City:	Riverwoods	State: IL	City:	State:
Zip Code:	60015 Phone:	847-945-3990	Zip Code:	Phone:
Contact: Stephen Witt			Contact:	
Email, if available: switt@riverwoods.gov			Email, if available:	

This Agency is authorized to require this information under Section 4 and Title X of the Environmental Protection Act (415 ILCS 5/4, 5/39). Failure to disclose this information may result in: a civil penalty of not to exceed \$50,000 for the violation and an additional civil penalty of not to exceed \$10,000 for each day during which the violation continues (415 ILCS 5/42). This form has been approved by the Forms Management Center.

Uncontaminated Soil Certification

III. Basis for Certification and Attachments

For each item listed below, reference the attachments to this form that provide the required information.

A Description of the soil sample points and how they were determined to be sufficient in number and appropriately located 35 III. Adm. Code 1100.610(a)]:

A May 2021 PESA was reviewed for the Project Corridor, which consisted of residential and commercial properties. Three (3) PIPs were identified in connection with the Project Corridors through the database review and site visit. Refer to the attachments for additional information.

b. Analytical soil testing results to show that soil chemical constituents comply with the maximum allowable concentrations established pursuant to 35 III. Adm. Code Part 1100, Subpart F and that the soil pH is within the range of 6.25 to 9.0,including the documentation of chain of custody control, a copy of the lab analysis; the accreditation status of the laboratory performing the analysis; and certification by an authorized agent of the laboratory that the analysis has been performed in accordance with the Agency's rules for the accreditation of environmental and the scope of the accreditation [35 III. Adm. Code 1100.201 (g), 1100.205(a), 1100.610]:

Eighteen (18) soil borings were advanced along the Project Corridor on April 11, 2024. Samples were analyzed for one or more of: VOCs, SVOCs, total RCRA Metals, and pH. Results achieve the CCDD requirements, except for the CCDD Exclusion Areas as shown in the attached documentation [SB-7(0-5), SB-9, SB-13, SB-16]. Refer to the attachments for additional info.

IV. Certification Statement, Signature and Seal of Licensed Professional Engineer or Licensed Professional Geologist


I. Jeremy J. Reynolds, P.G. (name of licensed professional engineer or geologist) certify under penalty of law that the information submitted, including but not limited to, all attachments and other information, is to the best of my knowledge and belief, true, accurate and complete. In accordance with the Environmental Protection Act [415 ILCS 5/22.51 or 22.51a] and 35 III. Adm. Code 1100.205(a), I certify that the soil from this site is uncontaminated soil. I also certify that the soil pH is within the range of 6.25 to 9.0. In addition, I certify that the soil has not been removed from the site as part of a cleanup or removal of contaminants. All necessary documentation is attached.

Any person who knowingly makes a false, fictitious, or fraudulent material statement, orally or in writing, to the Illinois EPA commits a Class 4 felony. A second or subsequent offense after conviction is a Class 3 felony. (415 ILCS 5/44(h))

Company Name: Huff & Huff, Inc., a Subsidiary of GZA, Inc.					
Street Address:	915 Harger Rd Suite 330				
City:	Oak Brook	State:	IL	Zip Code: 60523	
Phone:	(630) 684-9100				

Jeremy J. Reynolds, P.G. Printed Name:

Licensed Professional Engineer or Licensed Professional Geologist Signature:



Uncontaminated Soil Certification



Route	Marked Route	Section Number
FAU 2416	Saunders Road	21-00020-00-RS
Project Number	County	Contract Number
JFPC(674)	Lake	61K96

This plan has been prepared to comply with the provisions of the National Pollutant Discharge Elimination System (NPDES) Permit No. ILR10 (Permit ILR10), issued by the Illinois Environmental Protection Agency (IEPA) for storm water discharges from construction site activities.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature & Date

Sinhar R. Win	9/24/2024
gettin t. Will	0/2 1/202 1

<u>Note</u>: Guidance on preparing each section of BDE 2342 can be found in Chapter 41 of the IDOT Bureau of Design and Environment (BDE) Manual. Chapter 41 and this form also reference the IDOT Drainage Manual which should be readily available.

I. Site Description:

A. Provide a description of the project location; include latitude and longitude, section, town, and range: Saunders Road: Sta. 0.00 to 1.45, Village of Riverwoods, Lake County, IL (42.17729, -87.88191)

B. Provide a description of the construction activity which is the subject of this plan. Include the number of construction stages, drainage improvements, in-stream work, installation, maintenance, removal of erosion measures, and permanent stabilization:

The project scope involves resurfacing and shoulder widening of Saunders Road from Riverwoods Road to Duffy Lane. The project also involves storm sewer utility improvements. The erosion control plan will consist of one phase, which includes perimeter erosion barrier, inlet and pipe protection, and restoration of disturbed areas with topsoil, Class 2A seed, and erosion control blanket.

C. Provide the estimated duration of this project:

March 2025-November 2025

D. The total area of the construction site is estimated to be $\frac{4.0}{1.0}$ acres.

The total area of the site estimated to be disturbed by excavation, grading or other activities is 4.0 acres.

E. The following are weighted averages of the runoff coefficient for this project before and after construction activities are completed; see Section 4-102 of the IDOT Drainage Manual:

0.69

F. List all soils found within project boundaries; include map unit name, slope information, and erosivity:

320-Frankfort silt loam, 0 to 2 percent slopes

465-Montgomery silty clay loam, 0 to 2 percent slopes

696-Zurich silt loam, 2 to 4 percent slopes 228-Nappanee, 2 to 4 percent slopes G. If wetlands were delineated for this project, provide an extent of wetland acreage at the site; see Phase I report:5 wetlands are located within the project limits totaling 0.188 acres.

H. Provide a description of potentially erosive areas associated with this project:

N/A

I. The following is a description of soil disturbing activities by stages, their locations, and their erosive factors (e.g., steepness of slopes, length of slopes, etc.):

Clearing and grubbing, grading, fine grading, site restoration. No steep slopes are proposed.

J. See the erosion control plans and/or drainage plans for this contract for information regarding drainage patterns, approximate slopes anticipated before and after major grading activities, locations where vehicles enter or exit the site and controls to prevent offsite sediment tracking (to be added after contractor identifies locations), areas of soil disturbance, the location of major structural and non-structural controls identified in the plan, the location of areas where stabilization practices are expected to occur, surface waters (including wetlands), and locations where storm water is discharged to surface water including wetlands.

K. Identify who owns the drainage system (municipality or agency) this project will drain into: Village of Riverwoods

L. The following is a list of General NPDES ILR40 permittees within whose reporting jurisdiction this project is located: Village of Riverwoods

M. The following is a list of receiving water(s) and the ultimate receiving water(s) for this site. In addition, include receiving waters that are listed as Biologically Significant Streams by the Illinois Department of Natural Resources (IDNR). The location of the receiving waters can be found on the erosion and sediment control plans:

Discharges to the West Fork of the North Branch of the Chicago River

N. Describe areas of the site that are to be protected or remain undisturbed. These areas may include steep slopes (i.e., 1:3 or steeper), highly erodible soils, streams, stream buffers, specimen trees, natural vegetation, nature preserves, etc. Include any commitments or requirements to protect adjacent wetlands.

For any storm water discharges from construction activities within 50-feet of Waters of the U.S. (except for activities for waterdependent structures authorized by a Section 404 permit, describe: a) How a 50-foot undisturbed natural buffer will be provided between the construction activity and the Waters of the U.S. or b) How additional erosion and sediment controls will be provided within that area.

O. Per the Phase I document, the following sensitive environmental resources are associated with this project and may have the potential to be impacted by the proposed development. Further guidance on these resources is available in Section 41-4 of the BDE Manual.

None

303(d) Listed receiving waters for suspended solids, turbidity, or siltation. The name(s) of the listed water body, and identification of all pollutants causing impairment:

West Fork of the North Branch Chicago River; Chloride, Fecal coliform

Provide a description of how erosion and sediment control practices will prevent a discharge of sediment resulting from a storm event equal to or greater than a twenty-five (25) year, twenty-four (24) hour rainfall event:

Inlet filters and pipe protection will be placed at every inlet within the project area. Silt fence will be used at the boundary of the project area. Erosion control blanket will be laid over seed upon completion of grading/earth work.

Provide a description of the location(s) of any dewatering discharges to the MS4 and/or water body:

None

Applicable Federal, Tribal, State, or Local Programs

N/A

Floodplain

Floodway Zone AE

Historic Preservation

N/A

Receiving waters with Total Maximum Daily Load (TMDL) for sediment, total suspended solids, turbidity or siltation TMDL (fill out this section if checked above)

The name(s) of the listed water body:

Provide a description of the erosion and sediment control strategy that will be incorporated into the site design that is consistent with the assumptions and requirements of the TMDL:

If a specific numeric waste load allocation has been established that would apply to the project's discharges, provide a description of the necessary steps to meet that allocation:

Solid Waste Debris

Other (Specify)

X Waste water from cleaning construction equipments

Other (Specify)
 Other (Specify)

Other (Specify)

Other (Specify)

Solvents

X Threatened and Endangered Species/Illinois Natural Areas (INAI)/Nature Preserves

N/A see EcoCAT

Other

⊠ Wetland

5, one USACE, 4 Isolated Wetlands of Lake County (IWLC)

P. The following pollutants of concern will be associated with this construction project:

- Antifreeze / Coolants
- Concrete
- Concrete Curing Compounds
- Concrete Truck Waste
- Fertilizers / Pesticides
- ⊠ Paints
- Petroleum (gas, diesel, oil, kerosene, hydraulic oil / fluids)
- Soil Sediment
- II. Controls:

This section of the plan addresses the controls that will be implemented for each of the major construction activities described in Section I.C above and for all use areas, borrow sites, and waste sites. For each measure discussed, the Contractor will be responsible for its implementation as indicated. The Contractor shall provide to the Resident Engineer a plan for the implementation of the measures indicated. The Contractor, and subcontractors, will notify the Resident Engineer of any proposed changes, maintenance, or modifications to keep construction activities compliant with the Permit ILR10. Each such Contractor has signed the required certification on forms which are attached to, and are a part of, this plan:

A. Erosion and Sediment Controls: At a minimum, controls must be coordinated, installed and maintained to:

- 1. Minimize the amount of soil exposed during construction activity;
- 2. Minimize the disturbance of steep slopes;
- 3. Maintain natural buffers around surface waters, direct storm water to vegetated areas to increase sediment removal and maximize storm water infiltration, unless infeasible;
- 4. Minimize soil compaction and, unless infeasible, preserve topsoil.
- B. Stabilization Practices: Provided below is a description of interim and permanent stabilization practices, including site-specific scheduling of the implementation of the practices. Site plans will ensure that existing vegetation is preserved where attainable and disturbed portions of the site will be stabilized. Stabilization practices may include but are not limited to: temporary seeding, permanent seeding, mulching, geotextiles, sodding, vegetative buffer strips, protection of trees, preservation of mature vegetation, and other appropriate measures. Except as provided below in II.B.1 and II.B.2, stabilization measures shall be initiated **immediately** where construction activities have temporarily or permanently ceased, but in no case more than **one (1) day** after the construction activity in that portion of the site has temporarily or permanently ceases on all disturbed portions of the site where construction will not occur for a period of fourteen (14) or more calendar days.
 - 1. Where the initiation of stabilization measures is precluded by snow cover, stabilization measures shall be initiated as soon as practicable.
 - 2. On areas where construction activity has temporarily ceased and will resume after fourteen (14) days, a temporary stabilization method can be used.

The following stabilization practices will be used for this project:

Erosion Control Blanket / Mulching	Temporary Turf (Seeding, Class 7)
Geotextiles	Temporary Mulching
☑ Permanent Seeding	Vegetated Buffer Strips
Preservation of Mature Seeding	Other (Specify)
Protection of Trees	Other (Specify)
Sodding	Other (Specify)
I Temporary Erosion Control Seeding	Other (Specify)

Describe how the stabilization practices listed above will be utilized during construction: The erosion control blanket will be installed in all areas disturbed by grading for temporary stabilization.

Describe how the stabilization practices listed above will be utilized after construction activities have been completed: Permanent seed will be installed at all disturbed locations where final coverage is to be pervious. The site will not be considered permanently stabilized until it reaches 75% coverage of vegetative growth.

C. Structural Practices: Provided below is a description of structural practices that will be implemented, to the degree attainable, to divert flows from exposed soils, store flows or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Such practices may include but are not limited to: perimeter erosion barrier, earth dikes, drainage swales, sediment traps, ditch checks, subsurface drains, pipe slope drains, level spreaders, storm drain inlet protection, rock outlet protection, reinforced soil retaining systems, gabions, and temporary or permanent sediment basins. The installation of these devices may be subject to Section 404 of the Clean Water Act.

Aggregate Ditch	Stabilized Construction Exits
Concrete Revetment Mats	Stabilized Trench Flow
Dust Suppression	Slope Mattress
Dewatering Filtering	Slope Walls
Gabions	🔀 Temporary Ditch Check
In-Stream or Wetland Work	Temporary Pipe Slope Drain

Level Spreaders	Temporary Sediment Basin
Paved Ditch	Temporary Stream Crossing
Permanent Check Dams	Turf Reinforcement Mats
Perimeter Erosion Barrier	Other (Specify)
Permanent Sediment Basin	Other (Specify)
Retaining Walls	Other (Specify)
Riprap	Other (Specify)
Rock Outlet Protection	Other (Specify)
Sediment Trap	Other (Specify)
Storm Drain Inlet Protection	Other (Specify)

Describe how the structural practices listed above will be utilized during construction:

Perimeter erosion barrier will be installed in order to prevent sediment from entering the storm drains or washing off-site during construction. Storm drain inlet filters will be installed to prevent sediment from entering the storm sewer. Temporary ditch checks will be used to slow the flow of water in roadside ditches, reducing the potential for erosion.

Describe how the structural practices listed above will be utilized after construction activities have been completed: Perimeter erosion barrier and temporary ditch checks will be left in place until the site is permanently stabilized. Inlet filter and inlet and pipe protection will be removed after construction activities have been completed.

D. Treatment Chemicals

Will polymer flocculants or treatment chemicals be utilized on this project: Yes No

If yes above, identify where and how polymer flocculants or treatment chemicals will be utilized on this project.

E. **Permanent (i.e., Post-Construction) Storm Water Management Controls:** Provided below is a description of measures that will be installed during the construction process to control volume and pollutants in storm water discharges that will occur after construction operations have been completed. The installation of these devices may be subject to Section 404 of the Clean Water Act.

1. Such practices may include but are not limited to: storm water detention structures (including wet ponds), storm water retention structures, flow attenuation by use of open vegetated swales and natural depressions, infiltration of runoff on site, and sequential systems (which combine several practices).

The practices selected for implementation were determined based on the technical guidance in Chapter 41 (Construction Site Storm Water Pollution Control) of the IDOT BDE Manual. If practices other than those discussed in Chapter 41 are selected for implementation or if practices are applied to situations different from those covered in Chapter 41, the technical basis for such decisions will be explained below.

2. Velocity dissipation devices will be placed at discharge locations and along the length of any outfall channel as necessary to provide a non-erosive velocity flow from the structure to a water course so that the natural physical and biological characteristics and functions are maintained and protected (e.g., maintenance of hydrologic conditions such as the hydroperiod and hydrodynamics present prior to the initiation of construction activities).

Description of permanent storm water management controls:

The permanent stormwater quality control for the site is the existing roadside ditches along with driveway culverts conveying drainage in the the existing system.

F. **Approved State or Local Laws:** The management practices, controls and provisions contained in this plan will be in accordance with IDOT specifications, which are at least as protective as the requirements contained in the IEPA's Illinois Urban Manual. Procedures and requirements specified in applicable sediment and erosion site plans or storm water management plans approved by local officials shall be described or incorporated by reference in the space provided below. Requirements specified in sediment and erosion site plans, site permits, storm water management site plans or site permits approved by local officials that are applicable to protecting surface water resources are, upon submittal of an NOI, to be authorized to discharge under the Permit ILR10 incorporated by reference

and are enforceable under this permit even if they are not specifically included in the plan.

Description of procedures and requirements specified in applicable sediment and erosion site plans or storm water management plans approved by local officials:

Temporary erosion control measures such as perimeter erosion barrier, inlet filters, and inlet and pipe protection on existing storm structures must be installed prior to site disturbance. Inlet filters and inlet and pipe protection must be installed as soon as the proposed structures are set.

- G. **Contractor Required Submittals:** Prior to conducting any professional services at the site covered by this plan, the Contractor and each subcontractor responsible for compliance with the permit shall submit to the Resident Engineer a Contractor Certification Statement, BDE 2342A.
- 1. The Contractor shall provide a construction schedule containing an adequate level of detail to show major activities with implementation of pollution prevention BMPs, including the following items:
 - Approximate duration of the project, including each stage of the project
 - · Rainy season, dry season, and winter shutdown dates
 - Temporary stabilization measures to be employed by contract phases
 - Mobilization time-frame
 - Mass clearing and grubbing/roadside clearing dates
 - Deployment of Erosion Control Practices
 - Deployment of Sediment Control Practices (including stabilized cons
 - Deployment of Construction Site Management Practices (including concrete washout facilities, chemical storage, refueling locations, etc.)
 - Paving, saw-cutting, and any other pavement related operations
 - Major planned stockpiling operation
 - Time frame for other significant long-term operations or activities that may plan non-storm water discharges as dewatering, grinding, etc
 - Permanent stabilization activities for each area of the project
- 2. During the pre-construction meeting, the Contractor and each subcontractor shall provide, as an attachment to their signed Contractor Certification Statement, a discussion of how they will comply with the requirements of the permit in regard to the following items and provide a graphical representation showing location and type of BMPs to be used when applicable:
 - Temporary Ditch Checks Identify what type and the source of Temporary Ditch Checks that will be installed as part of the project. The installation details will then be included with the SWPPP.
 - Vehicle Entrances and Exits Identify type and location of stabilized construction entrances and exits to be used and how they will be maintained.
 - Material Delivery, Storage and Use Discuss where and how materials including chemicals, concrete curing compounds, petroleum products, etc. will be stored for this project.
 - Stockpile Management Identify the location of both on-site and off-site stockpiles. Discuss what BMPs will be used to prevent pollution of storm water from stockpiles.
 - Waste Disposal Discuss methods of waste disposal that will be used for this project.
 - Spill Prevention and Control Discuss steps that will be taken in the event of a material spill (chemicals, concrete curing compounds, petroleum, etc.)
 - Concrete Residuals and Washout Wastes Discuss the location and type of concrete washout facilities to be used on this project and how they will be signed and maintained.
 - Litter Management Discuss how litter will be maintained for this project (education of employees, number of dumpsters, frequency of dumpster pick-up, etc.).
 - Vehicle and Equipment Fueling Identify equipment fueling locations for this project and what BMPs will be used to ensure containment and spill prevention.
 - Vehicle and Equipment Cleaning and Maintenance Identify where equipment cleaning and maintenance locations for this project and what BMPs will be used to ensure containment and spill prevention.
 - Dewatering Activities Identify the controls which will be used during dewatering operations to ensure sediments will not leave the construction site.
 - Polymer Flocculants and Treatment Chemicals Identify the use and dosage of treatment chemicals and provide the Resident Engineer with Material Safety Data Sheets. Describe procedures on how the chemicals will be used and identify who will be responsible for the use and application of these chemicals. The selected individual must be trained on the established procedures.
 - · Additional measures indicated in the plan.

III. Maintenance:

When requested by the Contractor, the Resident Engineer will provide general maintenance guides (e.g., IDOT Erosion and Sediment Control Field Guide) to the Contractor for the practices associated with this project. Describe how all items will be checked for structural integrity, sediment accumulation and functionality. Any damage or undermining shall be repaired immediately. Provide specifics on how repairs will be made. The following additional procedures will be used to maintain, in good and effective operating conditions, the

vegetation, erosion and sediment control measures and other protective measures identified in this plan. It will be the Contractor's responsibility to attain maintenance guidelines for any manufactured BMPs which are to be installed and maintained per manufacture's specifications.

Perimeter erosion barrier - accumulated sediment shall be removed in front of perimeter erosion barrier when sediment reaches 1/2 the height of the fence. Perimeter erosion barrier shall promptly be replaced and/or repaired in the event it falls down or is torn.

Inlet protection - inlet protection devices shall be cleaned after storm events or when the devices become 25% full of sediment. Inlet protection devices shall promptly be replaced in the event that they are torn.

IV. Inspections:

Qualified personnel shall inspect disturbed areas of the construction site including Borrow, Waste, and Use Areas, which have not yet been finally stabilized, structural control measures, and locations where vehicles and equipment enter and exit the site using IDOT Storm Water Pollution Prevention Plan Erosion Control Inspection Report, BC 2259. Such inspections shall be conducted at least once every seven (7) calendar days and within twenty-four (24) hours of the end of a storm or by the end of the following business or work day that is 0.5 inch or greater or equivalent snowfall.

Inspections may be reduced to once per month when construction activities have ceased due to frozen conditions. Weekly inspections will recommence when construction activities are conducted, or if there is 0.5" or greater rain event, or a discharge due to snowmelt occurs.

If any violation of the provisions of this plan is identified during the conduct of the construction work covered by this plan, the Resident Engineer shall notify the appropriate IEPA Field Operations Section office by email at: <u>epa.swnoncomp@illinois.gov</u>, telephone or fax within twenty-four (24) hours of the incident. The Resident Engineer shall then complete and submit an "Incidence of Non-Compliance" (ION) report for the identified violation within five (5) days of the incident. The Resident Engineer shall use forms provided by IEPA and shall include specific information on the cause of noncompliance, actions which were taken to prevent any further causes of noncompliance, and a statement detailing any environmental impact which may have resulted from the noncompliance. All reports of non-compliance shall be signed by a responsible authority in accordance with Part VI. G of the Permit ILR10.

The Incidence of Non-Compliance shall be mailed to the following address: Illinois Environmental Protection Agency Division of Water Pollution Control Attn: Compliance Assurance Section 1021 North Grand East Post Office Box 19276 Springfield, Illinois 62794-9276

V. Failure to Comply:

Failure to comply with any provisions of this Storm Water Pollution Prevention Plan will result in the implementation of a National Pollutant Discharge Elimination System/Erosion and Sediment Control Deficiency Deduction against the Contractor and/or penalties under the Permit ILR10 which could be passed on to the Contractor.





Prior to conducting any professional services at the site covered by this contract, the Contractor and every subcontractor must complete and return to the Resident Engineer the following certification. A separate certification must be submitted by each firm. Attach to this certification all items required by Section II.G of the Storm Water Pollution Prevention Plan (SWPPP) which will be handled by the Contractor/subcontractor completing this form.

Route	Marked Route	Section Number
FAU 2416	Saunders Road	21-00020-00-RS
Project Number	County	Contract Number
JFPC(674)	Lake	61K96

This certification statement is a part of SWPPP for the project described above, in accordance with the General NPDES Permit No. ILR10 issued by the Illinois Environmental Protection Agency.

I certify under penalty of law that I understand the terms of the Permit No. ILR 10 that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification.

Additionally, I have read and understand all of the information and requirements stated in SWPPP for the above mentioned project; I have received copies of all appropriate maintenance procedures; and, I have provided all documentation required to be in compliance with the Permit ILR10 and SWPPP and will provide timely updates to these documents as necessary.

Contractor

Sub-Contractor

Signature	Date
Print Name	Title
Name of Firm	Phone
Street Address	City State _ Zip Code
Items which this Contractor/subcontractor will be responsible for as re-	equired in Section II.G. of SWPPP



December 19, 2024

Kris Ford Village of Riverwoods 300 Portwine Road Riverwoods, IL 60015

Subject: SMC Watershed Development Permit #WDP-24-696 Saunders Road Resurfacing

PERMIT ISSUANCE

Dear Mr. Ford:

Accompanying this letter is the required Watershed Development Permit for the proposed resurfacing project. This approval is subject to the conditions on the back of the permit application including the following:

- Provide prior notification to Tim Cook (of the SMC) of the pre-construction meeting at least 5 calendar days in advance to enable SMC attendance.
- Please note that the erosion control measures indicated on the plans are the minimum requirements. Additional measures may be required, as directed by the engineer, enforcement officer, or other governing agency.
- The project will require total impacts (0.003 acres) to a Waters of the United States, including 0.003 acres of permanent impact. The proposed impacts appear to be authorized under the U.S. Army Corps of Engineers non-reporting Nationwide Permit (NWP) Program, as asserted by the project's Certified Wetland Specialist. You shall comply with the specific conditions and general conditions of the NWP program, particularly Condition 12: Soil Erosion and Sediment Controls.
- Please provide SMC with a copy of the NOI application to the IEPA.
- Please provide authorization from the adjacent property owners for work on or through their property. Authorization can include a recorded easement, legal agreement or authorization letter that includes the proposed scope of work and signed by the property owner.
- Please coordinate all SE/SC modifications to the plan with the SMC Inspector.
- Discussion at the pre-construction meeting will include:
 - Designated Erosion Control Inspector (DECI) contact information
 - Maintenance of sediment and erosion control measures

- The DECI shall provide weekly reports to the SMC Inspector. At a minimum, the reports shall include photographs and evaluation of critical areas, as directed by the SMC Inspector.
- Isolated Wetlands Approval:

SMC hereby authorizes impacts to three non-high quality Isolated Waters of Lake County (IWLC) from the project totaling 0.08 acre of permanent impacts under our WDO.

This approval is based on the plans entitled:

STATE OF ILLINOIS, DEPARTMENT OF TRANSPORTATION, PLANS FOR PROPOSED FEDERAL AID HIGHWAY, FAU ROUTE 2416 SAUNDERS ROAD FROM RIVERWOODS ROAD TO DUFFY LANE, RESURFACING, SECTION 21-00020-00-RS, PROJECT: JFPC(674), VILLAGE OF RIVERWOODS, LAKE COUNTY, C-91-241-24, prepared by Gewalt Hamilton Associates, Inc., received by SMC August 27, 2024 109-sheets (Plans Dated 08/12/2024).

Please contact Tim Cook at <u>tcook@lakecountyil.gov</u> or (847)377-7703 if you have questions or would like to set up the pre-construction meeting.

Sincerely,

LAKE COUNTY STORMWATER MANAGEMENT COMMISSION

Philip Runy

Philip Ruiz, P.E., CFM Principal Permit Engineer

Brian Frank, P.E., CFM Chief Engineer

C: Tim Cook – Lake County SMC Bill Santelik – Lake County SMC Monica Hue – Gewalt Hamilton Associates, Inc. Joseph Hmieleski – JHWetco



WATERSHED DEVELOPMENT PERMIT NUMBER WDP-24-696 HAS BEEN SECURED

Project: Saunders Road Resurfacing

Date Issued: December 19, 2024

Conditions: • See WDP application page 2 for standard permit conditions

See permit letter for project specific permit conditions

Issued By: Philip Ruiz, P.E., CFM Principal Permit Engineer

Notice to Contractors and Owners

Post this card at the site, visible from the street and so located as to permit the inspector to record the indicated inspections on the placard. Do not post in the interior of a building.

Inspectors and sheriff's deputies are instructed to stop all work where this permit card is not displayed.

Always mention the Watershed Development Permit number when referring to this project. If this card becomes mislaid or lost please contact Lake County Stormwater Management Commission for a replacement.

Lake County Stormwater Management Commission (847) 377-7700



October 25, 2024

Regulatory Branch (LRC-2020-00661)

SUBJECT: Nationwide Permit Authorization for 0.18 ac of Permanent Impacts to the West Branch DuPage River for Replacement of Existing Bridge With a Box Culvert at Arlington Drive Between Catalina Drive and Greenbrook Boulevard, Hanover Park, DuPage County, Illinois (Latitude 41.97479°N, Longitude -88.13874°W)

Jonathan Stelle Village of Hanover Park 2121 West Lake Street Hanover Park, Illinois 60133

Dear Mr. Stelle:

The U.S. Army Corps of Engineers, Chicago District, has completed its review of your pre-construction notification for the above referenced project, dated February 19, 2024, for authorization under the Nationwide Permit (NWP) Number 14 (NWP 14 Linear Transportation Projects), submitted on your behalf by Huff & Huff. This office has verified that your proposed activity complies with the terms and conditions of the NWP.

This determination covers only your project as described above and in the approved project plans titled, "Plans for Proposed Federal Aid Highway, Arlington Dr W Section 15-00066-00-BR...Bridge Replacement DuPage County", dated November 1, 2023, prepared by Benesch. Caution must be taken to prevent construction materials and activities from impacting waters of the United States beyond the scope of this authorization. If the design, location, or purpose of the project is changed, it is recommended that you contact this office to determine the need for further authorization.

The subject activity may be performed without further authorization from this office provided that the activity complies with the NWP terms and general conditions, the regional conditions for Illinois, the special conditions listed below, and the Section 401 Water Quality Certification ("WQC") conditions added by the Illinois Environmental Protection Agency ("IEPA"). The NWP Program terms, general conditions, and regional conditions are listed in the enclosed NWP Summary. The WQC conditions are listed in the enclosed Fact Sheet.

Specifically, we wish to draw your attention to General Condition 21, which requires permittees to notify our office immediately in the event of discovery of previously unknown human remains, Native American cultural items, or archaeological artifacts; and a term of the NWP program, which states that NWPs do not obviate the need to obtain other federal, state, or local permits, approvals, or authorizations required by law.

In addition to the general, regional, and water quality conditions of this permit verification, the following special conditions also apply to this verification:

1. This permit does not authorize temporary construction activities, such as the use of earth moving machinery in non-impacted waters of the U.S. or temporarily stockpiling material within waters of the US.

2. To avoid potential impacts to the northern long-eared bat (*Myotis septentrionalis*), tree clearing (trees 3" DBH or greater) shall only occur between October 1 and March 31 of any construction year.

3. This authorization is contingent upon implementing and maintaining soil erosion and sediment controls in a serviceable condition throughout the duration of the project. You shall comply with the Kane-DuPage Soil and Water Conservation District's (SWCD) written and verbal recommendations regarding the soil erosion and sediment control (SESC) plan and the installation and maintenance requirements of the SESC practices on-site.

a. You shall schedule a preconstruction meeting with SWCD to discuss the SESC plan and the installation and maintenance requirements of the SESC practices on the site. You shall contact this office and the SWCD at least 10 calendar days prior to the preconstruction meeting so that a representative may attend.

b. You shall notify this office and the SWCD of any changes or modifications to the approved plan set. Field conditions during project construction may require the implementation of additional SESC measures. If you fail to implement corrective measures, this office may require more frequent site inspections to ensure the installed SESC measures are acceptable.

c. Prior to commencement of any in-stream work, you shall submit constructions plans and a detailed narrative to this office and the SWCD that disclose the contractor's preferred method of cofferdam and dewatering method. Work in the waterway shall NOT commence until the SWCD notifies you, in writing, that the plans have been approved.

4. Prior to commencement of work, you shall submit constructions plans and a narrative of the contractor's preferred method of cofferdam and dewatering to this office. Work in the waterway shall not commence until this office notifies you, in writing, that the plans have been approved.

5. You shall provide written notification to this office at least ten (10) days prior to the commencement of work indicating the start date and estimated end date of construction. If possible, this notification should be provided by email to patrick.j.verhalen@usace.army.mil.

6. You are responsible for all work authorized herein and for ensuring that all contractors are aware of the terms and conditions of this authorization.

7. A copy of this authorization must be present at the project site during all phases of construction.

8. Work in the waterway should be timed to take place during low or no-flow conditions. Low flow conditions are flow at or below the normal water elevation.

9. The plan must be designed to allow for the conveyance of the 2-year peak flow past the work area without overtopping the cofferdam. The Corps has the discretion to reduce this requirement if documented by the applicant to be infeasible or unnecessary.

10. Water shall be isolated from the in-stream work area using a cofferdam constructed of non-erodible materials (steel sheets, aqua barriers, rip rap and geotextile liner, etc.). Earthen cofferdams are not permissible.

11. The cofferdam must be constructed from the upland area and no equipment may enter flowing water at any time. If the installation of the cofferdam cannot be completed from shore and access is needed to reach the area to be coffered, other measures, such as the construction of a causeway, will be necessary to ensure that equipment does not enter the water. Once the cofferdam is in place and the isolated area is dewatered, equipment may enter the coffered area to perform the required work.

12. If bypass pumping is necessary, the intake hose shall be placed on a stable surface or floated to prevent sediment from entering the hose. The bypass discharge shall be placed on a non-erodible, energy dissipating surface prior to rejoining the stream flow and shall not cause erosion. Filtering of bypass water is not necessary unless the bypass water has become sediment-laden as a result of the current construction activities.

13. During dewatering of the coffered work area, all sediment-laden water must be filtered to remove sediment. Possible options for sediment removal include baffle systems, anionic polymers systems, dewatering bags, or other appropriate methods. Water shall have sediment removed prior to being re-introduced to the downstream waterway. A stabilized conveyance from the dewatering device to the waterway must be identified in the plan. Discharge water is considered clean if it does not result in a visually identifiable degradation of water clarity.

14. The portion of the side slope that is above the observed water elevation shall be stabilized as specified in the plans prior to accepting flows. The substrate and toe of slope that has been disturbed due to construction activities shall be restored to proposed or pre-construction conditions and fully stabilized prior to accepting flows.

Please note that IEPA has issued Section 401 Water Quality Certification for this NWP. The conditions of this WQC are automatically conditions of this NWP verification

and are included in the enclosed Fact Sheet. If you have any questions regarding Section 401 certification, please contact IEPA's Division of Water Pollution Control, Permit Section #15, by telephone at (217) 785-6939.

This verification is valid until March 14, 2026, when NWP 14 is scheduled to be modified, reissued, or revoked. Furthermore, if you commence or are under contract to commence this activity before the date the NWP is modified, reissued, or revoked, you will have 12 months from the date of the modification, reissuance or revocation to complete the activity under the present terms and conditions. Failure to comply with the general and regional conditions of this NWP, or any project-specific special conditions of this authorization, may result in the suspension or revocation of your authorization.

This office is in receipt of a letter from the School Springs Mitigation Bank confirming your purchase of certified stream mitigation credits. This requirement was calculated by multiplying 96 linear feet by a ratio of 1:1 which equals 96 linear feet of credits.

Once you have completed the authorized activity, please sign and return the enclosed compliance certification as required by general condition 30. If you have any questions, please contact Patrick VerHalen of this office by telephone at (312) 846-5545, or email at patrick.j.verhalen@usace.army.mil.

Sincerely,



Teralyn Pompeii Chief, Regulatory Branch

Enclosures

CC:

DuPage County Stormwater Management (Jenna Fahey) Kane/DuPage SWCD (Patrick McPartlan) Huff & Huff (Lailah Reich)

PERMIT COMPLIANCE

- 5 -



CERTIFICATION

Permit Number: LRC-2020-00661

Permittee: Jonathan Stelle Village of Hanover Park

Date: October 25, 2024

I hereby certify that the work authorized by the above-referenced permit has been completed in accordance with the terms and conditions of said permit and if applicable, compensatory wetland mitigation was completed in accordance with the approved mitigation plan.¹

PERMITTEE

DATE

Within 30 days after completion of the activity authorized by this permit and any mitigation required by the permit, this certification must be signed and returned to the following address:

Email to:ChicagoRequests@usace.army.milSubject:Compliance Certification, LRC-2020-00661

Please note that your permitted activity is subject to compliance inspections by Corps of Engineers representatives. If you fail to comply with this permit, you may be subject to permit suspension, modification, or revocation.

¹ If compensatory mitigation was required as part of your authorization, you are certifying that the mitigation area has been graded and planted in accordance with the approved plan. You are acknowledging that the maintenance and monitoring period will begin after a site inspection by a Corps of Engineers representative or after thirty days of the Corps' receipt of this certification. You agree to comply with all permit terms and conditions, including additional reporting requirements, for the duration of the maintenance and monitoring period.

Nationwide Permit 14 - Linear Transportation Projects

Effective Date: February 25, 2022; Expiration Date: March 14, 2026 (NWP Final Notice, 86 FR 73522)

Nationwide Permit 14 - Linear Transportation Projects. Activities required for crossings of waters of the United States associated with the construction, expansion, modification, or improvement of linear transportation projects (e.g., roads, highways, railways, trails, driveways, airport runways, and taxiways) in waters of the United States. For linear transportation projects in non-tidal waters, the discharge of dredged or fill material cannot cause the loss of greater than 1/2-acre of waters of the United States. For linear transportation projects in tidal waters, the discharge of dredged or fill material cannot cause the loss of greater than 1/3-acre of waters of the United States. For linear transportation, including bank stabilization, is limited to the minimum necessary to construct or protect the linear transportation project; such modifications must be in the immediate vicinity of the project.

This NWP also authorizes temporary structures, fills, and work, including the use of temporary mats, necessary to construct the linear transportation project. Appropriate measures must be taken to maintain normal downstream flows and minimize flooding to the maximum extent practicable, when temporary structures, work, and discharges of dredged or fill material, including cofferdams, are necessary for construction activities, access fills, or dewatering of construction sites. Temporary fills must consist of materials, and be placed in a manner, that will not be eroded by expected high flows. Temporary fills must be removed in their entirety and the affected areas returned to preconstruction elevations. The areas affected by temporary fills must be revegetated, as appropriate.

This NWP cannot be used to authorize non-linear features commonly associated with transportation projects, such as vehicle maintenance or storage buildings, parking lots, train stations, or aircraft hangars.

<u>Notification</u>: The permittee must submit a pre-construction notification to the district engineer prior to commencing the activity if: (1) the loss of waters of the United States exceeds 1/10-acre; or (2) there is a discharge of dredged or fill material in a special aquatic site, including wetlands. (See general condition 32.) (Authorities: Sections 10 and 404)

<u>Note 1</u>: For linear transportation projects crossing a single waterbody more than one time at separate and distant locations, or multiple waterbodies at separate and distant locations, each crossing is considered a single and complete project for purposes of NWP authorization. Linear transportation projects must comply with 33 CFR 330.6(d).

<u>Note 2</u>: Some discharges of dredged or fill material for the construction of farm roads or forest roads, or temporary roads for moving mining equipment, may qualify for an exemption under Section 404(f) of the Clean Water Act (see 33 CFR 323.4).

<u>Note 3</u>: For NWP 14 activities that require pre-construction notification, the PCN must include any other NWP(s), regional general permit(s), or individual permit(s) used or intended to be used to authorize any part of the proposed project or any related activity, including other separate and distant crossings that require Department of the Army authorization but do not require pre-construction notification (see paragraph (b)(4) of general condition 32). The district engineer will evaluate the PCN in accordance with Section D, "District Engineer's Decision." The district engineer may require mitigation to ensure that the authorized activity results in no more than minimal individual and cumulative adverse environmental effects (see general condition 23).

2021 Nationwide Permit General Conditions

<u>Note</u>: To qualify for NWP authorization, the prospective permittee must comply with the following general conditions, as applicable, in addition to any regional or case-specific conditions imposed by the division engineer or district engineer. Prospective permittees should contact the appropriate Corps district office to determine if regional conditions have been imposed on an NWP. Prospective permittees should also contact the appropriate Corps district office to determine the status of Clean Water Act Section 401 water quality certification and/or Coastal Zone Management Act consistency for an NWP. Every person who may wish to obtain permit authorization under one or more NWPs, or who is currently relying on an existing or prior permit authorization under one or more or more NWPs, has been and is on notice that all of the provisions of 33 CFR 330.1 through 330.6 apply to every NWP authorization. Note especially 33 CFR 330.5 relating to the modification, suspension, or revocation of any NWP authorization.

1. **<u>Navigation</u>**. (a) No activity may cause more than a minimal adverse effect on navigation.

(b) Any safety lights and signals prescribed by the U.S. Coast Guard, through regulations or otherwise, must be installed and maintained at the permittee's expense on authorized facilities in navigable waters of the United States.

(c) The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his or her authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.

2. <u>Aquatic Life Movements</u>. No activity may substantially disrupt the necessary life cycle movements of those species of aquatic life indigenous to the waterbody, including those species that normally migrate through the area, unless the activity's primary purpose is to impound water. All permanent and temporary crossings of waterbodies shall be suitably culverted, bridged, or otherwise designed and constructed to maintain

low flows to sustain the movement of those aquatic species. If a bottomless culvert cannot be used, then the crossing should be designed and constructed to minimize adverse effects to aquatic life movements.

3. **Spawning Areas**. Activities in spawning areas during spawning seasons must be avoided to the maximum extent practicable. Activities that result in the physical destruction (e.g., through excavation, fill, or downstream smothering by substantial turbidity) of an important spawning area are not authorized.

4. <u>Migratory Bird Breeding Areas</u>. Activities in waters of the United States that serve as breeding areas for migratory birds must be avoided to the maximum extent practicable.

5. **Shellfish Beds.** No activity may occur in areas of concentrated shellfish populations, unless the activity is directly related to a shellfish harvesting activity authorized by NWPs 4 and 48, or is a shellfish seeding or habitat restoration activity authorized by NWP 27.

6. **Suitable Material.** No activity may use unsuitable material (e.g., trash, debris, car bodies, asphalt, etc.). Material used for construction or discharged must be free from toxic pollutants in toxic amounts (see section 307 of the Clean Water Act).

7. <u>Water Supply Intakes</u>. No activity may occur in the proximity of a public water supply intake, except where the activity is for the repair or improvement of public water supply intake structures or adjacent bank stabilization.

8. <u>Adverse Effects From Impoundments</u>. If the activity creates an impoundment of water, adverse effects to the aquatic system due to accelerating the passage of water, and/or restricting its flow must be minimized to the maximum extent practicable.

9. <u>Management of Water Flows</u>. To the maximum extent practicable, the preconstruction course, condition, capacity, and location of open waters must be maintained for each activity, including stream channelization, storm water management activities, and temporary and permanent road crossings, except as provided below. The activity must be constructed to withstand expected high flows. The activity must not restrict or impede the passage of normal or high flows, unless the primary purpose of the activity is to impound water or manage high flows. The activity may alter the preconstruction course, condition, capacity, and location of open waters if it benefits the aquatic environment (e.g., stream restoration or relocation activities).

10. **Fills Within 100-Year Floodplains.** The activity must comply with applicable FEMA-approved state or local floodplain management requirements.

11. **<u>Equipment</u>**. Heavy equipment working in wetlands or mudflats must be placed on mats, or other measures must be taken to minimize soil disturbance.

12. <u>Soil Erosion and Sediment Controls</u>. Appropriate soil erosion and sediment controls must be used and maintained in effective operating condition during construction, and all exposed soil and other fills, as well as any work below the ordinary high water mark or high tide line, must be permanently stabilized at the earliest practicable date. Permittees are encouraged to perform work within waters of the United States during periods of low-flow or no-flow, or during low tides.

13. <u>Removal of Temporary Structures and Fills</u>. Temporary structures must be removed, to the maximum extent practicable, after their use has been discontinued. Temporary fills must be removed in their entirety and the affected areas returned to preconstruction elevations. The affected areas must be revegetated, as appropriate.

14. **Proper Maintenance.** Any authorized structure or fill shall be properly maintained, including maintenance to ensure public safety and compliance with applicable NWP general conditions, as well as any activity-specific conditions added by the district engineer to an NWP authorization.

15. **Single and Complete Project.** The activity must be a single and complete project. The same NWP cannot be used more than once for the same single and complete project.

16. <u>Wild and Scenic Rivers</u>. (a) No NWP activity may occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, unless the appropriate Federal agency with direct management responsibility for such river, has determined in writing that the proposed activity will not adversely affect the Wild and Scenic River designation or study status.

(b) If a proposed NWP activity will occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, the permittee must submit a pre-construction notification (see general condition 32). The district engineer will coordinate the PCN with the Federal agency with direct management responsibility for that river. Permittees shall not begin the NWP activity until notified by the district engineer that the Federal agency with direct management responsibility for that river. Permittees shall not begin the NWP activity until notified by the district engineer that the Federal agency with direct management responsibility for that river has determined in writing that the proposed NWP activity will not adversely affect the Wild and Scenic River designation or study status.

(c) Information on Wild and Scenic Rivers may be obtained from the appropriate Federal land management agency responsible for the designated Wild and Scenic River or study river (e.g., National Park Service, U.S. Forest Service, Bureau of Land Management, U.S. Fish and Wildlife Service). Information on these rivers is also available at: http://www.rivers.gov/.

17. <u>**Tribal Rights.**</u> No activity or its operation may impair reserved tribal rights, including, but not limited to, reserved water rights and treaty fishing and hunting rights.

18. <u>Endangered Species</u>. (a) No activity is authorized under any NWP which is likely to directly or indirectly jeopardize the continued existence of a threatened or endangered species or a species proposed for such designation, as identified under the Federal Endangered Species Act (ESA), or which will directly or indirectly destroy or adversely modify designated critical habitat or critical habitat proposed for such designation. No activity is authorized under any NWP which "may affect" a listed species or critical habitat, unless ESA section 7 consultation addressing the consequences of the proposed activity on listed species or critical habitat has been completed. See 50 CFR 402.02 for the definition of "effects of the action" for the purposes of ESA section 7 consultation, as well as 50 CFR 402.17, which provides further explanation under ESA section 7 regarding "activities that are reasonably certain to occur" and "consequences caused by the proposed action."

(b) Federal agencies should follow their own procedures for complying with the requirements of the ESA (see 33 CFR 330.4(f)(1)). If pre-construction notification is required for the proposed activity, the Federal permittee must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements. The district engineer will verify that the appropriate documentation has been submitted. If the appropriate documentation has not been submitted, additional ESA section 7 consultation may be necessary for the activity and the respective federal agency would be responsible for fulfilling its obligation under section 7 of the ESA.

(c) Non-federal permittees must submit a pre-construction notification to the district engineer if any listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed such designation) might be affected or is in the vicinity of the activity, or if the activity is located in designated critical habitat or critical habitat proposed for such designation, and shall not begin work on the activity until notified by the district engineer that the requirements of the ESA have been satisfied and that the activity is authorized. For activities that might affect Federally-listed endangered or threatened species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation), the pre-construction notification must include the name(s) of the endangered or threatened species (or species proposed for listing) that might be affected by the proposed activity or that utilize the designated critical habitat (or critical habitat proposed for such designation) that might be affected by the proposed activity. The district engineer will determine whether the proposed activity "may affect" or will have "no effect" to listed species and designated critical habitat and will notify the non-Federal applicant of the Corps' determination within 45 days of receipt of a complete pre-construction notification. For activities where the non-Federal applicant has identified listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation) that might be affected or is in the vicinity of the activity, and has so notified the Corps, the applicant shall not begin work until the Corps has provided notification that the proposed activity will have "no effect" on listed species (or species proposed for listing or designated critical habitat (or critical habitat proposed for such designation), or until ESA section 7 consultation or conference has been completed. If the non-Federal

applicant has not heard back from the Corps within 45 days, the applicant must still wait for notification from the Corps.

(d) As a result of formal or informal consultation or conference with the FWS or NMFS the district engineer may add species-specific permit conditions to the NWPs.

(e) Authorization of an activity by an NWP does not authorize the "take" of a threatened or endangered species as defined under the ESA. In the absence of separate authorization (e.g., an ESA Section 10 Permit, a Biological Opinion with "incidental take" provisions, etc.) from the FWS or the NMFS, the Endangered Species Act prohibits any person subject to the jurisdiction of the United States to take a listed species, where "take" means to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect, or to attempt to engage in any such conduct. The word "harm" in the definition of "take" means an act which actually kills or injures wildlife. Such an act may include significant habitat modification or degradation where it actually kills or injures wildlife by significantly impairing essential behavioral patterns, including breeding, feeding or sheltering.

(f) If the non-federal permittee has a valid ESA section 10(a)(1)(B) incidental take permit with an approved Habitat Conservation Plan for a project or a group of projects that includes the proposed NWP activity, the non-federal applicant should provide a copy of that ESA section 10(a)(1)(B) permit with the PCN required by paragraph (c) of this general condition. The district engineer will coordinate with the agency that issued the ESA section 10(a)(1)(B) permit to determine whether the proposed NWP activity and the associated incidental take were considered in the internal ESA section 7 consultation conducted for the ESA section 10(a)(1)(B) permit. If that coordination results in concurrence from the agency that the proposed NWP activity and the associated incidental take were considered in the internal ESA section 7 consultation for the ESA section 10(a)(1)(B) permit, the district engineer does not need to conduct a separate ESA section 7 consultation for the proposed NWP activity. The district engineer will notify the non-federal applicant within 45 days of receipt of a complete preconstruction notification whether the ESA section 10(a)(1)(B) permit covers the proposed NWP activity or whether additional ESA section 7 consultation is required.

(g) Information on the location of threatened and endangered species and their critical habitat can be obtained directly from the offices of the FWS and NMFS or their world wide web pages at http://www.fws.gov/ or http://www.fws.gov/ipac and http://www.nmfs.noaa.gov/pr/species/esa/ respectively.

19. <u>Migratory Birds and Bald and Golden Eagles</u>. The permittee is responsible for ensuring that an action authorized by an NWP complies with the Migratory Bird Treaty Act and the Bald and Golden Eagle Protection Act. The permittee is responsible for contacting the appropriate local office of the U.S. Fish and Wildlife Service to determine what measures, if any, are necessary or appropriate to reduce adverse effects to migratory birds or eagles, including whether "incidental take" permits are necessary and available under the Migratory Bird Treaty Act or Bald and Golden Eagle Protection Act for a particular activity.

20. <u>Historic Properties</u>. (a) No activity is authorized under any NWP which may have the potential to cause effects to properties listed, or eligible for listing, in the National Register of Historic Places until the requirements of Section 106 of the National Historic Preservation Act (NHPA) have been satisfied.

(b) Federal permittees should follow their own procedures for complying with the requirements of section 106 of the National Historic Preservation Act (see 33 CFR 330.4(g)(1)). If pre-construction notification is required for the proposed NWP activity, the Federal permittee must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements. The district engineer will verify that the appropriate documentation has been submitted. If the appropriate documentation is not submitted, then additional consultation under section 106 may be necessary. The respective federal agency is responsible for fulfilling its obligation to comply with section 106.

(c) Non-federal permittees must submit a pre-construction notification to the district engineer if the NWP activity might have the potential to cause effects to any historic properties listed on, determined to be eligible for listing on, or potentially eligible for listing on the National Register of Historic Places, including previously unidentified properties. For such activities, the pre-construction notification must state which historic properties might have the potential to be affected by the proposed NWP activity or include a vicinity map indicating the location of the historic properties or the potential for the presence of historic properties. Assistance regarding information on the location of, or potential for, the presence of historic properties can be sought from the State Historic Preservation Officer, Tribal Historic Preservation Officer, or designated tribal representative, as appropriate, and the National Register of Historic Places (see 33 CFR 330.4(g)). When reviewing pre-construction notifications, district engineers will comply with the current procedures for addressing the requirements of section 106 of the National Historic Preservation Act. The district engineer shall make a reasonable and good faith effort to carry out appropriate identification efforts commensurate with potential impacts, which may include background research, consultation, oral history interviews, sample field investigation, and/or field survey. Based on the information submitted in the PCN and these identification efforts, the district engineer shall determine whether the proposed NWP activity has the potential to cause effects on the historic properties. Section 106 consultation is not required when the district engineer determines that the activity does not have the potential to cause effects on historic properties (see 36 CFR 800.3(a)). Section 106 consultation is required when the district engineer determines that the activity has the potential to cause effects on historic properties. The district engineer will conduct consultation with consulting parties identified under 36 CFR 800.2(c) when he or she makes any of the following effect determinations for the purposes of section 106 of the NHPA: no historic properties affected, no adverse effect, or adverse effect.

(d) Where the non-Federal applicant has identified historic properties on which the proposed NWP activity might have the potential to cause effects and has so notified the Corps, the non-Federal applicant shall not begin the activity until notified by the district engineer either that the activity has no potential to cause effects to historic properties or that NHPA section 106 consultation has been completed. For non-federal permittees, the district engineer will notify the prospective permittee within 45 days of receipt of a complete pre-construction notification whether NHPA section 106 consultation is required. If NHPA section 106 consultation is required, the district engineer will notify the non-Federal applicant that he or she cannot begin the activity until section 106 consultation is completed. If the non-Federal applicant has not heard back from the Corps within 45 days, the applicant must still wait for notification from the Corps.

(e) Prospective permittees should be aware that section 110k of the NHPA (54 U.S.C. 306113) prevents the Corps from granting a permit or other assistance to an applicant who, with intent to avoid the requirements of section 106 of the NHPA, has intentionally significantly adversely affected a historic property to which the permit would relate, or having legal power to prevent it, allowed such significant adverse effect to occur, unless the Corps, after consultation with the Advisory Council on Historic Preservation (ACHP), determines that circumstances justify granting such assistance despite the adverse effect created or permitted by the applicant. If circumstances justify granting the assistance, the Corps is required to notify the ACHP and provide documentation specifying the circumstances, the degree of damage to the integrity of any historic properties affected, and proposed mitigation. This documentation must include any views obtained from the applicant, SHPO/THPO, appropriate Indian tribes if the undertaking occurs on or affects historic properties on tribal lands or affects properties of interest to those tribes, and other parties known to have a legitimate interest in the impacts to the permitted activity on historic properties.

21. **Discovery of Previously Unknown Remains and Artifacts.** Permittees that discover any previously unknown historic, cultural or archeological remains and artifacts while accomplishing the activity authorized by an NWP, they must immediately notify the district engineer of what they have found, and to the maximum extent practicable, avoid construction activities that may affect the remains and artifacts until the required coordination has been completed. The district engineer will initiate the Federal, Tribal, and state coordination required to determine if the items or remains warrant a recovery effort or if the site is eligible for listing in the National Register of Historic Places.

22. <u>Designated Critical Resource Waters</u>. Critical resource waters include, NOAAmanaged marine sanctuaries and marine monuments, and National Estuarine Research Reserves. The district engineer may designate, after notice and opportunity for public comment, additional waters officially designated by a state as having particular environmental or ecological significance, such as outstanding national resource waters or state natural heritage sites. The district engineer may also designate additional critical resource waters after notice and opportunity for public comment. (a) Discharges of dredged or fill material into waters of the United States are not authorized by NWPs 7, 12, 14, 16, 17, 21, 29, 31, 35, 39, 40, 42, 43, 44, 49, 50, 51, 52, 57 and 58 for any activity within, or directly affecting, critical resource waters, including wetlands adjacent to such waters.

(b) For NWPs 3, 8, 10, 13, 15, 18, 19, 22, 23, 25, 27, 28, 30, 33, 34, 36, 37, 38, and 54, notification is required in accordance with general condition 32, for any activity proposed by permittees in the designated critical resource waters including wetlands adjacent to those waters. The district engineer may authorize activities under these NWPs only after she or he determines that the impacts to the critical resource waters will be no more than minimal.

23. <u>Mitigation</u>. The district engineer will consider the following factors when determining appropriate and practicable mitigation necessary to ensure that the individual and cumulative adverse environmental effects are no more than minimal:

(a) The activity must be designed and constructed to avoid and minimize adverse effects, both temporary and permanent, to waters of the United States to the maximum extent practicable at the project site (i.e., on site).

(b) Mitigation in all its forms (avoiding, minimizing, rectifying, reducing, or compensating for resource losses) will be required to the extent necessary to ensure that the individual and cumulative adverse environmental effects are no more than minimal.

(c) Compensatory mitigation at a minimum one-for-one ratio will be required for all wetland losses that exceed 1/10-acre and require pre-construction notification, unless the district engineer determines in writing that either some other form of mitigation would be more environmentally appropriate or the adverse environmental effects of the proposed activity are no more than minimal, and provides an activity-specific waiver of this requirement. For wetland losses of 1/10-acre or less that require pre-construction notification, the district engineer may determine on a case-by-case basis that compensatory mitigation is required to ensure that the activity results in only minimal adverse environmental effects.

(d) Compensatory mitigation at a minimum one-for-one ratio will be required for all losses of stream bed that exceed 3/100-acre and require pre-construction notification, unless the district engineer determines in writing that either some other form of mitigation would be more environmentally appropriate or the adverse environmental effects of the proposed activity are no more than minimal, and provides an activity-specific waiver of this requirement. This compensatory mitigation requirement may be satisfied through the restoration or enhancement of riparian areas next to streams in accordance with paragraph (e) of this general condition. For losses of stream bed of 3/100-acre or less that require pre-construction notification, the district engineer may determine on a case-by-case basis that compensatory mitigation is required to ensure that the activity results in only minimal adverse environmental effects. Compensatory mitigation for losses of streams should be provided, if practicable, through stream

rehabilitation, enhancement, or preservation, since streams are difficult-to-replace resources (see 33 CFR 332.3(e)(3)).

(e) Compensatory mitigation plans for NWP activities in or near streams or other open waters will normally include a requirement for the restoration or enhancement, maintenance, and legal protection (e.g., conservation easements) of riparian areas next to open waters. In some cases, the restoration or maintenance/protection of riparian areas may be the only compensatory mitigation required. If restoring riparian areas involves planting vegetation, only native species should be planted. The width of the required riparian area will address documented water quality or aquatic habitat loss concerns. Normally, the riparian area will be 25 to 50 feet wide on each side of the stream, but the district engineer may require slightly wider riparian areas to address documented water quality or habitat loss concerns. If it is not possible to restore or maintain/protect a riparian area on both sides of a stream, or if the waterbody is a lake or coastal waters, then restoring or maintaining/protecting a riparian area along a single bank or shoreline may be sufficient. Where both wetlands and open waters exist on the project site, the district engineer will determine the appropriate compensatory mitigation (e.g., riparian areas and/or wetlands compensation) based on what is best for the aquatic environment on a watershed basis. In cases where riparian areas are determined to be the most appropriate form of minimization or compensatory mitigation, the district engineer may waive or reduce the requirement to provide wetland compensatory mitigation for wetland losses.

(f) Compensatory mitigation projects provided to offset losses of aquatic resources must comply with the applicable provisions of 33 CFR part 332.

(1) The prospective permittee is responsible for proposing an appropriate compensatory mitigation option if compensatory mitigation is necessary to ensure that the activity results in no more than minimal adverse environmental effects. For the NWPs, the preferred mechanism for providing compensatory mitigation is mitigation bank credits or in-lieu fee program credits (see 33 CFR 332.3(b)(2) and (3)). However, if an appropriate number and type of mitigation bank or in-lieu credits are not available at the time the PCN is submitted to the district engineer, the district engineer may approve the use of permittee-responsible mitigation.

(2) The amount of compensatory mitigation required by the district engineer must be sufficient to ensure that the authorized activity results in no more than minimal individual and cumulative adverse environmental effects (see 33 CFR 330.1(e)(3)). (See also 33 CFR 332.3(f).)

(3) Since the likelihood of success is greater and the impacts to potentially valuable uplands are reduced, aquatic resource restoration should be the first compensatory mitigation option considered for permittee-responsible mitigation.

(4) If permittee-responsible mitigation is the proposed option, the prospective permittee is responsible for submitting a mitigation plan. A conceptual or detailed mitigation plan

may be used by the district engineer to make the decision on the NWP verification request, but a final mitigation plan that addresses the applicable requirements of 33 CFR 332.4(c)(2) through (14) must be approved by the district engineer before the permittee begins work in waters of the United States, unless the district engineer determines that prior approval of the final mitigation plan is not practicable or not necessary to ensure timely completion of the required compensatory mitigation (see 33 CFR 332.3(k)(3)). If permittee-responsible mitigation is the proposed option, and the proposed compensatory mitigation site is located on land in which another federal agency holds an easement, the district engineer will coordinate with that federal agency to determine if proposed compensatory mitigation project is compatible with the terms of the easement.

(5) If mitigation bank or in-lieu fee program credits are the proposed option, the mitigation plan needs to address only the baseline conditions at the impact site and the number of credits to be provided (see 33 CFR 332.4(c)(1)(ii)).

(6) Compensatory mitigation requirements (e.g., resource type and amount to be provided as compensatory mitigation, site protection, ecological performance standards, monitoring requirements) may be addressed through conditions added to the NWP authorization, instead of components of a compensatory mitigation plan (see 33 CFR 332.4(c)(1)(ii)).

(g) Compensatory mitigation will not be used to increase the acreage losses allowed by the acreage limits of the NWPs. For example, if an NWP has an acreage limit of 1/2-acre, it cannot be used to authorize any NWP activity resulting in the loss of greater than 1/2-acre of waters of the United States, even if compensatory mitigation is provided that replaces or restores some of the lost waters. However, compensatory mitigation can and should be used, as necessary, to ensure that an NWP activity already meeting the established acreage limits also satisfies the no more than minimal impact requirement for the NWPs.

(h) Permittees may propose the use of mitigation banks, in-lieu fee programs, or permittee-responsible mitigation. When developing a compensatory mitigation proposal, the permittee must consider appropriate and practicable options consistent with the framework at 33 CFR 332.3(b). For activities resulting in the loss of marine or estuarine resources, permittee-responsible mitigation may be environmentally preferable if there are no mitigation banks or in-lieu fee programs in the area that have marine or estuarine credits available for sale or transfer to the permittee. For permittee-responsible mitigation, the special conditions of the NWP verification must clearly indicate the party or parties responsible for the implementation and performance of the compensatory mitigation project, and, if required, its long-term management.

(i) Where certain functions and services of waters of the United States are permanently adversely affected by a regulated activity, such as discharges of dredged or fill material into waters of the United States that will convert a forested or scrub-shrub wetland to a herbaceous wetland in a permanently maintained utility line right-of-way, mitigation may

be required to reduce the adverse environmental effects of the activity to the no more than minimal level.

24. **Safety of Impoundment Structures**. To ensure that all impoundment structures are safely designed, the district engineer may require non-Federal applicants to demonstrate that the structures comply with established state or federal, dam safety criteria or have been designed by qualified persons. The district engineer may also require documentation that the design has been independently reviewed by similarly qualified persons, and appropriate modifications made to ensure safety.

25. <u>Water Quality</u>. (a) Where the certifying authority (state, authorized tribe, or EPA, as appropriate) has not previously certified compliance of an NWP with CWA section 401, a CWA section 401 water quality certification for the proposed discharge must be obtained or waived (see 33 CFR 330.4(c)). If the permittee cannot comply with all of the conditions of a water quality certification previously issued by certifying authority for the issuance of the NWP, then the permittee must obtain a water quality certification or waiver for the proposed discharge in order for the activity to be authorized by an NWP.

(b) If the NWP activity requires pre-construction notification and the certifying authority has not previously certified compliance of an NWP with CWA section 401, the proposed discharge is not authorized by an NWP until water quality certification is obtained or waived. If the certifying authority issues a water quality certification for the proposed discharge, the permittee must submit a copy of the certification to the district engineer. The discharge is not authorized by an NWP until the district engineer has notified the permittee that the water quality certification requirement has been satisfied by the issuance of a water quality certification or a waiver.

(c) The district engineer or certifying authority may require additional water quality management measures to ensure that the authorized activity does not result in more than minimal degradation of water quality.

26. <u>Coastal Zone Management</u>. In coastal states where an NWP has not previously received a state coastal zone management consistency concurrence, an individual state coastal zone management consistency concurrence must be obtained, or a presumption of concurrence must occur (see 33 CFR 330.4(d)). If the permittee cannot comply with all of the conditions of a coastal zone management consistency concurrence previously issued by the state, then the permittee must obtain an individual coastal zone management consistency concurrence or presumption of concurrence in order for the activity to be authorized by an NWP. The district engineer or a state may require additional measures to ensure that the authorized activity is consistent with state coastal zone management requirements.

27. <u>Regional and Case-By-Case Conditions</u>. The activity must comply with any regional conditions that may have been added by the Division Engineer (see 33 CFR 330.4(e)) and with any case specific conditions added by the Corps or by the state,

Indian Tribe, or U.S. EPA in its CWA section 401 Water Quality Certification, or by the state in its Coastal Zone Management Act consistency determination.

28. <u>Use of Multiple Nationwide Permits</u>. The use of more than one NWP for a single and complete project is authorized, subject to the following restrictions:

(a) If only one of the NWPs used to authorize the single and complete project has a specified acreage limit, the acreage loss of waters of the United States cannot exceed the acreage limit of the NWP with the highest specified acreage limit. For example, if a road crossing over tidal waters is constructed under NWP 14, with associated bank stabilization authorized by NWP 13, the maximum acreage loss of waters of the United States for the total project cannot exceed 1/3-acre.

(b) If one or more of the NWPs used to authorize the single and complete project has specified acreage limits, the acreage loss of waters of the United States authorized by those NWPs cannot exceed their respective specified acreage limits. For example, if a commercial development is constructed under NWP 39, and the single and complete project includes the filling of an upland ditch authorized by NWP 46, the maximum acreage loss of waters of the United States for the commercial development under NWP 39 cannot exceed 1/2-acre, and the total acreage loss of waters of United States due to the NWP 39 and 46 activities cannot exceed 1 acre.

29. <u>Transfer of Nationwide Permit Verifications</u>. If the permittee sells the property associated with a nationwide permit verification, the permittee may transfer the nationwide permit verification to the new owner by submitting a letter to the appropriate Corps district office to validate the transfer. A copy of the nationwide permit verification must be attached to the letter, and the letter must contain the following statement and signature:

"When the structures or work authorized by this nationwide permit are still in existence at the time the property is transferred, the terms and conditions of this nationwide permit, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer of this nationwide permit and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below."

(Transferee)

(Date)

30. <u>**Compliance Certification</u>**. Each permittee who receives an NWP verification letter from the Corps must provide a signed certification documenting completion of the authorized activity and implementation of any required compensatory mitigation. The success of any required permittee-responsible mitigation, including the achievement of ecological performance standards, will be addressed separately by the district engineer. The Corps will provide the permittee the certification document with the NWP verification letter. The certification document will include:</u>

(a) A statement that the authorized activity was done in accordance with the NWP authorization, including any general, regional, or activity-specific conditions;

(b) A statement that the implementation of any required compensatory mitigation was completed in accordance with the permit conditions. If credits from a mitigation bank or in-lieu fee program are used to satisfy the compensatory mitigation requirements, the certification must include the documentation required by 33 CFR 332.3(I)(3) to confirm that the permittee secured the appropriate number and resource type of credits; and

(c) The signature of the permittee certifying the completion of the activity and mitigation.

The completed certification document must be submitted to the district engineer within 30 days of completion of the authorized activity or the implementation of any required compensatory mitigation, whichever occurs later.

31. <u>Activities Affecting Structures or Works Built by the United States</u>. If an NWP activity also requires review by, or permission from, the Corps pursuant to 33 U.S.C. 408 because it will alter or temporarily or permanently occupy or use a U.S. Army Corps of Engineers (USACE) federally authorized Civil Works project (a "USACE project"), the prospective permittee must submit a pre-construction notification. See paragraph (b)(10) of general condition 32. An activity that requires section 408 permission and/or review is not authorized by an NWP until the appropriate Corps office issues the section 408 permission or completes its review to alter, occupy, or use the USACE project, and the district engineer issues a written NWP verification.

32. **Pre-Construction Notification**. (a) *Timing*. Where required by the terms of the NWP, the prospective permittee must notify the district engineer by submitting a preconstruction notification (PCN) as early as possible. The district engineer must determine if the PCN is complete within 30 calendar days of the date of receipt and, if the PCN is determined to be incomplete, notify the prospective permittee within that 30 day period to request the additional information necessary to make the PCN complete. The request must specify the information needed to make the PCN complete. As a general rule, district engineers will request additional information necessary to make the PCN complete all of the requested information, then the district engineer will notify the prospective permittee that the PCN is still incomplete and the PCN review process will not commence until all of the requested information has been received by the district engineer. The prospective permittee shall not begin the activity until either: (1) He or she is notified in writing by the district engineer that the activity may proceed under the NWP with any special conditions imposed by the district or division engineer; or

(2) 45 calendar days have passed from the district engineer's receipt of the complete PCN and the prospective permittee has not received written notice from the district or division engineer. However, if the permittee was required to notify the Corps pursuant to general condition 18 that listed species or critical habitat might be affected or are in the vicinity of the activity, or to notify the Corps pursuant to general condition 20 that the activity might have the potential to cause effects to historic properties, the permittee cannot begin the activity until receiving written notification from the Corps that there is "no effect" on listed species or "no potential to cause effects" on historic properties, or that any consultation required under Section 7 of the Endangered Species Act (see 33 CFR 330.4(f)) and/or section 106 of the National Historic Preservation Act (see 33 CFR 330.4(g)) has been completed. If the proposed activity requires a written waiver to exceed specified limits of an NWP, the permittee may not begin the activity until the district engineer issues the waiver. If the district or division engineer notifies the permittee in writing that an individual permit is required within 45 calendar days of receipt of a complete PCN, the permittee cannot begin the activity until an individual permit has been obtained. Subsequently, the permittee's right to proceed under the NWP may be modified, suspended, or revoked only in accordance with the procedure set forth in 33 CFR 330.5(d)(2).

(b) *Contents of Pre-Construction Notification*: The PCN must be in writing and include the following information:

(1) Name, address and telephone numbers of the prospective permittee;

(2) Location of the proposed activity;

(3) Identify the specific NWP or NWP(s) the prospective permittee wants to use to authorize the proposed activity;

(4) (i) A description of the proposed activity; the activity's purpose; direct and indirect adverse environmental effects the activity would cause, including the anticipated amount of loss of wetlands, other special aquatic sites, and other waters expected to result from the NWP activity, in acres, linear feet, or other appropriate unit of measure; a description of any proposed mitigation measures intended to reduce the adverse environmental effects caused by the proposed activity; and any other NWP(s), regional general permit(s), or individual permit(s) used or intended to be used to authorize any part of the proposed project or any related activity, including other separate and distant crossings for linear projects that require Department of the Army authorization but do not require pre-construction notification. The description of the proposed activity and any proposed mitigation measures should be sufficiently detailed to allow the district engineer to determine that the adverse environmental effects of the activity will be no

more than minimal and to determine the need for compensatory mitigation or other mitigation measures.

(ii) For linear projects where one or more single and complete crossings require preconstruction notification, the PCN must include the quantity of anticipated losses of wetlands, other special aquatic sites, and other waters for each single and complete crossing of those wetlands, other special aquatic sites, and other waters (including those single and complete crossings authorized by an NWP but do not require PCNs). This information will be used by the district engineer to evaluate the cumulative adverse environmental effects of the proposed linear project, and does not change those non-PCN NWP activities into NWP PCNs.

(iii) Sketches should be provided when necessary to show that the activity complies with the terms of the NWP. (Sketches usually clarify the activity and when provided results in a quicker decision. Sketches should contain sufficient detail to provide an illustrative description of the proposed activity (e.g., a conceptual plan), but do not need to be detailed engineering plans);

(5) The PCN must include a delineation of wetlands, other special aquatic sites, and other waters, such as lakes and ponds, and perennial and intermittent streams, on the project site. Wetland delineations must be prepared in accordance with the current method required by the Corps. The permittee may ask the Corps to delineate the special aquatic sites and other waters on the project site, but there may be a delay if the Corps does the delineation, especially if the project site is large or contains many wetlands, other special aquatic sites, and other waters. Furthermore, the 45-day period will not start until the delineation has been submitted to or completed by the Corps, as appropriate;

(6) If the proposed activity will result in the loss of greater than 1/10-acre of wetlands or 3/100-acre of stream bed and a PCN is required, the prospective permittee must submit a statement describing how the mitigation requirement will be satisfied, or explaining why the adverse environmental effects are no more than minimal and why compensatory mitigation should not be required. As an alternative, the prospective permittee may submit a conceptual or detailed mitigation plan.

(7) For non-federal permittees, if any listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation) might be affected or is in the vicinity of the activity, or if the activity is located in designated critical habitat (or critical habitat proposed for such designation), the PCN must include the name(s) of those endangered or threatened species (or species proposed for listing) that might be affected by the proposed activity or utilize the designated critical habitat (or critical habitat proposed for such designation) that might be affected by the proposed for such designation) that might be affected by the proposed activity. For NWP activities that require pre-construction notification, Federal permittees must provide documentation demonstrating compliance with the Endangered Species Act;

(8) For non-federal permittees, if the NWP activity might have the potential to cause effects to a historic property listed on, determined to be eligible for listing on, or potentially eligible for listing on, the National Register of Historic Places, the PCN must state which historic property might have the potential to be affected by the proposed activity or include a vicinity map indicating the location of the historic property. For NWP activities that require pre-construction notification, Federal permittees must provide documentation demonstrating compliance with section 106 of the National Historic Preservation Act;

(9) For an activity that will occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, the PCN must identify the Wild and Scenic River or the "study river" (see general condition 16); and

(10) For an NWP activity that requires permission from, or review by, the Corps pursuant to 33 U.S.C. 408 because it will alter or temporarily or permanently occupy or use a U.S. Army Corps of Engineers federally authorized civil works project, the preconstruction notification must include a statement confirming that the project proponent has submitted a written request for section 408 permission from, or review by, the Corps office having jurisdiction over that USACE project.

(c) *Form of Pre-Construction Notification*: The nationwide permit pre-construction notification form (Form ENG 6082) should be used for NWP PCNs. A letter containing the required information may also be used. Applicants may provide electronic files of PCNs and supporting materials if the district engineer has established tools and procedures for electronic submittals.

(d) *Agency Coordination*: (1) The district engineer will consider any comments from Federal and state agencies concerning the proposed activity's compliance with the terms and conditions of the NWPs and the need for mitigation to reduce the activity's adverse environmental effects so that they are no more than minimal.

(2) Agency coordination is required for: (i) all NWP activities that require preconstruction notification and result in the loss of greater than 1/2-acre of waters of the United States; (ii) NWP 13 activities in excess of 500 linear feet, fills greater than one cubic yard per running foot, or involve discharges of dredged or fill material into special aquatic sites; and (iii) NWP 54 activities in excess of 500 linear feet, or that extend into the waterbody more than 30 feet from the mean low water line in tidal waters or the ordinary high water mark in the Great Lakes.

(3) When agency coordination is required, the district engineer will immediately provide (e.g., via e-mail, facsimile transmission, overnight mail, or other expeditious manner) a copy of the complete PCN to the appropriate Federal or state offices (FWS, state natural resource or water quality agency, EPA, and, if appropriate, the NMFS). With the exception of NWP 37, these agencies will have 10 calendar days from the date the material is transmitted to notify the district engineer via telephone, facsimile

transmission, or e-mail that they intend to provide substantive, site-specific comments. The comments must explain why the agency believes the adverse environmental effects will be more than minimal. If so contacted by an agency, the district engineer will wait an additional 15 calendar days before making a decision on the pre-construction notification. The district engineer will fully consider agency comments received within the specified time frame concerning the proposed activity's compliance with the terms and conditions of the NWPs, including the need for mitigation to ensure that the net adverse environmental effects of the proposed activity are no more than minimal. The district engineer will provide no response to the resource agency, except as provided below. The district engineer will indicate in the administrative record associated with each pre-construction notification that the resource agencies' concerns were considered. For NWP 37, the emergency watershed protection and rehabilitation activity may proceed immediately in cases where there is an unacceptable hazard to life or a significant loss of property or economic hardship will occur. The district engineer will consider any comments received to decide whether the NWP 37 authorization should be modified, suspended, or revoked in accordance with the procedures at 33 CFR 330.5.

(4) In cases of where the prospective permittee is not a Federal agency, the district engineer will provide a response to NMFS within 30 calendar days of receipt of any Essential Fish Habitat conservation recommendations, as required by section 305(b)(4)(B) of the Magnuson-Stevens Fishery Conservation and Management Act.

(5) Applicants are encouraged to provide the Corps with either electronic files or multiple copies of pre-construction notifications to expedite agency coordination.

2021 District Engineer's Decision

1. In reviewing the PCN for the proposed activity, the district engineer will determine whether the activity authorized by the NWP will result in more than minimal individual or cumulative adverse environmental effects or may be contrary to the public interest. If a project proponent requests authorization by a specific NWP, the district engineer should issue the NWP verification for that activity if it meets the terms and conditions of that NWP, unless he or she determines, after considering mitigation, that the proposed activity will result in more than minimal individual and cumulative adverse effects on the aquatic environment and other aspects of the public interest and exercises discretionary authority to require an individual permit for the proposed activity. For a linear project, this determination will include an evaluation of the single and complete crossings of waters of the United States that require PCNs to determine whether they individually satisfy the terms and conditions of the NWP(s), as well as the cumulative effects caused by all of the crossings of waters of the United States authorized by an NWP. If an applicant requests a waiver of an applicable limit, as provided for in NWPs 13, 36, or 54, the district engineer will only grant the waiver upon a written determination that the NWP activity will result in only minimal individual and cumulative adverse environmental effects.

2. When making minimal adverse environmental effects determinations the district engineer will consider the direct and indirect effects caused by the NWP activity. He or she will also consider the cumulative adverse environmental effects caused by activities authorized by an NWP and whether those cumulative adverse environmental effects are no more than minimal. The district engineer will also consider site specific factors, such as the environmental setting in the vicinity of the NWP activity, the type of resource that will be affected by the NWP activity, the functions provided by the aquatic resources that will be affected by the NWP activity, the degree or magnitude to which the aquatic resources perform those functions, the extent that aquatic resource functions will be lost as a result of the NWP activity (e.g., partial or complete loss), the duration of the adverse effects (temporary or permanent), the importance of the aquatic resource functions to the region (e.g., watershed or ecoregion), and mitigation required by the district engineer. If an appropriate functional or condition assessment method is available and practicable to use, that assessment method may be used by the district engineer to assist in the minimal adverse environmental effects determination. The district engineer may add case-specific special conditions to the NWP authorization to address site-specific environmental concerns.

3. If the proposed activity requires a PCN and will result in a loss of greater than 1/10acre of wetlands or 3/100-acre of stream bed, the prospective permittee should submit a mitigation proposal with the PCN. Applicants may also propose compensatory mitigation for NWP activities with smaller impacts, or for impacts to other types of waters. The district engineer will consider any proposed compensatory mitigation or other mitigation measures the applicant has included in the proposal in determining whether the net adverse environmental effects of the proposed activity are no more than minimal. The compensatory mitigation proposal may be either conceptual or detailed. If the district engineer determines that the activity complies with the terms and conditions of the NWP and that the adverse environmental effects are no more than minimal, after considering mitigation, the district engineer will notify the permittee and include any activity-specific conditions in the NWP verification the district engineer deems necessary. Conditions for compensatory mitigation requirements must comply with the appropriate provisions at 33 CFR 332.3(k). The district engineer must approve the final mitigation plan before the permittee commences work in waters of the United States, unless the district engineer determines that prior approval of the final mitigation plan is not practicable or not necessary to ensure timely completion of the required compensatory mitigation. If the prospective permittee elects to submit a compensatory mitigation plan with the PCN, the district engineer will expeditiously review the proposed compensatory mitigation plan. The district engineer must review the proposed compensatory mitigation plan within 45 calendar days of receiving a complete PCN and determine whether the proposed mitigation would ensure that the NWP activity results in no more than minimal adverse environmental effects. If the net adverse environmental effects of the NWP activity (after consideration of the mitigation proposal) are determined by the district engineer to be no more than minimal, the district engineer will provide a timely written response to the applicant. The response will state that the NWP activity can proceed under the terms and conditions of the NWP, including any activity-specific conditions added to the NWP authorization by the district engineer.

4. If the district engineer determines that the adverse environmental effects of the proposed activity are more than minimal, then the district engineer will notify the applicant either: (a) that the activity does not qualify for authorization under the NWP and instruct the applicant on the procedures to seek authorization under an individual permit; (b) that the activity is authorized under the NWP subject to the applicant's submission of a mitigation plan that would reduce the adverse environmental effects so that they are no more than minimal; or (c) that the activity is authorized under the NWP with specific modifications or conditions. Where the district engineer determines that mitigation is required to ensure no more than minimal adverse environmental effects, the activity will be authorized within the 45-day PCN period (unless additional time is required to comply with general conditions 18, 20, and/or 31), with activity-specific conditions that state the mitigation requirements. The authorization will include the necessary conceptual or detailed mitigation plan or a requirement that the applicant submit a mitigation plan that would reduce the adverse environmental effects so that they are no more than minimal. When compensatory mitigation is required, no work in waters of the United States may occur until the district engineer has approved a specific mitigation plan or has determined that prior approval of a final mitigation plan is not practicable or not necessary to ensure timely completion of the required compensatory mitigation.

2021 Further Information

1. District engineers have authority to determine if an activity complies with the terms and conditions of an NWP.

2. NWPs do not obviate the need to obtain other federal, state, or local permits, approvals, or authorizations required by law.

3. NWPs do not grant any property rights or exclusive privileges.

4. NWPs do not authorize any injury to the property or rights of others.

5. NWPs do not authorize interference with any existing or proposed Federal project (see general condition 31).

2021 Nationwide Permit Definitions

Best management practices (BMPs): Policies, practices, procedures, or structures implemented to mitigate the adverse environmental effects on surface water quality resulting from development. BMPs are categorized as structural or non-structural.

<u>Compensatory mitigation</u>: The restoration (re-establishment or rehabilitation), establishment (creation), enhancement, and/or in certain circumstances preservation of aquatic resources for the purposes of offsetting unavoidable adverse impacts which

remain after all appropriate and practicable avoidance and minimization has been achieved.

<u>Currently serviceable</u>: Useable as is or with some maintenance, but not so degraded as to essentially require reconstruction.

<u>Direct effects</u>: Effects that are caused by the activity and occur at the same time and place.

Discharge: The term "discharge" means any discharge of dredged or fill material into waters of the United States.

Ecological reference: A model used to plan and design an aquatic habitat and riparian area restoration, enhancement, or establishment activity under NWP 27. An ecological reference may be based on the structure, functions, and dynamics of an aquatic habitat type or a riparian area type that currently exists in the region where the proposed NWP 27 activity is located. Alternatively, an ecological reference may be based on a conceptual model for the aquatic habitat type or riparian area type to be restored, enhanced, or established as a result of the proposed NWP 27 activity. An ecological reference takes into account the range of variation of the aquatic habitat type or riparian area type in the region.

Enhancement: The manipulation of the physical, chemical, or biological characteristics of an aquatic resource to heighten, intensify, or improve a specific aquatic resource function(s). Enhancement results in the gain of selected aquatic resource function(s), but may also lead to a decline in other aquatic resource function(s). Enhancement does not result in a gain in aquatic resource area.

Establishment (creation): The manipulation of the physical, chemical, or biological characteristics present to develop an aquatic resource that did not previously exist at an upland site. Establishment results in a gain in aquatic resource area.

High Tide Line: The line of intersection of the land with the water's surface at the maximum height reached by a rising tide. The high tide line may be determined, in the absence of actual data, by a line of oil or scum along shore objects, a more or less continuous deposit of fine shell or debris on the foreshore or berm, other physical markings or characteristics, vegetation lines, tidal gages, or other suitable means that delineate the general height reached by a rising tide. The line encompasses spring high tides and other high tides that occur with periodic frequency but does not include storm surges in which there is a departure from the normal or predicted reach of the tide due to the piling up of water against a coast by strong winds such as those accompanying a hurricane or other intense storm.

<u>Historic Property</u>: Any prehistoric or historic district, site (including archaeological site), building, structure, or other object included in, or eligible for inclusion in, the National Register of Historic Places maintained by the Secretary of the Interior. This

term includes artifacts, records, and remains that are related to and located within such properties. The term includes properties of traditional religious and cultural importance to an Indian tribe or Native Hawaiian organization and that meet the National Register criteria (36 CFR part 60).

Independent utility: A test to determine what constitutes a single and complete nonlinear project in the Corps Regulatory Program. A project is considered to have independent utility if it would be constructed absent the construction of other projects in the project area. Portions of a multi-phase project that depend upon other phases of the project do not have independent utility. Phases of a project that would be constructed even if the other phases were not built can be considered as separate single and complete projects with independent utility.

Indirect effects: Effects that are caused by the activity and are later in time or farther removed in distance, but are still reasonably foreseeable.

Loss of waters of the United States: Waters of the United States that are permanently adversely affected by filling, flooding, excavation, or drainage because of the regulated activity. The loss of stream bed includes the acres of stream bed that are permanently adversely affected by filling or excavation because of the regulated activity. Permanent adverse effects include permanent discharges of dredged or fill material that change an aguatic area to dry land, increase the bottom elevation of a waterbody, or change the use of a waterbody. The acreage of loss of waters of the United States is a threshold measurement of the impact to jurisdictional waters or wetlands for determining whether a project may qualify for an NWP; it is not a net threshold that is calculated after considering compensatory mitigation that may be used to offset losses of aquatic functions and services. Waters of the United States temporarily filled, flooded, excavated, or drained, but restored to pre-construction contours and elevations after construction, are not included in the measurement of loss of waters of the United States. Impacts resulting from activities that do not require Department of the Army authorization, such as activities eligible for exemptions under section 404(f) of the Clean Water Act, are not considered when calculating the loss of waters of the United States.

<u>Navigable waters</u>: Waters subject to section 10 of the Rivers and Harbors Act of 1899. These waters are defined at 33 CFR part 329.

Non-tidal wetland: A non-tidal wetland is a wetland that is not subject to the ebb and flow of tidal waters. Non-tidal wetlands contiguous to tidal waters are located landward of the high tide line (i.e., spring high tide line).

Open water: For purposes of the NWPs, an open water is any area that in a year with normal patterns of precipitation has water flowing or standing above ground to the extent that an ordinary high water mark can be determined. Aquatic vegetation within the area of flowing or standing water is either non-emergent, sparse, or absent. Vegetated shallows are considered to be open waters. Examples of "open waters" include rivers, streams, lakes, and ponds.

Ordinary High Water Mark: The term ordinary high water mark means that line on the shore established by the fluctuations of water and indicated by physical characteristics such as a clear, natural line impressed on the bank, shelving, changes in the character of soil, destruction of terrestrial vegetation, the presence of litter and debris, or other appropriate means that consider the characteristics of the surrounding areas.

<u>Perennial stream</u>: A perennial stream has surface water flowing continuously yearround during a typical year.

<u>Practicable</u>: Available and capable of being done after taking into consideration cost, existing technology, and logistics in light of overall project purposes.

Pre-construction notification: A request submitted by the project proponent to the Corps for confirmation that a particular activity is authorized by nationwide permit. The request may be a permit application, letter, or similar document that includes information about the proposed work and its anticipated environmental effects. Pre-construction notification may be required by the terms and conditions of a nationwide permit, or by regional conditions. A pre-construction notification may be voluntarily submitted in cases where pre-construction notification is not required and the project proponent wants confirmation that the activity is authorized by nationwide permit.

Preservation: The removal of a threat to, or preventing the decline of, aquatic resources by an action in or near those aquatic resources. This term includes activities commonly associated with the protection and maintenance of aquatic resources through the implementation of appropriate legal and physical mechanisms. Preservation does not result in a gain of aquatic resource area or functions.

<u>Re-establishment</u>: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of returning natural/historic functions to a former aquatic resource. Re-establishment results in rebuilding a former aquatic resource and results in a gain in aquatic resource area and functions.

<u>Rehabilitation</u>: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of repairing natural/historic functions to a degraded aquatic resource. Rehabilitation results in a gain in aquatic resource function, but does not result in a gain in aquatic resource area.

<u>Restoration</u>: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of returning natural/historic functions to a former or degraded aquatic resource. For the purpose of tracking net gains in aquatic resource area, restoration is divided into two categories: re-establishment and rehabilitation.

<u>Riffle and pool complex</u>: Riffle and pool complexes are special aquatic sites under the 404(b)(1) Guidelines. Riffle and pool complexes sometimes characterize steep gradient sections of streams. Such stream sections are recognizable by their hydraulic

characteristics. The rapid movement of water over a course substrate in riffles results in a rough flow, a turbulent surface, and high dissolved oxygen levels in the water. Pools are deeper areas associated with riffles. A slower stream velocity, a streaming flow, a smooth surface, and a finer substrate characterize pools.

<u>Riparian areas</u>: Riparian areas are lands next to streams, lakes, and estuarine-marine shorelines. Riparian areas are transitional between terrestrial and aquatic ecosystems, through which surface and subsurface hydrology connects riverine, lacustrine, estuarine, and marine waters with their adjacent wetlands, non-wetland waters, or uplands. Riparian areas provide a variety of ecological functions and services and help improve or maintain local water quality. (See general condition 23.)

Shellfish seeding: The placement of shellfish seed and/or suitable substrate to increase shellfish production. Shellfish seed consists of immature individual shellfish or individual shellfish attached to shells or shell fragments (i.e., spat on shell). Suitable substrate may consist of shellfish shells, shell fragments, or other appropriate materials placed into waters for shellfish habitat.

Single and complete linear project: A linear project is a project constructed for the purpose of getting people, goods, or services from a point of origin to a terminal point, which often involves multiple crossings of one or more waterbodies at separate and distant locations. The term "single and complete project" is defined as that portion of the total linear project proposed or accomplished by one owner/developer or partnership or other association of owners/developers that includes all crossings of a single water of the United States (i.e., a single waterbody) at a specific location. For linear projects crossing a single or multiple waterbodies several times at separate and distant locations, each crossing is considered a single and complete project for purposes of NWP authorization. However, individual channels in a braided stream or river, or individual arms of a large, irregularly shaped wetland or lake, etc., are not separate waterbodies, and crossings of such features cannot be considered separately.

Single and complete non-linear project: For non-linear projects, the term "single and complete project" is defined at 33 CFR 330.2(i) as the total project proposed or accomplished by one owner/developer or partnership or other association of owners/developers. A single and complete non-linear project must have independent utility (see definition of "independent utility"). Single and complete non-linear projects may not be "piecemealed" to avoid the limits in an NWP authorization.

<u>Stormwater management</u>: Stormwater management is the mechanism for controlling stormwater runoff for the purposes of reducing downstream erosion, water quality degradation, and flooding and mitigating the adverse effects of changes in land use on the aquatic environment.

<u>Stormwater management facilities</u>: Stormwater management facilities are those facilities, including but not limited to, stormwater retention and detention ponds and best management practices, which retain water for a period of time to control runoff and/or

improve the quality (i.e., by reducing the concentration of nutrients, sediments, hazardous substances and other pollutants) of stormwater runoff.

<u>Stream bed</u>: The substrate of the stream channel between the ordinary high water marks. The substrate may be bedrock or inorganic particles that range in size from clay to boulders. Wetlands contiguous to the stream bed, but outside of the ordinary high water marks, are not considered part of the stream bed.

<u>Stream channelization</u>: The manipulation of a stream's course, condition, capacity, or location that causes more than minimal interruption of normal stream processes. A channelized jurisdictional stream remains a water of the United States.

<u>Structure</u>: An object that is arranged in a definite pattern of organization. Examples of structures include, without limitation, any pier, boat dock, boat ramp, wharf, dolphin, weir, boom, breakwater, bulkhead, revetment, riprap, jetty, artificial island, artificial reef, permanent mooring structure, power transmission line, permanently moored floating vessel, piling, aid to navigation, or any other manmade obstacle or obstruction.

<u>**Tidal wetland:**</u> A tidal wetland is a jurisdictional wetland that is inundated by tidal waters. Tidal waters rise and fall in a predictable and measurable rhythm or cycle due to the gravitational pulls of the moon and sun. Tidal waters end where the rise and fall of the water surface can no longer be practically measured in a predictable rhythm due to masking by other waters, wind, or other effects. Tidal wetlands are located channelward of the high tide line.

<u>Tribal lands</u>: Any lands title to which is either: 1) held in trust by the United States for the benefit of any Indian tribe or individual; or 2) held by any Indian tribe or individual subject to restrictions by the United States against alienation.

<u>Tribal rights</u>: Those rights legally accruing to a tribe or tribes by virtue of inherent sovereign authority, unextinguished aboriginal title, treaty, statute, judicial decisions, executive order or agreement, and that give rise to legally enforceable remedies.

Vegetated shallows: Vegetated shallows are special aquatic sites under the 404(b)(1) Guidelines. They are areas that are permanently inundated and under normal circumstances have rooted aquatic vegetation, such as seagrasses in marine and estuarine systems and a variety of vascular rooted plants in freshwater systems.

<u>Waterbody</u>: For purposes of the NWPs, a waterbody is a "water of the United States." If a wetland is adjacent to a waterbody determined to be a water of the United States, that waterbody and any adjacent wetlands are considered together as a single aquatic unit (see 33 CFR 328.4(c)(2)).

ADDITIONAL INFORMATION

Information about the U.S. Army Corps of Engineers Regulatory Program, including nationwide permits, may also be accessed at

http://www.swt.usace.army.mil/Missions/Regulatory.aspx or http://www.usace.army.mil/Missions/CivilWorks/RegulatoryProgramandPermits.aspx

AGGREGATE SUBGRADE IMPROVEMENT (BDE)

Effective: April 1, 2012 Revised: April 1, 2022

Add the following Section to the Standard Specifications:

"SECTION 303. AGGREGATE SUBGRADE IMPROVEMENT

303.01 Description. This work shall consist of constructing an aggregate subgrade improvement (ASI).

303.02 Materials. Materials shall be according to the following.

Item	Article/Section
(a) Coarse Aggregate	
(b) Reclaimed Asphalt Pavement (RAP)	

303.03 Equipment. The vibratory roller shall be according to Article 1101.01, or as approved by the Engineer. Vibratory machines, such as tampers, shall be used in areas where rollers do not fit.

303.04 Soil Preparation. The minimum immediate bearing value (IBV) of the soil below the improved subgrade shall be according to the Department's "Subgrade Stability Manual" for the aggregate thickness specified.

303.05 Placing and Compacting. The maximum nominal lift thickness of aggregate gradations CA 2, CA 6, and CA 10 when compacted shall be 9 in. (225 mm). The maximum nominal lift thickness of aggregate gradations CS 1, CS 2, and RR 1 when compacted shall be 24 in. (600 mm).

The top surface of the aggregate subgrade improvement shall consist of a layer of capping aggregate gradations CA 6 or CA 10 that is 3 in. (75 mm) thick after compaction. Capping aggregate will not be required when aggregate subgrade improvement is used as a cubic yard pay item for undercut applications.

Each lift of aggregate shall be compacted to the satisfaction of the Engineer. If the moisture content of the material is such that compaction cannot be obtained, sufficient water shall be added so that satisfactory compaction can be obtained.

303.06 Finishing and Maintenance. The aggregate subgrade improvement shall be finished to the lines, grades, and cross sections shown on the plans, or as directed by the Engineer. The aggregate subgrade improvement shall be maintained in a smooth and compacted condition.

303.07 Method of Measurement. This work will be measured for payment according to Article 311.08.

303.08 Basis of Payment. This work will be paid for at the contract unit price per cubic yard (cubic meter) or ton (metric ton) for AGGREGATE SUBGRADE IMPROVEMENT or at the contract unit price per square yard (square meter) for AGGREGATE SUBGRADE IMPROVEMENT, of the thickness specified."

Add the following to Section 1004 of the Standard Specifications:

"**1004.07 Coarse Aggregate for Aggregate Subgrade Improvement (ASI).** The aggregate shall be according to Article 1004.01 and the following.

- (a) Description. The coarse aggregate shall be crushed gravel, crushed stone, or crushed concrete. In applications where greater than 24 in. (600 mm) of ASI material is required, gravel may be used below the top 12 in (300 mm) of ASI.
- (b) Quality. The coarse aggregate shall consist of sound durable particles reasonably free of deleterious materials.
- (c) Gradation.
 - (1) The coarse aggregate gradation for total ASI thickness less than or equal to 12 in. (300 mm) shall be CA 2, CA 6, CA 10, or CS 1.

The coarse aggregate gradation for total ASI thickness greater than 12 in. (300 mm) shall be CS 1 or CS 2 as shown below or RR 1 according to Article 1005.01(c).

	COARSE AGGREGATE SUBGRADE GRADATIONS				
Grad No.	Sieve Size and Percent Passing				
Glau NO.	8"	6"	4"	2"	#4
CS 1	100	97 ± 3	90 ± 10	45 ± 25	20 ± 20
CS 2		100	80 ± 10	25 ± 15	

	COARSE AGGREGATE SUBGRADE GRADATIONS (Metric)				
Sieve Size and Percent Passing					
Grad No.	200 mm	150 mm	100 mm	50 mm	4.75 mm
CS 1	100	97 ± 3	90 ± 10	45 ± 25	20 ± 20
CS 2		100	80 ± 10	25 ± 15	

(2) Capping aggregate shall be gradation CA 6 or CA 10."

Add the following to Article 1031.09 of the Standard Specifications:

"(b) RAP in Aggregate Subgrade Improvement (ASI). RAP in ASI shall be according to Articles 1031.01(a), 1031.02(a), 1031.06(a)(1), and 1031.06(a)(2), and the following.

- (1) The testing requirements of Article 1031.03 shall not apply.
- (2) Crushed RAP used for the lower lift may be mechanically blended with aggregate gradations CS 1, CS 2, and RR 1 but it shall be no greater than 40 percent of the total product volume. RAP agglomerations shall be no greater than 4 in. (100 mm).
- (3) For capping aggregate, well graded RAP having 100 percent passing the 1 1/2 in. (38 mm) sieve may be used when aggregate gradations CS 1, CS 2, CA 2, or RR 1 are used in the lower lift. FRAP will not be permitted as capping material.

Blending shall be through calibrated interlocked feeders or a calibrated blending plant such that the prescribed blending percentage is maintained throughout the blending process. The calibration shall have an accuracy of ± 2.0 percent of the actual quantity of material delivered."

80274

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)

Effective: November 2, 2006 Revised: August 1, 2017

Description. Bituminous material cost adjustments will be made to provide additional compensation to the Contractor, or credit to the Department, for fluctuations in the cost of bituminous materials when optioned by the Contractor. The bidder shall indicate with their bid whether or not this special provision will be part of the contract.

The adjustments shall apply to permanent and temporary hot-mix asphalt (HMA) mixtures, bituminous surface treatments (cover and seal coats), and preventative maintenance type surface treatments that are part of the original proposed construction, or added as extra work and paid for by agreed unit prices. The adjustments shall not apply to bituminous prime coats, tack coats, crack filling/sealing, joint filling/sealing, or extra work paid for at a lump sum price or by force account.

Method of Adjustment. Bituminous materials cost adjustments will be computed as follows.

 $CA = (BPI_P - BPI_L) \times (%AC_V / 100) \times Q$

Where: CA = Cost Adjustment, \$.

- BPI₽ = Bituminous Price Index, as published by the Department for the month the work is performed, \$/ton (\$/metric ton).
- BPI = Bituminous Price Index, as published by the Department for the month prior to the letting for work paid for at the contract price; or for the month the agreed unit price letter is submitted by the Contractor for extra work paid for by agreed unit price, \$/ton (\$/metric ton).
- %ACv = Percent of virgin Asphalt Cement in the Quantity being adjusted. For HMA mixtures, the % AC_{V} will be determined from the adjusted job mix formula. For bituminous materials applied, a performance graded or cutback asphalt will be considered to be 100% ACv and undiluted emulsified asphalt will be considered to be 65% AC_V.
- Q = Authorized construction Quantity, tons (metric tons) (see below).

For HMA mixtures measured in square yards: Q, tons = A x D x (G_{mb} x 46.8) / 2000. For HMA mixtures measured in square meters: Q, metric tons = A x D x (G_{mb} x 1) / 1000. When computing adjustments for full-depth HMA pavement, separate calculations will be made for the binder and surface courses to account for their different G_{mb} and % AC_{V.}

For bituminous materials measured in gallons:	Q, tons = V x 8.33 lb/gal x SG / 2000
For bituminous materials measured in liters:	Q, metric tons = $V \times 1.0 \text{ kg/L} \times \text{SG} / 1000$

Where: A

- = Area of the HMA mixture, sq yd (sq m). D
 - = Depth of the HMA mixture, in. (mm).
- = Average bulk specific gravity of the mixture, from the approved mix design. G_{mb}

- V = Volume of the bituminous material, gal (L).
- SG = Specific Gravity of bituminous material as shown on the bill of lading.

<u>Basis of Payment</u>. Bituminous materials cost adjustments may be positive or negative but will only be made when there is a difference between the BPI_L and BPI_P in excess of five percent, as calculated by:

Percent Difference = {(BPI_L - BPI_P) \div BPI_L} × 100

Bituminous materials cost adjustments will be calculated for each calendar month in which applicable bituminous material is placed; and will be paid or deducted when all other contract requirements for the work placed during the month are satisfied. The adjustments shall not apply during contract time subject to liquidated damages for completion of the entire contract.

80173

CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE)

Effective: January 1, 2025

Revise the first paragraph of Article 285.05 of the Standard Specifications to read:

"285.05 Fabric Formed Concrete Revetment Mat. The grout shall consist of a mixture of cement, fine aggregate, and water so proportioned and mixed as to provide a pumpable slurry. Fly ash or ground granulated blast furnace (GGBF) slag, and concrete admixtures may be used at the option of the Contractor. The grout shall have an air content of not less than 6.0 percent nor more than 9.0 percent of the volume of the grout. The mix shall obtain a compressive strength of 2500 psi (17,000 kPa) at 28 days according to Article 1020.09."

Revise Article 302.02 of the Standard Specifications to read:

"302.02 Materials. Materials shall be according to the following.

	Item	Article/Section
(a)	Cement	
(b)	Water	
(c)	Hydrated Lime	
(d)	By-Product, Hydrated Lime	
(e)	By-Product, Non-Hydrated Lime	
(f)	Lime Slurry	
(g)	Fly Ash	
(h)	Soil for Soil Modification (Note 1)	
(i)	Bituminous Materials (Note 2)	

Note 1. This soil requirement only applies when modifying with lime (slurry or dry).

Note 2. The bituminous materials used for curing shall be emulsified asphalt RS-2, CRS-2, HFE 90, or HFE 150; rapid curing liquid asphalt RC-70; or medium curing liquid asphalt MC-70 or MC-250."

Revise Article 312.07(c) of the Standard Specifications to read:

Add Article 312.07(i) of the Standard Specifications to read:

"(i) Ground Granulated Blast Furnace (GGBF) Slag1010"

Revise the first paragraph of Article 312.09 of the Standard Specifications to read:

***312.09** Proportioning and Mix Design. At least 60 days prior to start of placing CAM II, the Contractor shall submit samples of materials to be used in the work for proportioning and testing.

The mixture shall contain a minimum of 200 lb (120 kg) of cement per cubic yard (cubic meter). Cement may be replaced with fly ash or ground granulated blast furnace (GGBF) slag according to Article 1020.05(c)(1) or 1020.05(c)(2), respectively, however the minimum cement content in the mixture shall be 170 lbs/cu yd (101 kg/cu m). Blends of coarse and fine aggregates will be permitted, provided the volume of fine aggregate does not exceed the volume of coarse aggregate. The Engineer will determine the proportions of materials for the mixture according to the "Portland Cement Concrete Level III Technician Course" manual. However, the Contractor may substitute their own mix design. Article 1020.05(a) shall apply, and a Level III PCC Technician shall develop the mix design."

Revise Article 352.02 of the Standard Specifications to read:

"352.02 Materials. Materials shall be according to the following.

Item	Article/Section
(a) Cement (Note 1)	
(b) Soil for Soil-Cement Base Course	
(c) Water	
(d) Bituminous Materials (Note 2)	

Note 1. Bulk cement may be used for the traveling mixing plant method if the equipment for handling, weighing, and spreading the cement is approved by the Engineer.

Note 2. The bituminous materials used for curing shall be emulsified asphalt RS-2, CRS-2, HFE 90, or HFE 150; rapid curing liquid asphalt RC-70; or medium curing liquid asphalt MC-70 or MC-250."

Revise Article 404.02 of the Standard Specifications to read:

"404.02 Materials. Materials shall be according to the following.

Item	Article/Section
(a) Cement	
(b) Water	
(c) Fine Aggregate	
(d) Bituminous Material (Tack Coat)	
(e) Emulsified Asphalts (Note 1) (Note 2)	
(f) Fiber Modified Joint Sealer	
(a) Additives (Note 3)	

(g) Additives (Note 3)

Note 1. When used for slurry seal, the emulsified asphalt shall be CQS-1h according to Article 1032.06(b).

Note 2. When used for micro-surfacing, the emulsified asphalt shall be CQS-1hP according to Article 1032.06(e).

Note 3. Additives may be added to the emulsion mix or any of the component materials to provide the control of the quick-traffic properties. They shall be included as part of the mix design and be compatible with the other components of the mix.

Revise the last sentence of the fourth paragraph of Article 404.08 of the Standard Specifications to read:

"When approved by the Engineer, the sealant may be dusted with fine sand, cement, or mineral filler to prevent tracking."

Revise Note 2 of Article 516.02 of the Standard Specifications to read:

"Note 2. The sand-cement grout mix shall be according to Section 1020 and shall be a 1:1 blend of sand and cement comprised of a Type I, IL, or II cement at 185 lb/cu yd (110 kg/cu m). The maximum water cement ratio shall be sufficient to provide a flowable mixture with a typical slump of 10 in. (250 mm)."

Revise Note 2 of Article 543.02 of the Standard Specifications to read:

"Note 2. The grout mixture shall be 6.50 hundredweight/cu yd (385 kg/cu m) of cement plus fine aggregate and water. Fly ash or ground granulated blast furnace (GGBF) slag may replace a maximum of 5.25 hundredweight/cu yd (310 kg/cu m) of the cement. The water/cement ratio, according to Article 1020.06, shall not exceed 0.60. An air-entraining admixture shall be used to produce an air content, according to Article 1020.08, of not less than 6.0 percent nor more than 9.0 percent of the volume of the grout. The Contractor shall have the option to use a water-reducing or high range water-reducing admixture."

Revise Article 583.01 of the Standard Specifications to read:

***583.01 Description.** This work shall consist of placing cement mortar along precast, prestressed concrete bridge deck beams as required for fairing out any unevenness between adjacent deck beams prior to placing of waterproofing membrane and surfacing."

Revise Article 583.02(a) of the Standard Specifications to read:

Revise the first paragraph of Article 583.03 of the Standard Specifications to read:

"583.03 General. This work shall only be performed when the air temperature is 45 °F (7 °C) and rising. The mixture for cement mortar shall consist of three parts sand to one part cement by volume. The amount of water shall be no more than that necessary to produce a workable, plastic mortar."

Revise Note 2/ in Article 1003.01(b) of the Standard Specifications to read:

"2/ Applies only to sand. Sand exceeding the colorimetric test standard of 11 (Illinois Modified AASHTO T 21) will be checked for mortar making properties according to Illinois Modified ASTM C 87 and shall develop a compressive strength at the age of 14 days when using Type I, IL, or II cement of not less than 95 percent of the comparable standard.

Revise the second sentence of Article 1003.02(e)(1) of the Standard Specifications to read:

"The test will be performed with Type I, IL, or II portland cement having a total equivalent alkali content (Na₂O + $0.658K_2O$) of 0.90 percent or greater."

Revise the first sentence of the second paragraph of Article 1003.02(e)(3) of the Standard Specifications to read:

"The ASTM C 1293 test shall be performed with Type I, IL, or II portland cement having a total equivalent alkali content (Na₂O + 0.658K₂O) of 0.80 percent or greater."

Revise the second sentence of Article 1004.02(g)(1) of the Standard Specifications to read:

"The test will be performed with Type I, IL, or II portland cement having a total equivalent alkali content (Na₂O + 0.658K₂O) of 0.90 percent or greater."

Revise Article 1017.01 of the Standard Specifications to read:

"1017.01 Requirements. The mortar shall be high-strength according to ASTM C 387 and shall have a minimum 80.0 percent relative dynamic modulus of elasticity when tested by the Department according to Illinois Modified AASHTO T 161 or AASHTO T 161 when tested by an independent lab. The high-strength mortar shall have a water-soluble chloride ion content of less than 0.40 lb/cu yd (0.24 kg/cu m). The test shall be performed according to ASTM C 1218, and the high-strength mortar shall have an age of 28 to 42 days at the time of test. The ASTM C 1218 test shall be performed by an independent lab a minimum of once every five years, and the test results shall be provided to the Department. Mixing of the high-strength mortar shall be according to the manufacturer's specifications. The Department will maintain a qualified product list."

Revise the fourth sentence of Article 1018.01 of the Standard Specifications to read:

"The ASTM C 1218 test shall be performed by an independent lab a minimum of once every five years, and the test results shall be provided to the Department."

Revise Article 1019.02 of the Standard Specifications to read:

"1019.02 Materials. Materials shall be according to the following.

Item	Article/Section
(a) Cement	
(b) Water	

(c)	Fine Aggregate for Controlled Low-Strength Material (CLSM)	1003.06
(d)	Fly Ash	1010
(e)	Ground Granulated Blast Furnace (GGBF) Slag	1010
11	Administration (Note 1)	

(f) Admixtures (Note 1)

Note 1. The air-entraining admixture may be in powder or liquid form. Prior to approval, a CLSM air-entraining admixture will be evaluated by the Department. The admixture shall be able to meet the air content requirements of Mix 2. The Department will maintain a qualified product list."

Revise Article 1019.05 of the Standard Specifications to read:

"**1019.05 Department Mix Design.** The Department mix design shall be Mix 1, 2, or 3 and shall be proportioned to yield approximately one cubic yard (cubic meter).

Mix 1		
Cement	50 lb (30 kg)	
Fly Ash – Class C or F, and/or GGBF Slag	125 lb (74 kg)	
Fine Aggregate – Saturated Surface Dry	2900 lb (1720 kg)	
Water	50-65 gal (248-322 L)	
Air Content	No air is entrained	

Mix 2	
Cement	125 lb (74 kg)
Fine Aggregate – Saturated Surface Dry	2500 lb (1483 kg)
Water	35-50 gal (173-248 L)
Air Content	15-25 %

Mix 3	
Cement	40 lb (24 kg)
Fly Ash – Class C or F, and/or GGBF Slag	125 lb (74 kg)
Fine Aggregate – Saturated Surface Dry	2500 lb (1483 kg)
Water	35-50 gal (179-248 L)
Air Content	15-25 %"

Revise Article 1020.04, Table 1, Note (8) of the Standard Specifications to read:

"(8) In addition to the Type III portland cement, 100 lb/cu yd of ground granulated blast-furnace slag and 50 lb/cu yd of microsilica (silica fume) shall be used. For an air temperature greater than 85 °F, the Type III portland cement may be replaced with Type I, IL, or II portland cement."

Revise Article 1020.04, Table 1 (Metric), Note (8) of the Standard Specifications to read:

"(8) In addition to the Type III portland cement, 60 kg/cu m of ground granulated blastfurnace slag and 30 kg/cu m of microsilica (silica fume) shall be used. For an air temperature greater than 30 °C, the Type III portland cement may be replaced with Type I, IL, or II portland cement."

Revise the second paragraph of Article 1020.05(a) of the Standard Specifications to read:

"For a mix design using a portland-pozzolan cement, portland blast-furnace slag cement, portland-limestone cement, or replacing portland cement with finely divided minerals per Articles 1020.05(c) and 1020.05(d), the Contractor may submit a mix design with a minimum portland cement content less than 400 lbs/cu yd (237 kg/cu m), but not less than 375 lbs/cu yd (222 kg/cu m), if the mix design is shown to have a minimum relative dynamic modulus of elasticity of 80 percent determined according to AASHTO T 161. Testing shall be performed by an independent laboratory accredited by AASHTO re:source for Portland Cement Concrete."

Revise the first sentence of the first paragraph of Article 1020.05(b) of the Standard Specifications to read:

"Corrosion inhibitors and concrete admixtures shall be according to the qualified product lists."

Delete the fourth and fifth sentences of the second paragraph of Article 1020.05(b) of the Standard Specifications.

Revise the third sentence of the second paragraph of Article 1020.05(b)(5) of the Standard Specifications to read:

"The qualified product lists of concrete admixtures shall not apply."

Revise second paragraph of Article 1020.05(b)(10) of the Standard Specifications to read:

"When calcium nitrite is used, it shall be added at the rate of 4 gal/cu yd (20 L/cu m) and shall be added to the mix immediately after all compatible admixtures have been introduced to the batch. Other corrosion inhibitors shall be added per the manufacturer's specifications."

Delete the third paragraph of Article 1020.05(b)(10) of the Standard Specifications.

Revise Article 1020.15(b)(1)c. of the Standard Specifications to read:

"c. The minimum portland cement content in the mixture shall be 375 lbs/cu yd (222 kg/cu m). When the total of organic processing additions, inorganic processing additions, and limestone addition exceed 5.0 percent in the cement, the minimum portland cement content in the mixture shall be 400 lbs/cu yd (237 kg/cu m). For a drilled shaft, foundation, footing, or substructure, the

minimum portland cement may be reduced to as low as 330 lbs/cu yd (196 kg/cu m) if the concrete has adequate freeze/thaw durability. The Contractor shall provide freeze/thaw test results according to AASHTO T 161, and the relative dynamic modulus of elasticity of the mix design shall be a minimum of 80 percent. Testing shall be performed by an independent laboratory accredited by AASHTO re:source for Portland Cement Concrete. Freeze/thaw testing will not be required for concrete that will not be exposed to freezing and thawing conditions as determined by the Engineer."

Revise Article 1021.01 of the Standard Specifications to read:

"1021.01 General. Admixtures shall be furnished in liquid or powder form ready for use. The admixtures shall be delivered in the manufacturer's original containers, bulk tank trucks or such containers or tanks as are acceptable to the Engineer. Delivery shall be accompanied by a ticket which clearly identifies the manufacturer, the date of manufacture, and trade name of the material. Containers shall be readily identifiable as to manufacturer, the date of manufacture, and trade name of the material they contain.

Concrete admixtures shall be on one of the Department's qualified product lists. Unless otherwise noted, admixtures shall have successfully completed and remain current with the AASHTO Product Eval and Audit Concrete Admixture (CADD) testing program. For admixture submittals to the Department; the product brand name, manufacturer name, admixture type or types, an electronic link to the product's technical data sheet, and the NTPEP testing number which contains an electronic link to all test data shall be provided. In addition, a letter shall be submitted certifying that no changes have been made in the formulation of the material since the most current round of tests conducted by AASHTO Product Eval and Audit. After 28 days of testing by AASHTO Product Eval and Audit, air-entraining admixtures may be provisionally approved and used on Departmental projects. For all other admixtures, unless otherwise noted, the time period after which provisionally approved status may be earned is 6 months.

The manufacturer shall include the following in the submittal to the AASHTO Product Eval and Audit CADD testing program: the manufacturing range for specific gravity, the midpoint and manufacturing range for residue by oven drying, and manufacturing range of pH. The submittal shall also include an infrared spectrophotometer trace no more than five years old.

For air-entraining admixtures according to Article 1021.02, the specific gravity allowable manufacturing range established by the manufacturer shall be according to AASHTO M 194. For residue by oven drying and pH, the allowable manufacturing range and test methods shall be according to AASHTO M 194.

For admixtures according to Articles 1021.03, 1021.04, 1021.05, 1021.06, 1021.07, and 1021.08, the pH allowable manufacturing range established by the manufacturer shall be according to ASTM E 70. For specific gravity and residue by oven drying, the allowable manufacturing range and test methods shall be according to ASHTO M 194.

All admixtures, except chloride-based accelerators, shall contain a maximum of 0.3 percent chloride by weight (mass) as determined by an appropriate test method. To verify the test result, the Department will use Illinois Modified AASHTO T 260, Procedure A, Method 1.

Prior to final approval of an admixture, the Engineer reserves the right to request a sample for testing. The test and reference concrete mixtures tested by the Engineer will contain a cement content of 5.65 cwt/cu yd (335 kg/cu m). For freeze-thaw testing, the Department will perform the test according to Illinois Modified AASHTO T 161. The flexural strength test will be performed according to AASHTO T 177. If the Engineer decides to test the admixture, the manufacturer shall submit AASHTO T 197 water content and set time test results on the standard cement used by the Department. The manufacturer may select their lab or an independent lab to perform this testing. The laboratory is not required to be accredited by AASHTO.

Random field samples may be taken by the Department to verify an admixture meets specification. A split sample will be provided to the manufacturer if requested. Admixtures that do not meet specification requirements or an allowable manufacturing range established by the manufacturer shall be replaced with new material."

Revise Article 1021.03 of the Standard Specifications to read:

"**1021.03 Retarding and Water-Reducing Admixtures.** The admixture shall be according to the following.

- (a) Retarding admixtures shall be according to AASHTO M 194, Type B (retarding) or Type D (water-reducing and retarding).
- (b) Water-reducing admixtures shall be according to AASHTO M 194, Type A.
- (c) High range water-reducing admixtures shall be according to AASHTO M 194, Type F (high range water-reducing) or Type G (high range water-reducing and retarding)."

Revise Article 1021.05 of the Standard Specifications to read:

"1021.05 Self-Consolidating Admixtures. Self-consolidating admixture systems shall consist of either a high range water-reducing admixture only or a high range water-reducing admixture combined with a separate viscosity modifying admixture. The one or two component admixture system shall be capable of producing a concrete that can flow around reinforcement and consolidate under its own weight without additional effort and without segregation.

High range water-reducing admixtures shall be according to AASHTO M 194, Type F.

Viscosity modifying admixtures shall be according to AASHTO M 194, Type S (specific performance)."

Revise Article 1021.06 of the Standard Specifications to read:

"**1021.06 Rheology-Controlling Admixture.** Rheology-controlling admixtures shall be capable of producing a concrete mixture with a lower yield stress that will consolidate easier for slipform applications used by the Contractor. Rheology-controlling admixtures shall be according to AASHTO M 194, Type S (specific performance)."

Revise Article 1021.07 of the Standard Specifications to read:

"1021.07 Corrosion Inhibitor. The corrosion inhibitor shall be according to one of the following.

- (a) Calcium Nitrite. Corrosion inhibitors shall contain a minimum 30 percent calcium nitrite by weight (mass) of solution and shall comply with either the requirements of AASHTO M 194, Type C (accelerating) or the requirements of ASTM C 1582. The corrosion inhibiting performance requirements of ASTM C 1582 shall not apply.
- (b) Other Materials. The corrosion inhibitor shall be according to ASTM C 1582.

For submittals requiring testing according to ASTM M 194, Type C (accelerating), the admixture shall meet the requirements of the AASHTO Product Eval and Audit CADD testing program according to Article 1021.01.

For submittals requiring testing according to ASTM C 1582, a report prepared by an independent laboratory accredited by AASHTO re:source for portland cement concrete shall be provided. The report shall show the results of physical tests conducted no more than five years prior to the time of submittal, according to applicable specifications. However, ASTM G 109 test information specified in ASTM C 1582 is not required to be from an independent accredited lab. All other information in ASTM C 1582 shall be from an independent accredited lab. Test data and other information required to be submitted to AASHTO Product Eval and Audit according to Article 1021.01, shall instead be submitted directly to the Department."

Add Article 1021.08 of the Standard Specifications as follows:

"**1021.08 Other Specific Performance Admixtures.** Other specific performance admixtures shall, at a minimum, be according to AASHTO M 194, Type S (specific performance). The Department also reserves the right to require other testing, as determined by the Engineer, to show evidence of specific performance characteristics.

Initial testing according to AASHTO M 194 may be conducted under the AASHTO Product Eval and Audit CADD testing program according to Article 1021.01, or by an independent laboratory accredited by AASHTO re:source for Portland Cement Concrete. In either case, test data and other information required to be submitted to AASHTO Product Eval and Audit according to Article 1021.01, shall also be submitted directly to the Department. The independent accredited lab report shall show the results of physical tests conducted no more than five years prior to the time of submittal, according to applicable specifications."

Revise Article 1024.01 of the Standard Specifications to read:

"1024.01 Requirements for Grout. The grout shall be proportioned by dry volume, thoroughly mixed, and shall have a minimum temperature of 50 °F (10 °C). Water shall not exceed the minimum needed for placement and finishing.

Materials for the grout shall be according to the following.

Item (a) Cement	Article/Section
(b) Water	
c) Fine Aggregate	
(d) Fly Ash	
(e) Ground Granulated Blast Furnace (GGBF) Slag	
(f) Concrete Admixtures	

Revise Note 1 of Article 1024.02 of the Standard Specifications to read:

"Note 1. Nonshrink grout shall be according to Illinois Modified ASTM C 1107.

The nonshrink grout shall have a water-soluble chloride ion content of less than 0.40 lb/cu yd (0.24 kg/cu m). The test shall be performed according to ASTM C 1218, and the grout shall have an age of 28 to 42 days at the time of test. The ASTM C 1218 test shall be performed by an independent lab a minimum of once every five years, and the test results shall be provided to the Department. Mixing of the nonshrink grout shall be according to the manufacturer's specifications. The Department will maintain a qualified product list."

Revise Article 1029.02 of the Standard Specifications to read:

"1029.02 Materials. Materials shall be according to the following.

Item	Article/Section
(a) Cement	
(b) Fly Ash	
(c) Ground Granulated Blast Furnace (GGBF) Slag	
(d) Water	
(e) Fine Aggregate	
(f) Concrete Admixtures	
(a) Enaming Agent (Note 1)	

(g) Foaming Agent (Note 1)

Note 1. The manufacturer shall submit infrared spectrophotometer trace and test results indicating the foaming agent meets the requirements of ASTM C 869 in order to be on the Department's qualified product list. Submitted data/results shall not be more than five years old."

Revise the second paragraph of Article 1103.03(a)(4) the Standard Specifications to read:

"The dispenser system shall provide a visual indication that the liquid admixture is actually entering the batch, such as via a transparent or translucent section of tubing or by independent check with an integrated secondary metering device. If approved by the Engineer, an alternate indicator may be used for admixtures dosed at rates of 25 oz/cwt (1630 mL/100 kg) or greater, such as accelerating admixtures, corrosion inhibitors, and viscosity modifying admixtures."

Revise the first two sections of Check Sheet #11 of the Supplemental Specifications and Recurring Special Provisions to read:

"<u>Description</u>. This work shall consist of filling voids beneath rigid and composite pavements with cement grout.

<u>Materials</u>. Materials shall be according to the following Articles of Division 1000 - Materials of the Standard Specifications:

Item	Article/Section
(a) Cement	
(b) Water	
(c) Fly Ash	
(d) Ground Granulated Blast Furnace (GGBF) Slag	
(e) Admixtures	
(f) Packaged Rapid Hardening Mortar or Concrete	

Revise the third paragraph of Materials Note 2 of Check Sheet #28 of the Supplemental Specifications and Recurring Special Provisions to read:

"The Department will maintain a qualified product list of synthetic fibers, which will include the minimum required dosage rate. For the minimum required fiber dosage rate based on the Illinois Modified ASTM C 1609 test, a report prepared by an independent laboratory accredited by AASHTO re:source for Portland Cement Concrete shall be provided. The report shall show results of tests conducted no more than five years prior to the time of submittal."

COMPENSABLE DELAY COSTS (BDE)

Effective: June 2, 2017 Revised: April 1, 2019

Revise Article 107.40(b) of the Standard Specifications to read:

- "(b) Compensation. Compensation will not be allowed for delays, inconveniences, or damages sustained by the Contractor from conflicts with facilities not meeting the above definition; or if a conflict with a utility in an unanticipated location does not cause a shutdown of the work or a documentable reduction in the rate of progress exceeding the limits set herein. The provisions of Article 104.03 notwithstanding, compensation for delays caused by a utility in an unanticipated location will be paid according to the provisions of this Article governing minor and major delays or reduced rate of production which are defined as follows.
 - (1) Minor Delay. A minor delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two hours, but not to exceed two weeks.
 - (2) Major Delay. A major delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two weeks.
 - (3) Reduced Rate of Production Delay. A reduced rate of production delay occurs when the rate of production on the work in conflict with the utility in an unanticipated location decreases by more than 25 percent and lasts longer than seven calendar days."

Revise Article 107.40(c) of the Standard Specifications to read:

- "(c) Payment. Payment for Minor, Major, and Reduced Rate of Production Delays will be made as follows.
 - (1) Minor Delay. Labor idled which cannot be used on other work will be paid for according to Article 109.04(b)(1) and (2) for the time between start of the delay and the minimum remaining hours in the work shift required by the prevailing practice in the area.

Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4).

(2) Major Delay. Labor will be the same as for a minor delay.

Equipment will be the same as for a minor delay, except Contractor-owned equipment will be limited to two weeks plus the cost of move-out to either the

Contractor's yard or another job and the cost to re-mobilize, whichever is less. Rental equipment may be paid for longer than two weeks provided the Contractor presents adequate support to the Department (including lease agreement) to show retaining equipment on the job is the most economical course to follow and in the public interest.

(3) Reduced Rate of Production Delay. The Contractor will be compensated for the reduced productivity for labor and equipment time in excess of the 25 percent threshold for that portion of the delay in excess of seven calendar days. Determination of compensation will be in accordance with Article 104.02, except labor and material additives will not be permitted.

Payment for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be determined according to Article 109.13."

Revise Article 108.04(b) of the Standard Specifications to read:

- "(b) No working day will be charged under the following conditions.
 - (1) When adverse weather prevents work on the controlling item.
 - (2) When job conditions due to recent weather prevent work on the controlling item.
 - (3) When conduct or lack of conduct by the Department or its consultants, representatives, officers, agents, or employees; delay by the Department in making the site available; or delay in furnishing any items required to be furnished to the Contractor by the Department prevents work on the controlling item.
 - (4) When delays caused by utility or railroad adjustments prevent work on the controlling item.
 - (5) When strikes, lock-outs, extraordinary delays in transportation, or inability to procure critical materials prevent work on the controlling item, as long as these delays are not due to any fault of the Contractor.
 - (6) When any condition over which the Contractor has no control prevents work on the controlling item."

Revise Article 109.09(f) of the Standard Specifications to read:

"(f) Basis of Payment. After resolution of a claim in favor of the Contractor, any adjustment in time required for the work will be made according to Section 108. Any adjustment in the costs to be paid will be made for direct labor, direct materials, direct equipment, direct jobsite overhead, direct offsite overhead, and other direct costs allowed by the resolution. Adjustments in costs will not be made for interest charges, loss of anticipated profit, undocumented loss of efficiency, home office overhead and unabsorbed overhead other than as allowed by Article 109.13, lost opportunity, preparation of claim expenses and other consequential indirect costs regardless of method of calculation.

The above Basis of Payment is an essential element of the contract and the claim cost recovery of the Contractor shall be so limited."

Add the following to Section 109 of the Standard Specifications.

"**109.13 Payment for Contract Delay.** Compensation for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be allowed when such costs result from a delay meeting the criteria in the following table.

Contract Type	Cause of Delay	Length of Delay
Working Days	Article 108.04(b)(3) or Article 108.04(b)(4)	No working days have been charged for two consecutive weeks.
Completion Date	Article 108.08(b)(1) or Article 108.08(b)(7)	The Contractor has been granted a minimum two week extension of contract time, according to Article 108.08.

Payment for each of the various costs will be according to the following.

- (a) Escalated Material and/or Labor Costs. When the delay causes work, which would have otherwise been completed, to be done after material and/or labor costs have increased, such increases will be paid. Payment for escalated material costs will be limited to the increased costs substantiated by documentation furnished by the Contractor. Payment for escalated labor costs will be limited to those items in Article 109.04(b)(1) and (2), except the 35 percent and 10 percent additives will not be permitted.
- (b) Extended Project Overhead. For the duration of the delay, payment for extended project overhead will be paid as follows.
 - (1) Direct Jobsite and Offsite Overhead. Payment for documented direct jobsite overhead and documented direct offsite overhead, including onsite supervisory and administrative personnel, will be allowed according to the following table.

Original Contract Amount	Supervisory and Administrative Personnel
Up to \$5,000,000	One Project Superintendent
Over \$ 5,000,000 - up to \$25,000,000	One Project Manager, One Project Superintendent or Engineer, and One Clerk
Over \$25,000,000 - up to \$50,000,000	One Project Manager, One Project Superintendent, One Engineer, and

	One Clerk
Over \$50,000,000	One Project Manager, Two Project Superintendents,
Over \$30,000,000	One Engineer, and One Clerk

- (2) Home Office and Unabsorbed Overhead. Payment for home office and unabsorbed overhead will be calculated as 8 percent of the total delay cost.
- (c) Extended Traffic Control. Traffic control required for an extended period of time due to the delay will be paid for according to Article 109.04.

When an extended traffic control adjustment is paid under this provision, an adjusted unit price as provided for in Article 701.20(a) for increase or decrease in the value of work by more than ten percent will not be paid.

Upon payment for a contract delay under this provision, the Contractor shall assign subrogation rights to the Department for the Department's efforts of recovery from any other party for monies paid by the Department as a result of any claim under this provision. The Contractor shall fully cooperate with the Department in its efforts to recover from another party any money paid to the Contractor for delay damages under this provision."

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)

Effective: June 1, 2010 Revised: January 1, 2025

The reduction of emissions of particulate matter (PM) for off-road equipment shall be accomplished by installing retrofit emission control devices. The term "equipment" refers to diesel fuel powered devices rated at 50 hp and above, to be used on the jobsite in excess of seven calendar days over the course of the construction period on the jobsite (including rental equipment).

Contractor and subcontractor diesel powered off-road equipment assigned to the contract shall be retrofitted according to the table below.

Horsepower Range	Model Year and Older
50-99	2003
100-299	2002
300-599	2000
600-749	2001
750 and up	2005

The retrofit emission control devices shall achieve a minimum PM emission reduction of 50 percent and shall be:

 a) Included on the U.S. Environmental Protection Agency (USEPA) Verified Retrofit Technology List (<u>https://www.epa.gov/verified-diesel-tech/verified-technologies-list-cleandiesel</u>),
 or verified by the California Air Bessuress Board (CAPB)

or verified by the California Air Resources Board (CARB) (<u>http://www.arb.ca.gov/diesel/verdev/vt/cvt.htm</u>); or

b) Retrofitted with a non-verified diesel retrofit emission control device if verified retrofit emission control devices are not available for equipment proposed to be used on the project, and if the Contractor has obtained a performance certification from the retrofit device manufacturer that the emission control device provides a minimum PM emission reduction of 50 percent.

Note: Large cranes (Crawler mounted cranes) which are responsible for critical lift operations are exempt from installing retrofit emission control devices if such devices adversely affect equipment operation.

Diesel powered off-road equipment with engine ratings of 50 hp and above, which are unable to be retrofitted with verified emission control devices or if performance certifications are not available which will achieve a minimum 50 percent PM reduction, may be granted a waiver by the Department if documentation is provided showing good faith efforts were made by the Contractor to retrofit the equipment.

Construction shall not proceed until the Contractor submits a certified list of the diesel powered off-road equipment that will be used, and as necessary, retrofitted with emission control devices. The list(s) shall include (1) the equipment number, type, make, Contractor/rental company name; and (2) the emission control devices make, model, USEPA or CARB verification number, or performance certification from the retrofit device manufacturer. Equipment reported as fitted with emissions control devices shall be made available to the Engineer for visual inspection of the device installation, prior to being used on the jobsite.

The Contractor shall submit an updated list of retrofitted off-road construction equipment as retrofitted equipment changes or comes on to the jobsite. The addition or deletion of any diesel powered equipment shall be included on the updated list.

If any diesel powered off-road equipment is found to be in non-compliance with any portion of this special provision, the Engineer will issue the Contractor a diesel retrofit deficiency deduction.

Any costs associated with retrofitting any diesel powered off-road equipment with emission control devices shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed. The Contractor's compliance with this notice and any associated regulations shall not be grounds for a claim.

Diesel Retrofit Deficiency Deduction

When the Engineer determines that a diesel retrofit deficiency exists, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency continues to exist. The calendar day(s) will begin when the time period for correction is exceeded and end with the Engineer's written acceptance of the correction. The daily monetary deduction will be \$1,000.00 for each deficiency identified.

The deficiency will be based on lack of diesel retrofit emissions control.

If a Contractor accumulates three diesel retrofit deficiency deductions for the same piece of equipment in a contract period, the Contractor will be shutdown until the deficiency is corrected. Such a shutdown will not be grounds for any extension of the contract time, waiver of penalties, or be grounds for any claim.

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)

Effective: September 1, 2000 Revised: January 2, 2025

- 1. <u>OVERVIEW AND GENERAL OBLIGATION</u>. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR Part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified in accordance with the requirements of 49 CFR Part 26 and listed in the Illinois Unified Certification Program (IL UCP) DBE Directory. Award of the contract is conditioned on meeting the requirements of 49 CFR Part 26, and failure by the Contractor to carry out the requirements of Part 26 is a material breach of the contract and may result in the termination of the contract or such other remedies as the Department deems appropriate.
- <u>CONTRACTOR ASSURANCE</u>. All assurances set forth in FHWA 1273 are hereby incorporated by reference and will be physically attached to the final contract and all subcontracts.
- 3. <u>CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR</u>. The Department has determined the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies and that, in the absence of unlawful discrimination and in an arena of fair and open competition, DBE companies can be expected to perform <u>13</u>% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will only award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work in accordance with the requirements of 49 CFR 26.53 and SBE Memorandum No. 24-02.
- 4. <u>IDENTIFICATION OF CERTIFIED DBE</u>. Information about certified DBE Contractors can be found in the Illinois UCP Directory. Bidders can obtain additional information and assistance with identifying DBE-certified companies at the Department's website or by contacting the Department's Bureau of Small Business Enterprises at (217) 785-4611.
- 5. <u>BIDDING PROCEDURES</u>. Compliance with this Special Provision and SBE Policy Memorandum 24-02 is a material bidding requirement. The following shall be included with the bid.
 - (a) DBE Utilization Plan (form SBE 2026) documenting enough DBE participation has been obtained to meet the goal, or a good faith effort has been made to meet the goal even though the efforts did not succeed in obtaining enough DBE participation to meet the goal.

(b) Applicable DBE Participation Statement (form SBE 2023, 2024, and/or 2025) for each DBE firm the bidder has committed to perform the work to achieve the contract goal.

The required forms and documentation shall be submitted as a single .pdf file using the "Integrated Contractor Exchange (iCX)" application within the Department's "EBids System".

The Department will not accept a bid if it does not meet the bidding procedures set forth herein and the bid will be declared non-responsive. A bidder declared non-responsive for failure to meet the bidding procedures will not give rise to an administrative reconsideration. In the event the bid is declared non-responsive, the Department may elect to cause the forfeiture of the penal sum of the bidder's proposal guaranty and may deny authorization to bid the project if re-advertised for bids.

6. <u>UTILZATION PLAN EVALUATION</u>. The contract will not be awarded until the Utilization Plan is approved. All information submitted by the bidder must be complete, accurate, and adequately document the bidder has committed to DBE participation sufficient to meet the goal, or that the bidder has made good faith efforts to do so, in the event the bidder cannot meet the goal, in order for the Department to commit to the performance of the contract by the bidder.

The Utilization Plan will be approved by the Department if the Utilization Plan documents sufficient commercially useful DBE work to meet the contract goal or the Department determines, based upon the documentation submitted, that the bidder has made a good faith effort to meet the contract goal pursuant to 49 CFR Part 26, Appendix A and the requirements of SBE 2026.

If the Department determines that a good faith effort has not been made, the Department will notify the responsible company official designated in the Utilization Plan of that determination in accordance with SBE Policy Memorandum 24-02.

- 7. <u>CALCULATING DBE PARTICIPATION</u>. The Utilization Plan values represent work the bidder commits to have performed by the specified DBEs and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE firms. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR Part 26.55(c) on questions of commercially useful functions as it affects the work. Specific guidelines for counting goal credit are provided in 49 CFR Part 26.55. In evaluating Utilization Plans for award the Department will count goal credit as set forth in Part 26 and in accordance with SBE Policy Memorandum 24-02.
- 8. <u>CONTRACT COMPLIANCE</u>. The Contractor must utilize the specific DBEs listed to perform the work and supply the materials for which each DBE is listed in the Contractor's approved Utilization Plan, unless the Contractor obtains the Department's written consent to

terminate the DBE or any portion of its work. The DBE Utilization Plan approved by SBE is a condition-of-award, and any deviation to that Utilization Plan, the work set forth therein to be performed by DBE firms, or the DBE firms specified to perform that work, must be approved, in writing, by the Department in accordance with federal regulatory requirements. Deviation from the DBE Utilization Plan condition-of-award without such written approval is a violation of the contract and may result in termination of the contract or such other remedy the Department deems appropriate. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan.

- (a) NOTICE OF DBE PERFORMANCE. The Contractor shall provide the Engineer with at least three days advance notice of when all DBE firms are expected to perform the work committed under the Contractor's Utilization Plan.
- (b) SUBCONTRACT. If awarded the contract, the Contractor is required to enter into written subcontracts with all DBE firms indicated in the approved Utilization Plan and must provide copies of fully executed DBE subcontracts to the Department upon request. Subcontractors shall ensure that all lower tier subcontracts or agreements with DBEs to supply labor or materials be performed in accordance with this Special Provision.
- (c) PAYMENT TO DBE FIRMS. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goal has been paid to the DBE. The Contractor shall document and report all payments for work performed by DBE certified firms in accordance with Article 109.11 of the Standard Specifications. All records of payment for work performed by DBE certified firms shall be made available to the Department upon request.
- (d) FINAL PAYMENT. After the performance of the final item of work or trucking, or delivery of material by a DBE and final payment to the DBE by the Contractor, but not later than 30 calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Agreement (form SBE 2115) to the Engineer. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Utilization Plan and after good faith efforts are reviewed, the Department may deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages.
- (g) ENFORCEMENT. The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.

PAVEMENT MARKING INSPECTION (BDE)

Effective: April 1, 2025

Revise the second sentence of the first paragraph of Article 780.13 of the Standard Specifications to read:

"In addition, thermoplastic, preformed plastic, epoxy, preformed thermoplastic, polyurea, and modified urethane pavement markings will be inspected following a winter performance period that extends from November 15 to April 1 of the next year."

PERFORMANCE GRADED ASPHALT BINDER (BDE)

Effective: January 1, 2023

Revise Article 1032.05 of the Standard Specifications to read:

"1032.05 Performance Graded Asphalt Binder. These materials will be accepted according to the Bureau of Materials Policy Memorandum, "Performance Graded Asphalt Binder Qualification Procedure." The Department will maintain a qualified producer list. These materials shall be free from water and shall not foam when heated to any temperature below the actual flash point. Air blown asphalt, recycle engine oil bottoms (ReOB), and polyphosphoric acid (PPA) modification shall not be used.

When requested, producers shall provide the Engineer with viscosity/temperature relationships for the performance graded asphalt binders delivered and incorporated in the work.

(a) Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans and the following.

Test	Parameter
Small Strain Parameter (AASHTO PP 113) BBR, ΔTc, 40 hrs PAV (40 hrs continuous or 2 PAV at 20 hrs)	-5 °C min.

(b) Modified Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans.

Asphalt binder modification shall be performed at the source, as defined in the Bureau of Materials Policy Memorandum, "Performance Graded Asphalt Binder Qualification Procedure."

Modified asphalt binder shall be safe to handle at asphalt binder production and storage temperatures or HMA construction temperatures. Safety Data Sheets (SDS) shall be provided for all asphalt modifiers.

(1) Polymer Modification (SB/SBS or SBR). Elastomers shall be added to the base asphalt binder to achieve the specified performance grade and shall be either a styrene-butadiene diblock, triblock copolymer without oil extension, or a styrenebutadiene rubber. The polymer modified asphalt binder shall be smooth, homogeneous, and be according to the requirements shown in Table 1 or 2 for the grade shown on the plans.

Table 1 - Requirements for Styrene-Butadiene Copolymer (SB/SBS) Modified Asphalt Binders			
Test	Asphalt Grade SB/SBS PG 64-28 SB/SBS PG 70-22	Asphalt Grade SB/SBS PG 64-34 SB/SBS PG 70-28 SB/SBS PG 76-22 SB/SBS PG 76-28	
Separation of Polymer ITP, "Separation of Polymer from Asphalt Binder" Difference in °F (°C) of the softening point between top and bottom portions	4 (2) max.	4 (2) max.	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	60 min.	70 min.	

Table 2 - Requirements for Styrene-Butadiene Rubber (SBR) Modified Asphalt Binders			
Test	Asphalt Grade SBR PG 64-28 SBR PG 70-22	Asphalt Grade SB/SBS PG 64-34 SB/SBS PG 70-28 SBR PG 76-22 SBR PG 76-28	
Separation of Polymer ITP, "Separation of Polymer from Asphalt Binder" Difference in °F (°C) of the softening point between top and bottom portions	4 (2) max.	4 (2) max.	
Toughness ASTM D 5801, 77 °F (25 °C), 20 in./min. (500 mm/min.), inlbs (N-m)	110 (12.5) min.	110 (12.5) min.	
Tenacity ASTM D 5801, 77 °F (25 °C), 20 in./min. (500 mm/min.), inlbs (N-m)	75 (8.5) min.	75 (8.5) min.	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	40 min.	50 min.	

(2) Ground Tire Rubber (GTR) Modification. GTR modification is the addition of recycled ground tire rubber to liquid asphalt binder to achieve the specified performance grade. GTR shall be produced from processing automobile and/or truck tires by the ambient

grinding method or micronizing through a cryogenic process. GTR shall not exceed 1/16 in. (2 mm) in any dimension and shall not contain free metal particles, moisture that would cause foaming of the asphalt, or other foreign materials. A mineral powder (such as talc) meeting the requirements of AASHTO M 17 may be added, up to a maximum of four percent by weight of GTR to reduce sticking and caking of the GTR particles. When tested in accordance with Illinois Modified AASHTO T 27 "Standard Method of Test for Sieve Analysis of Fine and Coarse Aggregates" or AASHTO PP 74 "Standard Practice for Determination of Size and Shape of Glass Beads Used in Traffic Markings by Means of Computerized Optical Method", a 50 g sample of the GTR shall conform to the following gradation requirements.

Sieve Size	Percent Passing	
No. 16 (1.18 mm)	100	
No. 30 (600 μm)	95 ± 5	
No. 50 (300 μm)	> 20	

GTR modified asphalt binder shall be tested for rotational viscosity according to AASHTO T 316 using spindle S27. GTR modified asphalt binder shall be tested for original dynamic shear and RTFO dynamic shear according to AASHTO T 315 using a gap of 2 mm.

The GTR modified asphalt binder shall meet the requirements of Table 3.

Table 3 - Requirements for Ground Tire Rubber (GTR) Modified Asphalt Binders			
Test	Asphalt Grade GTR PG 64-28 GTR PG 70-22	Asphalt Grade GTR PG 76-22 GTR PG 76-28 GTR PG 70-28	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	60 min.	70 min.	

(3) Softener Modification (SM). Softener modification is the addition of organic compounds, such as engineered flux, bio-oil blends, modified vegetable oils, glycol amines, and fatty acid derivatives, to the base asphalt binder to achieve the specified performance grade. Softeners shall be dissolved, dispersed, or reacted in the asphalt binder to enhance its performance and shall remain compatible with the asphalt binder with no separation. Softeners shall not be added to modified PG asphalt binder as defined in Articles 1032.05(b)(1) or 1032.05(b)(2).

An Attenuated Total Reflectance-Fourier Transform Infrared spectrum (ATR-FTIR) shall be collected for both the softening compound as well as the softener modified

asphalt binder at the dose intended for qualification. The ATR-FTIR spectra shall be collected on unaged softener modified binder, 20-hour Pressurized Aging Vessel (PAV) aged softener modified binder, and 40-hour PAV aged softener modified binder. The ATR-FTIR shall be collected in accordance with Illinois Test Procedure 601. The electronic files spectral files (in one of the following extensions or equivalent: *.SPA, *.SPG, *.IRD, *.IFG, *.CSV, *.SP, *.IRS, *.GAML, *.[0-9], *.IGM, *.ABS, *.DRT, *.SBM, *.RAS) shall be submitted to the Central Bureau of Materials.

Softener modified asphalt binders shall meet the requirements in Table 4.

Table 4 - Requirements for Softener Modified Asphalt Binders		
	Asphalt Grade	
	SM PG 46-28 SM PG 46-34	
Test	SM PG 52-28 SM PG 52-34	
	SM PG 58-22 SM PG 58-28	
	SM PG 64-22	
Small Strain Parameter (AASHTO PP 113)		
BBR, ΔTc, 40 hrs PAV (40 hrs	-5°C min.	
continuous or 2 PAV at 20 hrs)		
Large Strain Parameter (Illinois Modified		
AASHTO T 391) DSR/LAS Fatigue	> EA 0/	
Property, Δ G [*] peak τ, 40 hrs PAV	≥ 54 %	
(40 hrs continuous or 2 PAV at 20 hrs)		

The following grades may be specified as tack coats.

Asphalt Grade	Use
PG 58-22, PG 58-28, PG 64-22	Tack Coat"

Revise Article 1031.06(c)(1) and 1031.06(c)(2) of the Standard Specifications to read:

"(1) RAP/RAS. When RAP is used alone or RAP is used in conjunction with RAS, the percentage of virgin ABR shall not exceed the amounts listed in the following table.

HM	HMA Mixtures - RAP/RAS Maximum ABR % ^{1/2/}				
NdesignBinderSurfacePolymer Modified Binder or Surface 3/					
30	30	30	10		
50	25	15	10		
70	15	10	10		
90	10	10	10		

1/ For Low ESAL HMA shoulder and stabilized subbase, the RAP/RAS ABR shall not exceed 50 percent of the mixture.

- 2/ When RAP/RAS ABR exceeds 20 percent, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ The maximum ABR percentages for ground tire rubber (GTR) modified mixes shall be equivalent to the percentages specified for SBS/SBR polymer modified mixes.
- (2) FRAP/RAS. When FRAP is used alone or FRAP is used in conjunction with RAS, the percentage of virgin asphalt binder replacement shall not exceed the amounts listed in the following table.

HMA Mixtures - FRAP/RAS Maximum ABR % ^{1/2/}			
Ndesign	Binder	Polymer Modified Binder or Surface ^{3/}	
30	55	45	15
50	45	40	15
70	45	35	15
90	45	35	15
SMA			25
IL-4.75			35

- 1/ For Low ESAL HMA shoulder and stabilized subbase, the FRAP/RAS ABR shall not exceed 50 percent of the mixture.
- 2/ When FRAP/RAS ABR exceeds 20 percent for all mixes, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ The maximum ABR percentages for GTR modified mixes shall be equivalent to the percentages specified for SBS/SBR polymer modified mixes."

Add the following to the end of Note 2 of Article 1030.03 of the Standard Specifications.

"A dedicated storage tank for the ground tire rubber (GTR) modified asphalt binder shall be provided. This tank shall be capable of providing continuous mechanical mixing throughout and/or recirculation of the asphalt binder to provide a uniform mixture. The tank shall be heated and capable of maintaining the temperature of the asphalt binder at 300 °F to 350 °F (149 °C to 177 °C). The asphalt binder metering systems of dryer drum plants shall be calibrated with the actual GTR modified asphalt binder material with an accuracy of ± 0.40 percent."

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)

Effective: January 1, 2024 Revised: April 1, 2024

Revise the first paragraph of Article 669.04 of the Standard Specifications to read:

"669.04 Regulated Substances Monitoring. Regulated substances monitoring includes environmental observation and field screening during regulated substances management activities. The excavated soil and groundwater within the work areas shall be managed as either uncontaminated soil, hazardous waste, special waste, or non-special waste.

As part of the regulated substances monitoring, the monitoring personnel shall perform and document the applicable duties listed on form BDE 2732 "Regulated Substances Monitoring Daily Record (RSMDR)"."

Revise the first two sentences of the nineteenth paragraph of Article 669.05 of the Standard Specifications to read:

"The Contractor shall coordinate waste disposal approvals with the disposal facility and provide the specific analytical testing requirements of that facility. The Contractor shall make all arrangements for collection, transportation, and analysis of landfill acceptance testing."

Revise the last paragraph of Article 669.05 of the Standard Specifications to read:

"The Contractor shall select a permitted landfill facility or CCDD/USFO facility meeting the requirements of 35 III. Admin. Code Parts 810-814 or Part 1100, respectively. The Department will review and approve or reject the facility proposed by the Contractor based upon information provided in BDE 2730. The Contractor shall verify whether the selected facility is compliant with those applicable standards as mandated by their permit and whether the facility is presently, has previously been, or has never been, on the United States Environmental Protection Agency (U.S. EPA) National Priorities List or the Resource Conservation and Recovery Act (RCRA) List of Violating Facilities. The use of a Contractor selected facility shall in no manner delay the construction schedule or alter the Contractor's responsibilities as set forth."

Revise the first paragraph of Article 669.07 of the Standard Specifications to read:

"669.07 Temporary Staging. Soil classified according to Articles 669.05(a)(2), (b)(1), or (c) may be temporarily staged at the Contractor's option. All other soil classified according to Articles 669.05(a)(1), (a)(3), (a)(4), (a)(5), (a)(6), or (b)(2) shall be managed and disposed of without temporary staging to the greatest extent practicable. If circumstances beyond the Contractor's control require temporary staging of these latter materials, the Contractor shall request approval from the Engineer in writing.

Topsoil for re-use as final cover which has been field screened and found not to exhibit PID readings over daily background readings as documented on the BDE 2732, visual staining or

odors, and is classified according to Articles 669.05(a)(2), (a)(3), (a)(4), (b)(1), or (c) may be temporarily staged at the Contractor's option."

Add the following paragraph after the sixth paragraph of Article 669.11 of the Standard Specifications.

"The sampling and testing of effluent water derived from dewatering discharges for priority pollutants volatile organic compounds (VOCs), priority pollutants semi-volatile organic compounds (SVOCs), or priority pollutants metals, will be paid for at the contract unit price per each for VOCS GROUNDWATER ANALYSIS using EPA Method 8260B, SVOCS GROUNDWATER ANALYSIS using EPA Method 8270C, or RCRA METALS GROUNDWATER ANALYSIS using EPA Methods 6010B and 7471A. This price shall include transporting the sample from the job site to the laboratory."

Revise the first sentence of the eight paragraph of Article 669.11 of the Standard Specifications to read:

"Payment for temporary staging of soil classified according to Articles 669.05(a)(1), (a)(3), (a)(4), (a)(5), (a)(6), or (b)(2) to be managed and disposed of, if required and approved by the Engineer, will be paid according to Article 109.04."

SEEDING (BDE)

Effective: November 1, 2022

Revise Article 250.07 of the Standard Specifications to read:

"**250.07** Seeding Mixtures. The classes of seeding mixtures and combinations of mixtures will be designated in the plans.

When an area is to be seeded with two or more seeding classes, those mixtures shall be applied separately on the designated area within a seven day period. Seeding shall occur prior to placement of mulch cover. A Class 7 mixture can be applied at any time prior to applying any seeding class or added to them and applied at the same time.

		TABLE 1 - SEEDING MIXTURES	
Class	- Туре	Seeds	lb/acre (kg/hectare
1	Lawn Mixture 1/	Kentucky Bluegrass Perennial Ryegrass <i>Festuca rubra</i> ssp. r <i>ubra</i> (Creeping Red Fescue)	100 (110) 60 (70) 40 (50)
1A	Salt Tolerant Lawn Mixture 1/	Kentucky Bluegrass Perennial Ryegrass <i>Festuca rubra</i> ssp. <i>rubra</i> (Creeping Red Fescue) <i>Festuca brevipilla</i> (Hard Fescue)	60 (70) 20 (20) 20 (20) 20 (20) 20 (20)
1B	Low Maintenance Lawn Mixture 1/	Puccinellia distans (Fults Saltgrass or Salty Alkaligrass) Turf-Type Fine Fescue 3/ Perennial Ryegrass Red Top Festuca rubra ssp. rubra (Creeping Red Fescue)	60 (70) 150 (170) 20 (20) 10 (10) 20 (20)
2	Roadside Mixture 1/	Lolium arundinaceum (Tall Fescue) Perennial Ryegrass Festuca rubra ssp. rubra (Creeping Red Fescue) Red Top	100 (110) 50 (55) 40 (50) 10 (10)
2A	Salt Tolerant Roadside Mixture 1/	Lolium arundinaceum (Tall Fescue) Perennial Ryegrass Festuca rubra ssp. rubra (Creeping Red Fescue) Festuca brevipila (Hard Fescue) Puccinellia distans (Fults Saltgrass or Salty Alkaligrass)	60 (70) 20 (20) 30 (20) 30 (20) 60 (70)
3	Northern Illinois Slope Mixture 1/	Elymus canadensis (Canada Wild Rye) 5/ Perennial Ryegrass Alsike Clover 4/ Desmanthus illinoensis (Illinois Bundleflower) 4/ 5/ Schizachyrium scoparium (Little Bluestem) 5/ Bouteloua curtipendula	5 (5) 20 (20) 5 (5) 2 (2) 12 (12) 10 (10)
		(Side-Oats Grama) 5/ <i>Puccinellia distans</i> (Fults Saltgrass or Salty Alkaligrass) Oats, Spring Slender Wheat Grass 5/ Buffalo Grass 5/ 7/	30 (35) 50 (55) 15 (15) 5 (5)
3A	Southern Illinois Slope Mixture 1/	Perennial Ryegrass Elymus canadensis (Canada Wild Rye) 5/ Panicum virgatum (Switchgrass) 5/	20 (20) 20 (20) 10 (10)
		Schizachyrium scoparium (Little Blue Stem) 5/ Bouteloua curtipendula (Side-Oats Grama) 5/	12 (12) 10 (10)
		Dalea candida (White Prairie Clover) 4/ 5/ Rudbeckia hirta (Black-Eyed Susan) 5/	5 (5) 5 (5)
		Oats, Spring	5 (5) 50 (55)

Class	s – Туре	Seeds	lb/acre (kg/hectare)
4	Native Grass 2/ 6/	Andropogon gerardi (Big Blue Stem) 5/	4 (4)
		Schizachyrium scoparium (Little Blue Stem) 5/	5 (5)
		Bouteloua curtipendula (Side-Oats Grama) 5/	5 (5)
		Elymus canadensis (Canada Wild Rye) 5/	1 (1)
		Panicum virgatum (Switch Grass) 5/	1 (1)
		Sorghastrum nutans (Indian Grass) 5/	2 (2)
		Annual Ryegrass	25 (25)
		Oats, Spring	25 (25)
4.4		Perennial Ryegrass	15 (15)
4A	Low Profile Native Grass 2/ 6/	Schizachyrium scoparium (Little Blue Stem) 5/	5 (5)
		<i>Bouteloua curtipendula</i> (Side-Oats Grama) 5/	5 (5)
		<i>Elymus canadensis</i> (Canada Wild Rye) 5/	1 (1)
		Sporobolus heterolepis (Prairie Dropseed) 5/	0.5 (0.5)
		Annual Ryegrass	25 (25)
		Oats, Spring	25 (25)
		Perennial Ryegrass	15 (15)
4B	Wetland Grass and	Annual Ryegrass	25 (25)
	Sedge Mixture 2/ 6/	Oats, Spring Wetland Grasses (species below) 5/	25 (25) 6 (6)
	<u>Species:</u>		<u>% By Weight</u>
		densis (Blue Joint Grass)	12
	Carex lacustris (Lak		6
	<i>Carex slipata</i> (Awl-F <i>Carex stricta</i> (Tusso		6 6
	Carex vulpinoidea (1		6
	Eleocharis aciculari	3	
	Eleocharis obtusa (I		3
	<i>Glyceria striata</i> (For		14
	Juncus effusus (Cor		6
	Juncus tenuis (Slen		6
	Juncus torreyi (Torre	ey's Rush)	6
	Leersia oryzoides (F	Rice Cut Grass)	10
		d-Stemmed Bulrush)	3
	Scirpus atrovirens (3
		<i>iatilis</i> (River Bulrush)	3
	•	ernaemontani (Softstem Bulrush)	3
	Spartina pectinata (Uord Grass)	4

Class	s – Type	Seeds	lb/acre (kg/hectare)
5	Forb with	Annuals Mixture (Below)	1 (1)
	Annuals Mixture 2/ 5/ 6/	Forb Mixture (Below)	10 (10)
		not exceeding 25 % by weight of pecies, of the following:	
		,	
	Coreopsis lanceolata (Sa		
	Leucanthemum maximu		
	<i>Gaillardia pulchella</i> (Blar		
	Ratibida columnifera (Pr		
	<i>Rudbeckia hirta</i> (Black-E	syed Susan)	
		exceeding 5 % by weight PLS of	
	any one spec	ies, of the following:	
	Amorpha canescens (Le	ad Plant) 4/	
	Anemone cylindrica (Thi		
	Asclepias tuberosa (Butt		
	Aster azureus (Sky Blue		
	Symphyotrichum leave (
	Aster novae-angliae (Ne		
	Baptisia leucantha (Whit		
	Coreopsis palmata (Prai		
	Echinacea pallida (Pale		
	Eryngium yuccifolium (R		
	Helianthus mollis (Down Heliopsis helianthoides (
	Liatris aspera (Rough Bl		
	Liatris pycnostachya (Pra		
	Monarda fistulosa (Prairi		
	Parthenium integrifolium		
	Dalea candida (White Pr		
	Dalea purpurea (Purple		
	Physostegia virginiana (I		
	Potentilla arguta (Prairie		
	Ratibida pinnata (Yellow		
	Rudbeckia subtomentos		
	Silphium laciniatum (Cor	npass Plant)	
	Silphium terebinthinaceu	m (Prairie Dock)	
	Oligoneuron rigidum (Rig		
	Tradescantia ohiensis (S	· · · · · · · · · · · · · · · · · · ·	
	Veronicastrum virginicur	n (Culver's Root)	

Class -	– Туре	Seeds	lb/acre (kg/hectare)
5A	Large Flower Native Forb Mixture 2/ 5/ 6/	Forb Mixture (see below)	5 (5)
	<u>Species:</u>		<u>% By Weight</u>
	Aster novae-angliae (I	New England Aster)	5
	Echinacea pallida (Pa	le Purple Coneflower)	10
	Helianthus mollis (Dov	wny Sunflower)	10
	Heliopsis helianthoide	es (Ox-Eye)	10
	Liatris pycnostachya (Prairie Blazing Star)	10
	Ratibida pinnata (Yelle		5
	Rudbeckia hirta (Blacl		10
	Silphium laciniatum (C		10
	Silphium terebinthinad		20
	Oligoneuron rigidum (10
5B	Wetland Forb 2/ 5/ 6/	Forb Mixture (see below)	2 (2)
	Species:		<u>% By Weight</u>
	Acorus calamus (Swe		3
	Angelica atropurpurea		6
	Asclepias incarnata (S		2
	Aster puniceus (Purpl		10
	Bidens cernua (Begga		7
		<i>m</i> (Spotted Joe Pye Weed)	7 7
	Eupatorium perfoliatu	Autumn Sneeze Weed)	2
	Iris virginica shrevei (E		2
	Lobelia cardinalis (Ca		5
	Lobelia siphilitica (Gre		5
	Lythrum alatum (Wing		2
	Physostegia virginiana		5
		ca (Pennsylvania Smartweed)	10
	Persicaria lapathifolia		10
		ianum (Mountain Mint)	5
	Rudbeckia laciniata (C		5
	Oligoneuron riddellii (I	2	
	Sparganium eurycarp		5
6	Conservation	Schizachyrium scoparium	5 (5)
	Mixture 2/ 6/	(Little Blue Stem) 5/ <i>Elymus canadensis</i>	2 (2)
		(Canada Wild Rye) 5/	~ (~)
		Buffalo Grass 5/ 7/	5 (5)
		Vernal Alfalfa 4/	15 (15)
		Oats, Spring	48 (55)
6A	Salt Tolerant	Schizachyrium scoparium	5 (5)
	Conservation	(Little Blue Stem) 5/	
	Mixture 2/ 6/	Elymus canadensis	2 (2)
		(Canada Wild Rye) 5/	
		Buffalo Grass 5/ 7/	5 (5)
		Vernal Alfalfa 4/	15 (15)
		Oats, Spring	48 (55)
		Puccinellia distans (Fults Saltgrass or Salty Alkaligrass)	20 (20)
7	Temporary Turf	Perennial Ryegrass	50 (55)
	Cover Mixture	Oats, Spring	64 (70)

Notes:

- 1/ Seeding shall be performed when the ambient temperature has been between 45 °F (7 °C) and 80 °F (27 °C) for a minimum of seven (7) consecutive days and is forecasted to be the same for the next five (5) days according to the National Weather Service.
- 2/ Seeding shall be performed in late fall through spring beginning when the ambient temperature has been below 45 °F (7 °C) for a minimum of seven (7) consecutive days and ending when the ambient temperature exceeds 80 °F (27 °C) according to the National Weather Service.
- 3/ Specific variety as shown in the plans or approved by the Engineer.
- 4/ Inoculation required.
- 5/ Pure Live Seed (PLS) shall be used.
- 6/ Fertilizer shall not be used.
- 7/ Seed shall be primed with KNO₃ to break dormancy and dyed to indicate such.

Seeding will be inspected after a period of establishment. The period of establishment shall be six (6) months minimum, but not to exceed nine (9) months. After the period of establishment, areas not exhibiting 75 percent uniform growth shall be interseeded or reseeded, as determined by the Engineer, at no additional cost to the Department."

SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)

Effective: April 1, 2024 Revised: April 2, 2024

Revise Article 701.02(d) of the Standard Specifications to read:

"(d) Pavement Marking Tapes (Note 3)1095.06"

Add the following Note to the end of Article 701.02 of the Standard Specifications:

"Note 3. White or yellow pavement marking tape that is to remain in place longer than 14 days shall be Type IV tape."

Revise Article 703.02(c) of the Standard Specifications to read:

"(c) Pavement Marking Tapes (Note 1)1095.06"

Add the following Note to the end of Article 703.02 of the Standard Specifications:

"Note 1. White or yellow pavement marking tape that is to remain in place longer than 14 days shall be Type IV tape."

Revise Article 1095.06 of the Standard Specifications to read:

"1095.06 Pavement Marking Tapes. Type I white or yellow marking tape shall consist of glass spheres embedded into a binder on a foil backing that is precoated with a pressure sensitive adhesive. The spheres shall be of uniform gradation and distributed evenly over the surface of the tape.

Type IV tape shall consist of white or yellow tape with wet reflective media incorporated to provide immediate and continuing retroreflection in wet and dry conditions. The wet retroreflective media shall be bonded to a durable polyurethane surface. The patterned surface shall have approximately 40 ± 10 percent of the surface area raised and presenting a near vertical face to traffic from any direction. The channels between the raised areas shall be substantially free of exposed reflective elements or particles.

Blackout tape shall consist of a matte black, non-reflective, patterned surface that is precoated with a pressure sensitive adhesive.

(a) Color. The white and yellow markings shall meet the following requirements for daylight reflectance and color, when tested, using a color spectrophotometer with 45 degrees circumferential/zero degree geometry, illuminant D65, and two degree observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm.

Color	Daylight Reflectance %Y	
White	65 min.	
Yellow *	36 - 59	

*Shall match Aerospace Material Specification Standard 595 33538 (Orange Yellow) and the chromaticity limits as follows.

х	0.490	0.475	0.485	0.530
у	0.470	0.438	0.425	0.456

(b) Retroreflectivity. The white and yellow markings shall be retroreflective. Reflective values measured in accordance with the photometric testing procedure of ASTM D 4061 shall not be less than those listed in the table below. The coefficient of retroreflected luminance, R_L, shall be expressed as average millicandelas/footcandle/sq ft (millicandelas/lux/sq m), measured on a 3.0 x 0.5 ft (900 mm x 150 mm) panel at 86 degree entrance angle.

	Coefficient of Retroreflected Luminance, RL, Dry				
Туре І				Type IV	
Observation Angle	White	Yellow	Observation Angle	White	Yellow
0.2°	2700	2400	0.2°	1300	1200
0.5°	2250	2000	0.5°	1100	1000

Wet retroreflectance shall be measured for Type IV under wet conditions according to ASTM E 2177 and meet the following.

Wet Retroreflectance, Initial RL		
Color R _L 1.05/88.76		
White 300		
Yellow 200		

- (c) Skid Resistance. The surface of Type IV and blackout markings shall provide a minimum skid resistance of 45 BPN when tested according to ASTM E 303.
- (d) Application. The pavement marking tape shall have a precoated pressure sensitive adhesive and shall require no activation procedures. Test pieces of the tape shall be applied according to the manufacturer's instructions and tested according to ASTM D 1000, Method A, except that a stiff, short bristle roller brush and heavy hand pressure will be substituted for the weighted rubber roller in applying the test pieces to the metal test panel. Material tested as directed above shall show a minimum adhesion value of 750 g/in. (30 g/mm) width at the temperatures specified in ASTM D 1000. The adhesive shall be resistant to oils, acids, solvents, and water, and shall not leave objectionable stains or residue after removal. The material shall be flexible and conformable to the texture of the pavement.

- (e) Durability. Type IV and blackout tape shall be capable of performing for the duration of a normal construction season and shall then be capable of being removed intact or in large sections at pavement temperatures above 40 °F (4 °C) either manually or with a roll-up device without the use of sandblasting, solvents, or grinding. The Contractor shall provide a manufacturer's certification that the material meets the requirements for being removed after the following minimum traffic exposure based on transverse test decks with rolling traffic.
 - (1) Time in place 400 days
 - (2) ADT per lane 9,000 (28 percent trucks)
 - (3) Axle hits 10,000,000 minimum

Samples of the material applied to standard specimen plates will be measured for thickness and tested for durability in accordance with ASTM D 4060, using a CS-17 wheel and 1000-gram load, and shall meet the following criteria showing no significant change in color after being tested for the number of cycles indicated.

Test	Type I	Type IV	Blackout
Minimum Initial Thickness, mils (mm)	20 (0.51)	65 (1.65) ^{1/} 20 (0.51) ^{2/}	65 (1.65) ^{1/} 20 (0.51) ^{2/}
Durability (cycles)	5,000	1,500	1,500

- 1/ Measured at the thickest point of the patterned surface.
- 2/ Measured at the thinnest point of the patterned surface.

The pavement marking tape, when applied according to the manufacturer's recommended procedures, shall be weather resistant and shall show no appreciable fading, lifting, or shrinkage during the useful life of the marking. The tape, as applied, shall be of good appearance, free of cracks, and edges shall be true, straight, and unbroken.

- (f) Sampling and Inspection.
 - (1) Sample. Prior to approval and use of Type IV pavement marking tape, the manufacturer shall submit a notarized certification from an independent laboratory, together with the results of all tests, stating that the material meets the requirements as set forth herein. The independent laboratory test report shall state the lot tested, the manufacturer's name, and the date of manufacture.

After initial approval by the Department, samples and certification by the manufacturer shall be submitted for each subsequent batch of Type IV tape used. The manufacturer shall submit a certification stating that the material meets the requirements as set forth herein and is essentially identical to the material sent for qualification. The certification shall state the lot tested, the manufacturer's name, and the date of manufacture.

(2) Inspection. The Contractor shall provide a manufacturer's certification to the Engineer stating the material meets all requirements of this specification. All material samples for acceptance tests shall be taken or witnessed by a representative of the Bureau of Materials and shall be submitted to the Engineer of Materials, 126 East Ash Street, Springfield, Illinois 62704-4766 at least 30 days in advance of the pavement marking operations."

SIGN PANELS AND APPURTENANCES (BDE)

Effective: January 1, 2025 Revised: April 1, 2025

Add Article 720.02(c) of the Standard Specifications to read:

"(c) Aluminum Epoxy Mastic1008.03"

Revise the second and third paragraphs of Article 720.02 of the Standard Specifications to read:

"The sign mounting support channel shall be manufactured from steel or aluminum and shall be according to Standard 720001.

Steel support channels shall be according to ASTM A 1011 (A 1011M), ASTM A 635 (A 635M), ASTM A 568 (A 568M), or ASTM A 684 (A 684M), and shall be galvanized. Galvanizing shall be according to ASTM A 653 (A 653M) when galvanized before fabrication, and AASHTO M 111 (M 111M) when galvanized after fabrication. Field or post fabricated drilled holes shall be spot painted with one coat of aluminum epoxy mastic paint prior to installation."

Revise the fifth paragraph of Article 720.02 of the Standard Specifications to read:

"The stainless steel banding for mounting signs or sign support channels to light or signal standards shall be according to ASTM A 240 (A 240M) Type 302 stainless steel."

SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)

Effective: January 2, 2023

Add the following to Article 106.01 of the Standard Specifications:

"The final manufacturing process for construction materials and the immediately preceding manufacturing stage for construction materials shall occur within the United States. Construction materials shall include an article, material, or supply that is or consists primarily of the following.

- (a) Non-ferrous metals;
- (b) Plastic and polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables);
- (c) Glass (including optic glass);
- (d) Lumber;
- (e) Drywall.

Items consisting of two or more of the listed construction materials that have been combined through a manufacturing process, and items including at least one of the listed materials combined with a material that is not listed through a manufacturing process shall be exempt."

SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)

Effective: April 2, 2018

Add the following to Section 109 of the Standard Specifications.

"**109.14 Subcontractor and Disadvantaged Business Enterprise Payment Reporting.** The Contractor shall report all payments made to the following parties:

- (a) first tier subcontractors;
- (b) lower tier subcontractors affecting disadvantaged business enterprise (DBE) goal credit;
- (c) material suppliers or trucking firms that are part of the Contractor's submitted DBE utilization plan.

The report shall be made through the Department's on-line subcontractor payment reporting system within 21 days of making the payment."

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)

Effective: November 2, 2017 Revised: April 1, 2019

Replace the second paragraph of Article 109.12 of the Standard Specifications with the following:

"This mobilization payment shall be made at least seven days prior to the subcontractor starting work. The amount paid shall be at the following percentage of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

Value of Subcontract Reported on Form BC 260A	Mobilization Percentage	
Less than \$10,000	25%	
\$10,000 to less than \$20,000	20%	
\$20,000 to less than \$40,000	18%	
\$40,000 to less than \$60,000	16%	
\$60,000 to less than \$80,000	14%	
\$80,000 to less than \$100,000	12%	
\$100,000 to less than \$250,000	10%	
\$250,000 to less than \$500,000	9%	
\$500,000 to \$750,000	8%	
Over \$750,000	7%"	

SUBMISSION OF BIDDERS LIST INFORMATION (BDE)

Effective: January 2, 2025 Revised: March 2, 2025

In accordance with 49 CFR 26.11(c) all DBE and non-DBEs who bid as prime contractors and subcontractors shall provide bidders list information, including all DBE and non-DBE firms from whom the bidder has received a quote or bid to work as a subcontractor, whether or not the bidder has relied upon that bid in placing its bid as the prime contractor.

The bidders list information shall be submitted with the bid using the link provided within the "Integrated Contractor Exchange (iCX)" application of the Department's "EBids System".

SUBMISSION OF PAYROLL RECORDS (BDE)

Effective: April 1, 2021 Revised: November 2, 2023

<u>FEDERAL AID CONTRACTS</u>. Revise the following section of Check Sheet #1 of the Recurring Special Provisions to read:

"STATEMENTS AND PAYROLLS

The payroll records shall include the worker's name, social security number, last known address, telephone number, email address, classification(s) of work actually performed, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof), daily and weekly number of hours actually worked in total, deductions made, and actual wages paid.

The Contractor and each subcontractor shall submit certified payroll records to the Department each week from the start to the completion of their respective work, except that full social security numbers, last known addresses, telephone numbers, and email addresses shall not be included on weekly submittals. Instead, the payrolls need only include an identification number for each employee (e.g., the last four digits of the employee's social security number). The submittals shall be made using LCPtracker Pro software. The software is web-based and can be accessed at https://lcptracker.com/. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate option ("No Work", "Suspended", or "Complete") selected."

<u>STATE CONTRACTS</u>. Revise Item 3 of Section IV of Check Sheet #5 of the Recurring Special Provisions to read:

"3. Submission of Payroll Records. The Contractor and each subcontractor shall, no later than the 15th day of each calendar month, file a certified payroll for the immediately preceding month to the Illinois Department of Labor (IDOL) through the Illinois Prevailing Wage Portal in compliance with the State Prevailing Wage Act (820 ILCS 130). The portal can be found on the IDOL website at <u>https://www2.illinois.gov/idol/Laws-Rules/CONMED/Pages/Prevailing-Wage-Portal.aspx</u>. Payrolls shall be submitted in the format prescribed by the IDOL.

In addition to filing certified payroll(s) with the IDOL, the Contractor and each subcontractor shall certify and submit payroll records to the Department each week from the start to the completion of their respective work, except that full social security numbers shall not be included on weekly submittals. Instead, the payrolls shall include an identification number for each employee (e.g., the last four digits of the employee's social security number). In addition, starting and ending times of work each day may be omitted from the payroll records submitted. The submittals shall be made using LCPtracker Pro software. The software is web-based and can be accessed at https://lcptracker.com/.

When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate option ("No Work", "Suspended", or "Complete") selected."

SURVEYING SERVICES (BDE)

Effective: April 1, 2025

Delete the fourth paragraph of Article 667.04 of the Standard Specifications.

Delete Section 668 of the Standard Specifications.

TRAINING SPECIAL PROVISIONS (BDE)

Effective: October 15, 1975 Revised: September 2, 2021

This Training Special Provision supersedes Section 7b of the Special Provision entitled "Specific Equal Employment Opportunity Responsibilities," and is in implementation of 23 U.S.C. 140(a).

As part of the Contractor's equal employment opportunity affirmative action program, training shall be provided as follows:

The Contractor shall provide on-the-job training aimed at developing full journeyman in the type of trade or job classification involved. The number of trainees to be trained under this contract will be $\underline{1}$. In the event the Contractor subcontracts a portion of the contract work, it shall determine how many, if any, of the trainees are to be trained by the subcontractor, provided however, that the Contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The Contractor shall also ensure that this Training Special Provision is made applicable to such subcontract. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training.

The number of trainees shall be distributed among the work classifications on the basis of the Contractor's needs and the availability of journeymen in the various classifications within the reasonable area of recruitment. Prior to commencing construction, the Contractor shall submit to the Illinois Department of Transportation for approval the number of trainees to be trained in each selected classification and training program to be used. Furthermore, the Contractor shall specify the starting time for training in each of the classifications. The Contractor will be credited for each trainee it employs on the contract work who is currently enrolled or becomes enrolled in an approved program and will be reimbursed for such trainees as provided hereinafter.

Training and upgrading of minorities and women toward journeyman status is a primary objective of this Training Special Provision. Accordingly, the Contractor shall make every effort to enroll minority trainees and women (e.g. by conducting systematic and direct recruitment through public and private sources likely to yield minority and women trainees) to the extent such persons are available within a reasonable area of recruitment. The Contractor will be responsible for demonstrating the steps it has taken in pursuance thereof, prior to a determination as to whether the Contractor is in compliance with this Training Special Provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which he or she has successfully completed a training course leading to journeyman status or in which he or she has been employed as a journeyman. The Contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the Contractor's records should document the findings in each case.

The minimum length and type of training for each classification will be as established in the training program selected by the Contractor and approved by the Illinois Department of Transportation and the Federal Highway Administration. The Illinois Department of Transportation and the Federal Highway Administration shall approve a program, if it is reasonably calculated to meet the equal employment opportunity obligations of the Contractor and to qualify the average trainee for journeyman status in the classification concerned by the end of the training period. Furthermore, apprenticeship programs registered with the U.S. Department of Labor, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau and training programs approved by not necessarily sponsored by the U.S. Department of Labor Employment Training Administration shall also be considered acceptable provided it is being administered in a manner consistent with the equal employment obligations of Federal-aid highway construction contracts. Approval or acceptance of a training program shall be obtained from the State prior to commencing work on the classification covered by the program. It is the intention of these provisions that training is to be provided in the construction crafts rather than clerk-typists or secretarial-type positions. Training is permissible in lower level management positions such as office engineers, estimators, timekeepers, etc., where the training is oriented toward construction applications. Training in the laborer classification may be permitted provided that significant and meaningful training is provided and approved by the Illinois Department of Transportation and the Federal Highway Administration. Some offsite training is permissible as long as the training is an integral part of an approved training program and does not comprise a significant part of the overall training.

Except as otherwise noted below, the Contractor will be reimbursed 80 cents per hour of training given an employee on this contract in accordance with an approved training program. As approved by the Engineer, reimbursement will be made for training of persons in excess of the number specified herein. This reimbursement will be made even though the Contractor receives additional training program funds from other sources, provided such other source does not specifically prohibit the Contractor from receiving other reimbursement. Reimbursement for offsite training indicated above may only be made to the Contractor where he does one or more of the following and the trainees are concurrently employed on a Federal-aid project; contributes to the cost of the training, provides the instruction to the trainee or pays the trainee's wages during the offsite training period.

No payment shall be made to the Contractor if either the failure to provide the required training, or the failure to hire the trainee as a journeyman, is caused by the Contractor and evidences a lack of good faith on the part of the Contractor in meeting the requirement of this Training Special Provision. It is normally expected that a trainee will begin his training on the project as soon as feasible after start of work utilizing the skill involved and remain on the project as long as training opportunities exist in his work classification or until he has completed his training program.

It is not required that all trainees be on board for the entire length of the contract. A Contractor will have fulfilled his responsibilities under this Training Special Provision if he has provided acceptable training to the number of trainees specified. The number trained shall be determined on the basis of the total number enrolled on the contract for a significant period.

Trainees will be paid at least 60 percent of the appropriate minimum journeyman's rate specified in the contract for the first half of the training period, 75 percent for the third quarter of the training period, and 90 percent for the last quarter of the training period, unless apprentices or trainees in an approved existing program are enrolled as trainees on this project. In that case, the appropriate rates approved by the Departments of Labor or Transportation in connection with the existing program shall apply to all trainees being trained for the same classification who are covered by this Training Special Provision.

The Contractor shall furnish the trainee a copy of the program he will follow in providing the training. The Contractor shall provide each trainee with a certification showing the type and length of training satisfactorily complete.

The Contractor shall provide for the maintenance of records and furnish periodic reports documenting its performance under this Training Special Provision.

For contracts with an awarded contract value of \$500,000 or more, the Contractor is required to comply with the Illinois Works Apprenticeship Initiative (30 ILCS 559/20-20 to 20-25) and all applicable administrative rules to the extent permitted by Section 20-20(g). For federally funded projects, the number of trainees to be trained under this contract, as stated in the Training Special Provisions, will be the established goal for the Illinois Works Apprenticeship Initiative 30 ILCS 559/20-20(g). The Contractor shall make a good faith effort to meet this goal. For federally funded projects, the Illinois Works Apprenticeship Initiative will be implemented using the FHWA approved OJT procedures. The Contractor must comply with the recordkeeping and reporting obligations of the Illinois Works Apprenticeship Initiative for the life of the project, including the certification as to whether the trainee/apprentice labor hour goals were met.

Method of Measurement. The unit of measurement is in hours.

<u>Basis of Payment</u>. This work will be paid for at the contract unit price of 80 cents per hour for TRAINEES. The estimated total number of hours, unit price, and total price have been included in the schedule of prices.

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)

Effective: November 1, 2021 Revised: November 1, 2022

Add the following paragraph after the first paragraph of Article 701.08 of the Standard Specifications:

"The Contractor shall equip all vehicles and equipment with high-intensity oscillating, rotating, or flashing, amber or amber-and-white, warning lights which are visible from all directions. In accordance with 625 ILCS 5/12-215, the lights may only be in operation while the vehicle or equipment is engaged in construction operations."

WEEKLY DBE TRUCKING REPORTS (BDE)

Effective: June 2, 2012 Revised: January 2, 2025

The following applies to all Disadvantaged Business Enterprise (DBE) trucks on the project, whether they are utilized for DBE goal credit or not.

The Contractor shall notify the Engineer at least three days prior to DBE trucking activity.

The Contractor shall submit a weekly report of DBE trucks hired by the Contractor or subcontractors (i.e. not owned by the Contractor or subcontractors) to the Engineer on Department form "SBE 723" within ten business days following the reporting period. The reporting period shall be Sunday through Saturday for each week reportable trucking activities occur.

Any costs associated with providing weekly DBE trucking reports shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed.

WORK ZONE TRAFFIC CONTROL DEVICES (BDE)

Effective: March 2, 2020 Revised: January 1, 2025

Add the following to Article 701.03 of the Standard Specifications:

"(q) Temporary Sign Supports1106.02"

Revise the third paragraph of Article 701.14 of the Standard Specifications to read:

"For temporary sign supports, the Contractor shall provide a FHWA eligibility letter for each device used on the contract. The letter shall provide information for the set-up and use of the device as well as a detailed drawing of the device. The signs shall be supported within 20 degrees of vertical. Weights used to stabilize signs shall be attached to the sign support per the manufacturer's specifications."

Revise the first paragraph of Article 701.15 of the Standard Specifications to read:

"701.15 Traffic Control Devices. For devices that must meet crashworthiness standards, the Contractor shall provide a manufacturer's self-certification or a FHWA eligibility letter for each Category 1 device and a FHWA eligibility letter for each Category 2 and Category 3 device used on the contract. The self-certification or letter shall provide information for the set-up and use of the device as well as a detailed drawing of the device."

Revise the first six paragraphs of Article 1106.02 of the Standard Specifications to read:

"1106.02 Devices. Work zone traffic control devices and combinations of devices shall meet crashworthiness standards for their respective categories. The categories are as follows.

Category 1 includes small, lightweight, channelizing and delineating devices that have been in common use for many years and are known to be crashworthy by crash testing of similar devices or years of demonstrable safe performance. These include cones, tubular markers, plastic drums, and delineators, with no attachments (e.g. lights). Category 1 devices shall be MASH compliant.

Category 2 includes devices that are not expected to produce significant vehicular velocity change but may otherwise be hazardous. These include vertical panels with lights, barricades, temporary sign supports, and Category 1 devices with attachments (e.g. drums with lights). Category 2 devices shall be MASH compliant.

Category 3 includes devices that are expected to cause significant velocity changes or other potentially harmful reactions to impacting vehicles. These include crash cushions (impact attenuators), truck mounted attenuators, and other devices not meeting the definitions of Category 1 or 2. Category 3 devices manufactured after December 31, 2019 shall be MASH compliant. Category 3 devices manufactured on or before December 31, 2019, and compliant

with NCHRP 350, may be used on contracts let before December 31, 2029. Category 3 devices shall be crash tested for Test Level 3 or the test level specified.

Category 4 includes portable or trailer-mounted devices such as sign supports, speed feedback displays, arrow boards, changeable message signs, temporary traffic signals, and area lighting supports. It is preferable for Category 4 devices manufactured after December 31, 2019 to be MASH-16 compliant; however, there are currently no crash tested devices in this category, so it remains exempt from the NCHRP 350 or MASH compliance requirement.

For each type of device, when no more than one MASH compliant is available, an NCHRP 350 compliant device may be used, even if manufactured after December 31, 2019."

Revise Articles 1106.02(g), 1106.02(k), and 1106.02(l) to read:

- "(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be approved for use at Test Level 3. Test Level 2 may be used for normal posted speeds less than or equal to 45 mph.
- (k) Temporary Water Filled Barrier. The water filled barrier shall be a lightweight plastic shell designed to accept water ballast and be on the Department's qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings.

(I) Movable Traffic Barrier. The movable traffic barrier shall be on the Department's qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis."

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within <u>85</u> working days.

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Non-segregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- X. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion
- XI. Certification Regarding Use of Contract Funds for Lobbying
- XII. Use of United States-Flag Vessels:

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under title 23, United States Code, as required in 23 CFR 633.102(b) (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services). 23 CFR 633.102(e).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider. 23 CFR 633.102(e).

Form FHWA-1273 must be included in all Federal-aid designbuild contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services) in accordance with 23 CFR 633.102. The designbuilder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in solicitation-for-bids or request-for-proposals documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract). 23 CFR 633.102(b).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work

performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract. 23 CFR 633.102(d).

3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.

4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. 23 U.S.C. 114(b). The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors. 23 U.S.C. 101(a).

II. NONDISCRIMINATION (23 CFR 230.107(a); 23 CFR Part 230, Subpart A, Appendix A; EO 11246)

The provisions of this section related to 23 CFR Part 230, Subpart A, Appendix A are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR Part 60, 29 CFR Parts 1625-1627, 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR Part 60, and 29 CFR Parts 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), and Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR Part 230, Subpart A, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements. 1. Equal Employment Opportunity: Equal Employment Opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (see 28 CFR Part 35, 29 CFR Part 1630, 29 CFR Parts 1625-1627, 41 CFR Part 60 and 49 CFR Part 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140, shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR Part 35 and 29 CFR Part 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract. 23 CFR 230.409 (g)(4) & (5).

b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, sexual orientation, gender identity, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."

2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.

3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action or are substantially involved in such action, will be made fully cognizant of and will implement the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer or other knowledgeable company official.

b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.

c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women. d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.

e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

4. Recruitment: When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.

a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.

b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.

c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.

5. Personnel Actions: Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, sexual orientation, gender identity, national origin, age or disability. The following procedures shall be followed:

a. The contractor will conduct periodic inspections of project sites to ensure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.

b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.

c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.

b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs (i.e., apprenticeship and on-the-job training programs for the geographical area of contract performance). In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).

c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.

d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.

7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. 23 CFR 230.409. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:

a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.

b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability.

c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.

d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.

8. Reasonable Accommodation for Applicants /

Employees with Disabilities: The contractor must be familiar with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established thereunder. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.

9. Selection of Subcontractors, Procurement of Materials

and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.

a. The contractor shall notify all potential subcontractors, suppliers, and lessors of their EEO obligations under this contract.

b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

10. Assurances Required:

a. The requirements of 49 CFR Part 26 and the State DOT's FHWA-approved Disadvantaged Business Enterprise (DBE) program are incorporated by reference.

b. The contractor, subrecipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:

- (1) Withholding monthly progress payments;
- (2) Assessing sanctions;
- (3) Liquidated damages; and/or

(4) Disqualifying the contractor from future bidding as nonresponsible.

c. The Title VI and nondiscrimination provisions of U.S. DOT Order 1050.2A at Appendixes A and E are incorporated by reference. 49 CFR Part 21.

11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.

a. The records kept by the contractor shall document the following:

(1) The number and work hours of minority and nonminority group members and women employed in each work classification on the project;

(2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and

(3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women.

b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project indicating the number of minority, women, and nonminority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

III. NONSEGREGATED FACILITIES

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of more than \$10,000. 41 CFR 60-1.5.

As prescribed by 41 CFR 60-1.8, the contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, sexual orientation, gender identity, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location under the contractor's control where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size), in accordance with 29 CFR 5.5. The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. 23 U.S.C. 113. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. 23 U.S.C. 101. Where applicable law requires that projects be treated as a project on a Federal-aid highway, the provisions of this subpart will apply regardless of the location of the project. Examples include: Surface Transportation Block Grant Program projects funded under 23 U.S.C. 133 [excluding recreational trails projects], the Nationally Significant Freight and Highway Projects funded under 23 U.S.C. 117, and National Highway Freight Program projects funded under 23 U.S.C. 167.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA- 1273 format and FHWA program requirements.

1. Minimum wages (29 CFR 5.5)

a. Wage rates and fringe benefits. All laborers and mechanics employed or working upon the site of the work (or otherwise working in construction or development of the project under a development statute), will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of basic hourly wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics. As provided in paragraphs (d) and (e) of 29 CFR 5.5, the appropriate wage determinations are effective by operation of law even if they have not been attached to the contract. Contributions made or costs reasonably anticipated for bona fide fringe benefits under the Davis-Bacon Act (40 U.S.C. 3141(2)(B)) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph 1.e. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics must be paid the appropriate wage rate and fringe benefits on the wage determination for the classification(s) of work actually performed, without regard to skill, except as provided in paragraph 4. of this section. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classifications and wage rates conformed under paragraph 1.c. of this section) and the Davis-Bacon poster (WH-1321) must be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

b. Frequently recurring classifications. (1) In addition to wage and fringe benefit rates that have been determined to be prevailing under the procedures set forth in <u>29 CFR part 1</u>, a wage determination may contain, pursuant to § 1.3(f), wage and fringe benefit rates for classifications of laborers and mechanics for which conformance requests are regularly submitted pursuant to paragraph 1.c. of this section, provided that:

(i) The work performed by the classification is not performed by a classification in the wage determination for which a prevailing wage rate has been determined; (ii) The classification is used in the area by the construction industry; and

(iii) The wage rate for the classification bears a reasonable relationship to the prevailing wage rates contained in the wage determination.

(2) The Administrator will establish wage rates for such classifications in accordance with paragraph 1.c.(1)(iii) of this section. Work performed in such a classification must be paid at no less than the wage and fringe benefit rate listed on the wage determination for such classification.

c. Conformance. (1) The contracting officer must require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract be classified in conformance with the wage determination. Conformance of an additional classification and wage rate and fringe benefits is appropriate only when the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

(ii) The classification is used in the area by the construction industry; and

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) The conformance process may not be used to split, subdivide, or otherwise avoid application of classifications listed in the wage determination.

(3) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken will be sent by the contracting officer by email to <u>DBAconformance@dol.gov</u>. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30–day period that additional time is necessary.

(4) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer will, by email to <u>DBAconformance@dol.gov</u>, refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30–day period that additional time is necessary.

(5) The contracting officer must promptly notify the contractor of the action taken by the Wage and Hour Division

under paragraphs 1.c.(3) and (4) of this section. The contractor must furnish a written copy of such determination to each affected worker or it must be posted as a part of the wage determination. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 1.c.(3) or (4) of this section must be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

d. *Fringe benefits not expressed as an hourly rate.* Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor may either pay the benefit as stated in the wage determination or may pay another bona fide fringe benefit or an hourly cash equivalent thereof.

e. Unfunded plans. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, *Provided*, That the Secretary of Labor has found, upon the written request of the contractor, in accordance with the criteria set forth in § 5.28, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

f. *Interest*. In the event of a failure to pay all or part of the wages required by the contract, the contractor will be required to pay interest on any underpayment of wages.

2. Withholding (29 CFR 5.5)

a. Withholding requirements. The contracting agency may, upon its own action, or must, upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor so much of the accrued payments or advances as may be considered necessary to satisfy the liabilities of the prime contractor or any subcontractor for the full amount of wages and monetary relief, including interest, required by the clauses set forth in this section for violations of this contract, or to satisfy any such liabilities required by any other Federal contract, or federally assisted contract subject to Davis-Bacon labor standards, that is held by the same prime contractor (as defined in § 5.2). The necessary funds may be withheld from the contractor under this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract that is subject to Davis-Bacon labor standards requirements and is held by the same prime contractor, regardless of whether the other contract was awarded or assisted by the same agency, and such funds may be used to satisfy the contractor liability for which the funds were withheld. In the event of a contractor's failure to pay any laborer or mechanic, including any apprentice or helper working on the site of the work all or part of the wages required by the contract, or upon the contractor's failure to submit the required records as discussed in paragraph 3.d. of this section, the contracting agency may on its own initiative and after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

b. *Priority to withheld funds*. The Department has priority to funds withheld or to be withheld in accordance with paragraph

2.a. of this section or Section V, paragraph 3.a., or both, over claims to those funds by:

(1) A contractor's surety(ies), including without limitation performance bond sureties and payment bond sureties;

(2) A contracting agency for its reprocurement costs;

(3) A trustee(s) (either a court-appointed trustee or a U.S. trustee, or both) in bankruptcy of a contractor, or a contractor's bankruptcy estate;

(4) A contractor's assignee(s);

(5) A contractor's successor(s); or

(6) A claim asserted under the Prompt Payment Act, <u>31</u> <u>U.S.C. 3901</u>–3907.

3. Records and certified payrolls (29 CFR 5.5)

a. Basic record requirements (1) Length of record retention. All regular payrolls and other basic records must be maintained by the contractor and any subcontractor during the course of the work and preserved for all laborers and mechanics working at the site of the work (or otherwise working in construction or development of the project under a development statute) for a period of at least 3 years after all the work on the prime contract is completed.

(2) Information required. Such records must contain the name; Social Security number; last known address, telephone number, and email address of each such worker; each worker's correct classification(s) of work actually performed; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in 40 U.S.C. <u>3141(2)(B)</u> of the Davis-Bacon Act); daily and weekly number of hours actually worked in total and on each covered contract; deductions made; and actual wages paid.

(3) Additional records relating to fringe benefits. Whenever the Secretary of Labor has found under paragraph 1.e. of this section that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in <u>40 U.S.C.</u> <u>3141(2)(B)</u> of the Davis-Bacon Act, the contractor must maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits.

(4) Additional records relating to apprenticeship. Contractors with apprentices working under approved programs must maintain written evidence of the registration of apprenticeship programs, the registration of the apprentices, and the ratios and wage rates prescribed in the applicable programs.

b. Certified payroll requirements (1) Frequency and method of submission. The contractor or subcontractor must submit weekly, for each week in which any DBA- or Related Actscovered work is performed, certified payrolls to the contracting agency. The prime contractor is responsible for the submission of all certified payrolls by all subcontractors. A contracting agency or prime contractor may permit or require contractors to submit certified payrolls through an electronic system, as long as the electronic system requires a legally valid electronic signature; the system allows the contractor, the contracting agency, and the Department of Labor to access the certified payrolls upon request for at least 3 years after the work on the prime contractor permits other methods of submission in situations where the contractor is unable or limited in its ability to use or access the electronic system.

(2) Information required. The certified payrolls submitted must set out accurately and completely all of the information required to be maintained under paragraph 3.a.(2) of this section, except that full Social Security numbers and last known addresses, telephone numbers, and email addresses must not be included on weekly transmittals. Instead, the certified payrolls need only include an individually identifying number for each worker (e.g., the last four digits of the worker's Social Security number). The required weekly certified payroll information may be submitted using Optional Form WH-347 or in any other format desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division website at https://www.dol.gov/sites/dolgov/files/WHD/ legacy/files/wh347/.pdf or its successor website. It is not a violation of this section for a prime contractor to require a subcontractor to provide full Social Security numbers and last known addresses, telephone numbers, and email addresses to the prime contractor for its own records, without weekly submission by the subcontractor to the contracting agency.

(3) Statement of Compliance. Each certified payroll submitted must be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor, or the contractor's or subcontractor's agent who pays or supervises the payment of the persons working on the contract, and must certify the following:

(i) That the certified payroll for the payroll period contains the information required to be provided under paragraph 3.b. of this section, the appropriate information and basic records are being maintained under paragraph 3.a. of this section, and such information and records are correct and complete;

(ii) That each laborer or mechanic (including each helper and apprentice) working on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in <u>29 CFR part 3</u>; and

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification(s) of work actually performed, as specified in the applicable wage determination incorporated into the contract.

(4) Use of Optional Form WH–347. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 will satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(3) of this section.

(5) *Signature*. The signature by the contractor, subcontractor, or the contractor's or subcontractor's agent must be an original handwritten signature or a legally valid electronic signature.

(6) *Falsification*. The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under <u>18 U.S.C. 1001</u> and <u>31 U.S.C. 3729</u>.

(7) *Length of certified payroll retention.* The contractor or subcontractor must preserve all certified payrolls during the course of the work and for a period of 3 years after all the work on the prime contract is completed.

c. Contracts, subcontracts, and related documents. The contractor or subcontractor must maintain this contract or subcontract and related documents including, without limitation, bids, proposals, amendments, modifications, and extensions. The contractor or subcontractor must preserve these contracts, subcontracts, and related documents during the course of the work and for a period of 3 years after all the work on the prime contract is completed.

d. Required disclosures and access (1) Required record disclosures and access to workers. The contractor or subcontractor must make the records required under paragraphs 3.a. through 3.c. of this section, and any other documents that the contracting agency, the State DOT, the FHWA, or the Department of Labor deems necessary to determine compliance with the labor standards provisions of any of the applicable statutes referenced by § 5.1, available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and must permit such representatives to interview workers during working hours on the job.

(2) Sanctions for non-compliance with records and worker access requirements. If the contractor or subcontractor fails to submit the required records or to make them available, or refuses to permit worker interviews during working hours on the job, the Federal agency may, after written notice to the contractor, sponsor, applicant, owner, or other entity, as the case may be, that maintains such records or that employs such workers, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available, or to permit worker interviews during working hours on the job, may be grounds for debarment action pursuant to § 5.12. In addition, any contractor or other person that fails to submit the required records or make those records available to WHD within the time WHD requests that the records be produced will be precluded from introducing as evidence in an administrative proceeding under 29 CFR part 6 any of the required records that were not provided or made available to WHD. WHD will take into consideration a reasonable request from the contractor or person for an extension of the time for submission of records. WHD will determine the reasonableness of the request and may consider, among other things, the location of the records and the volume of production.

(3) *Required information disclosures.* Contractors and subcontractors must maintain the full Social Security number and last known address, telephone number, and email address

of each covered worker, and must provide them upon request to the contracting agency, the State DOT, the FHWA, the contractor, or the Wage and Hour Division of the Department of Labor for purposes of an investigation or other compliance action.

4. Apprentices and equal employment opportunity (29 CFR 5.5)

a. Apprentices (1) Rate of pay. Apprentices will be permitted to work at less than the predetermined rate for the work they perform when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship (OA), or with a State Apprenticeship Agency recognized by the OA. A person who is not individually registered in the program, but who has been certified by the OA or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice, will be permitted to work at less than the predetermined rate for the work they perform in the first 90 days of probationary employment as an apprentice in such a program. In the event the OA or a State Apprenticeship Agency recognized by the OA withdraws approval of an apprenticeship program, the contractor will no longer be permitted to use apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(2) *Fringe benefits.* Apprentices must be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringe benefits must be paid in accordance with that determination.

(3) Apprenticeship ratio. The allowable ratio of apprentices to journeyworkers on the job site in any craft classification must not be greater than the ratio permitted to the contractor as to the entire work force under the registered program or the ratio applicable to the locality of the project pursuant to paragraph 4.a.(4) of this section. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in paragraph 4.a.(1) of this section, must be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under this section must be paid not less than the applicable wage rate on the wage determination for the work actually performed.

(4) Reciprocity of ratios and wage rates. Where a contractor is performing construction on a project in a locality other than the locality in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyworker's hourly rate) applicable within the locality in which the construction is being performed must be observed. If there is no applicable ratio or wage rate for the locality of the project, the ratio and wage rate specified in the contractor's registered program must be observed.

b. Equal employment opportunity. The use of apprentices and journeyworkers under this part must be in conformity with

the equal employment opportunity requirements of Executive Order 11246, as amended, and <u>29 CFR part 30</u>.

c. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federalaid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. 23 CFR 230.111(e)(2). The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeyworkers shall not be greater than permitted by the terms of the particular program.

5. Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract as provided in 29 CFR 5.5.

6. Subcontracts. The contractor or subcontractor must insert FHWA-1273 in any subcontracts, along with the applicable wage determination(s) and such other clauses or contract modifications as the contracting agency may by appropriate instructions require, and a clause requiring the subcontractors to include these clauses and wage determination(s) in any lower tier subcontracts. The prime contractor is responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in this section. In the event of any violations of these clauses, the prime contractor and any subcontractor(s) responsible will be liable for any unpaid wages and monetary relief, including interest from the date of the underpayment or loss, due to any workers of lower-tier subcontractors, and may be subject to debarment, as appropriate. 29 CFR 5.5.

7. Contract termination: debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract as provided in 29 CFR 5.5.

9. Disputes concerning labor standards. As provided in 29 CFR 5.5, disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

10. Certification of eligibility. a. By entering into this contract, the contractor certifies that neither it nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of $\underline{40}$ U.S.C. 3144(b) or § 5.12(a).

b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of $\underline{40}$ <u>U.S.C. 3144(b)</u> or § 5.12(a).

c. The penalty for making false statements is prescribed in the U.S. Code, Title 18 Crimes and Criminal Procedure, <u>18</u> <u>U.S.C. 1001</u>.

11. Anti-retaliation. It is unlawful for any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, or to cause any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, any worker or job applicant for:

a. Notifying any contractor of any conduct which the worker reasonably believes constitutes a violation of the DBA, Related Acts, this part, or $\underline{29 \text{ CFR part 1}}$ or $\underline{3}$;

b. Filing any complaint, initiating or causing to be initiated any proceeding, or otherwise asserting or seeking to assert on behalf of themselves or others any right or protection under the DBA, Related Acts, this part, or <u>29 CFR part 1</u> or <u>3</u>;

c. Cooperating in any investigation or other compliance action, or testifying in any proceeding under the DBA, Related Acts, this part, or $\underline{29 \ CFR \ part \ 1}$ or $\underline{3}$; or

d. Informing any other person about their rights under the DBA, Related Acts, this part, or $\frac{29 \text{ CFR part 1}}{3}$ or $\frac{3}{2}$.

V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

Pursuant to 29 CFR 5.5(b), the following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchpersons and guards.

1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek. 29 CFR 5.5.

2. Violation; liability for unpaid wages; liquidated

damages. In the event of any violation of the clause set forth in paragraph 1. of this section the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages and interest from the date of the underpayment. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchpersons and guards, employed in violation of the clause set forth in paragraph 1. of this section, in the sum currently provided in 29 CFR $5.5(b)(2)^*$ for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph 1. of this section.

* \$31 as of January 15, 2023 (See 88 FR 88 FR 2210) as may be adjusted annually by the Department of Labor, pursuant to the Federal Civil Penalties Inflation Adjustment Act of 1990.

3. Withholding for unpaid wages and liquidated damages

a. Withholding process. The FHWA or the contracting agency may, upon its own action, or must, upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor so much of the accrued payments or advances as may be considered necessary to satisfy the liabilities of the prime contractor or any subcontractor for any unpaid wages; monetary relief, including interest; and liquidated damages required by the clauses set forth in this section on this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract subject to the Contract Work Hours and Safety Standards Act that is held by the same prime contractor (as defined in § 5.2). The necessary funds may be withheld from the contractor under this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract that is subject to the Contract Work Hours and Safety Standards Act and is held by the same prime contractor, regardless of whether the other contract was awarded or assisted by the same agency, and such funds may be used to satisfy the contractor liability for which the funds were withheld.

b. *Priority to withheld funds*. The Department has priority to funds withheld or to be withheld in accordance with Section IV paragraph 2.a. or paragraph 3.a. of this section, or both, over claims to those funds by:

(1) A contractor's surety(ies), including without limitation performance bond sureties and payment bond sureties;

(2) A contracting agency for its reprocurement costs;

(3) A trustee(s) (either a court-appointed trustee or a U.S. trustee, or both) in bankruptcy of a contractor, or a contractor's bankruptcy estate;

(4) A contractor's assignee(s);

(5) A contractor's successor(s); or

(6) A claim asserted under the Prompt Payment Act, <u>31</u> <u>U.S.C. 3901</u>–3907.

4. Subcontracts. The contractor or subcontractor must insert in any subcontracts the clauses set forth in paragraphs 1. through 5. of this section and a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor is responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs 1. through 5. In the

event of any violations of these clauses, the prime contractor and any subcontractor(s) responsible will be liable for any unpaid wages and monetary relief, including interest from the date of the underpayment or loss, due to any workers of lowertier subcontractors, and associated liquidated damages and may be subject to debarment, as appropriate.

5. Anti-retaliation. It is unlawful for any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, or to cause any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, any worker or job applicant for:

a. Notifying any contractor of any conduct which the worker reasonably believes constitutes a violation of the Contract Work Hours and Safety Standards Act (CWHSSA) or its implementing regulations in this part;

b. Filing any complaint, initiating or causing to be initiated any proceeding, or otherwise asserting or seeking to assert on behalf of themselves or others any right or protection under CWHSSA or this part;

c. Cooperating in any investigation or other compliance action, or testifying in any proceeding under CWHSSA or this part; or

d. Informing any other person about their rights under CWHSSA or this part.

VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System pursuant to 23 CFR 635.116.

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).

a. The term "perform work with its own organization" in paragraph 1 of Section VI refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions: (based on longstanding interpretation)

(1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;

(2) the prime contractor remains responsible for the quality of the work of the leased employees;

 (3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
 (4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.

b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract. 23 CFR 635.102.

2. Pursuant to 23 CFR 635.116(a), the contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. Pursuant to 23 CFR 635.116(c), the contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract. (based on longstanding interpretation of 23 CFR 635.116).

5. The 30-percent self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements. 23 CFR 635.116(d).

VII. SAFETY: ACCIDENT PREVENTION

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR Part 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract. 23 CFR 635.108.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and

health standards (29 CFR Part 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704). 29 CFR 1926.10.

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal- aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR Part 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 11, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT (42 U.S.C. 7606; 2 CFR 200.88; EO 11738)

This provision is applicable to all Federal-aid construction contracts in excess of \$150,000 and to all related subcontracts. 48 CFR 2.101; 2 CFR 200.327.

By submission of this bid/proposal or the execution of this contract or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, subcontractor, supplier, or vendor agrees to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401-7671q) and the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251-1387). Violations must be reported to the Federal Highway Administration and the Regional Office of the Environmental Protection Agency. 2 CFR Part 200, Appendix II.

The contractor agrees to include or cause to be included the requirements of this Section in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements. 2 CFR 200.327.

X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200. 2 CFR 180.220 and 1200.220.

1. Instructions for Certification – First Tier Participants:

a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction. 2 CFR 180.320.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default. 2 CFR 180.325.

d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances. 2 CFR 180.345 and 180.350. e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900-180.1020, and 1200. "First Tier Covered Transactions" refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction. 2 CFR 180.330.

g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold. 2 CFR 180.220 and 180.300.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. 2 CFR 180.300; 180.320, and 180.325. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. 2 CFR 180.335. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (<u>https://www.sam.gov/</u>). 2 CFR 180.300, 180.320, and 180.325.

i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default. 2 CFR 180.325.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:

(1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.335;.

(2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State, or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property, 2 CFR 180.800;

(3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification, 2 CFR 180.700 and 180.800; and

(4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default. 2 CFR 180.335(d).

(5) Are not a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and

(6) Are not a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability (USDOT Order 4200.6 implementing appropriations act requirements).

b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal. 2 CFR 180.335 and 180.340.

* * * * *

3. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders, and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200). 2 CFR 180.220 and 1200.220.

a. By signing and submitting this proposal, the prospective lower tier participant is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances. 2 CFR 180.365.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900 - 180.1020, and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. "First Tier Covered Transactions" refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated. 2 CFR 1200.220 and 1200.332.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold. 2 CFR 180.220 and 1200.220.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (<u>https://www.sam.gov/</u>), which is compiled by the General Services Administration. 2 CFR 180.300, 180.320, 180.330, and 180.335.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment. 2 CFR 180.325.

* * * * *

4. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

a. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals:

(1) is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.355;

(2) is a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and

(3) is a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability. (USDOT Order 4200.6 implementing appropriations act requirements)

 b. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal.

* * * * *

XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000. 49 CFR Part 20, App. A.

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

 This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

XII. USE OF UNITED STATES-FLAG VESSELS:

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, or any other covered transaction. 46 CFR Part 381.

This requirement applies to material or equipment that is acquired for a specific Federal-aid highway project. 46 CFR 381.7. It is not applicable to goods or materials that come into inventories independent of an FHWA funded-contract.

When oceanic shipments (or shipments across the Great Lakes) are necessary for materials or equipment acquired for a specific Federal-aid construction project, the bidder, proposer, contractor, subcontractor, or vendor agrees:

1. To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels. 46 CFR 381.7.

2. To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b)(1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Office of Cargo and Commercial Sealift (MAR-620), Maritime Administration, Washington, DC 20590. (MARAD requires copies of the ocean carrier's (master) bills of lading, certified onboard, dated, with rates and charges. These bills of lading may contain business sensitive information and therefore may be submitted directly to MARAD by the Ocean Transportation Intermediary on behalf of the contractor). 46 CFR 381.7.

ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS

ROAD CONTRACTS (23 CFR 633, Subpart B, Appendix B) This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:

a. To the extent that qualified persons regularly residing in the area are not available.

b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.

c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.

2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.

 The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.

4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.

 The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

 The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.