

SIDEWALK LAYOUT POINTS

- ① STA. 12+58.01, 16.68' LT ELEV. = 583.61
- ② STA. 12+56.18, 14.78' LT ELEV. = 583.55
- ③ STA. 12+52.86, 14.51' LT ELEV. = 583.49
- ④ STA. 12+52.86, 9.49' LT ELEV. = 583.29

BILL OF MATERIALS - SHAG BARK & CEDAR GROVE

| ITEM | UNIT | TOTAL |
|--|-------|-------|
| EARTH EXCAVATION | CU YD | 1 |
| TOPSOIL FURNISH AND PLACE, 4" | SO YD | 651 |
| HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SO YD | 27 |
| HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 344.6 |
| PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SO FT | 177 |
| SIDEWALK REMOVAL | SO FT | 152 |
| AGGREGATE WEDGE SHOULDER, TYPE B | TON | 21.2 |
| SIGN PANEL - TYPE 1 | SO FT | 26 |
| WOOD SIGN SUPPORT | FOOT | 105 |
| PAINT PAVEMENT MARKING - LINE 4" | FOOT | 1,896 |
| PAINT PAVEMENT MARKING - LINE 6" | FOOT | 208 |
| PAINT PAVEMENT MARKING - LINE 12" | FOOT | 378 |
| PAINT PAVEMENT MARKING - LINE 24" | FOOT | 18 |
| REMOVE EXISTING PARKING BLOCKS | EACH | 61 |
| PRECAST CONCRETE PARKING BLOCK | EACH | 57 |
| FOLD DOWN BOLLARDS | EACH | 1 |
| BOLLARD REMOVAL | EACH | 3 |
| PIPE CULVERTS TO BE CLEANED 15" | FOOT | 34 |
| REMOVE SIGN COMPLETE | EACH | 5 |
| BOLLARDS | EACH | 2 |
| BITUMINOUS MATERIALS (PRIME COAT) | POUND | 1,385 |

