NO PARKING
R8-3 (18 x 24)
STA. 101+25, 14' LT.
SIGN PANEL - TYPE 1, 3 SQ. FT.
WOOD SIGN SUPPORT, 15'

NO PARKING
R8-3 (18 x 24)
STA. 102+25, 14' LT.
SIGN PANEL - TYPE 1, 3 SQ. FT.
WOOD SIGN SUPPORT, 15'

NO PARKING
R8-3 (18 x 24)
STA. 103+25, 14' LT.
SIGN PANEL - TYPE 1, 3 SQ. FT.
WOOD SIGN SUPPORT, 15'

NO PARKING
R8-3 (18 x 24)
STA. 104+25, 14' LT.
SIGN PANEL - TYPE 1, 3 SQ. FT.
WOOD SIGN SUPPORT, 15'

OM-3R (12 x 36)
STA. 105+16, 18' LT. (EX.)
STA. 105+18, 12' LT. (PR.)
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
WOOD SIGN SUPPORT, 11'

20' 0 20' 40'
SCALE: 1" = 20'

N

MATCHLINE STA. 105+25

EXISTING TRASH CAN

101 102 103 104 105+00

STA. 104+55, 16' LT.
REMOVE SIGN PANEL -
TYPE, 3 SQ. FT.

OM-3L (12 x 36)
STA. 105+13, 18' LT. (EX.)
STA. 105+09, 13' LT. (PR.)
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
WOOD SIGN SUPPORT, 11'

TRAILER PARKING ONLY THIS ROW
(18 x 24)
STA. 104+55, 20' RT. (EX.)
STA. 104+77, 14' RT. (PR.)
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
TELESCOPING STEEL SIGN
SUPPORT, 14'

NO BOAT TRAILERS ALLOWED IN THIS LOT
(24 x 24)

OM-3R (12 x 36)
STA. 105+44, 9' RT. (EX.)
STA. 105+09, 17' RT. (PR.)
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
WOOD SIGN SUPPORT, 13'

OM-3L (12 x 36)
STA. 105+48, 8' RT. (EX.)
STA. 105+18, 15' RT. (PR.)
SIGN PANEL - TYPE 1, 3 SQ. FT.
WOOD SIGN SUPPORT, 11'

EXISTING TRASH CAN

CARS/w/o TRAILERS PROCEED TO BACK LOT
(24 x 24)
STA. 100+78, 21' RT.
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
WOOD SIGN SUPPORT, 15'

TRAILER PARKING ONLY THIS ROW
(18 x 24)
STA. 101+53, 75' RT. (EX.)
STA. 101+08, 30' RT. (PR.)
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
TELESCOPING STEEL SIGN
SUPPORT, 14'

RESERVED PARKING
$250 FINE
R7-8 (12 x 18)
R7-101 (12 x 6)
STA. 102+53, 131' RT. (EX.)
STA. 102+42, 134' RT. (PR.)
REMOVE SIGN PANEL - TYPE 1, 2 SQ. FT.
SIGN PANEL - TYPE 1, 2 SQ. FT.
TELESCOPING STEEL SIGN
SUPPORT, 14'

RESERVED PARKING
$250 FINE
R7-8 (12 x 18)
R7-101 (12 x 6)
STA. 102+72, 134' RT. (EX.)
STA. 102+66, 134' RT. (PR.)
REMOVE SIGN PANEL - TYPE 1, 2 SQ. FT.
SIGN PANEL - TYPE 1, 2 SQ. FT.
TELESCOPING STEEL SIGN
SUPPORT, 14'

TRAILER PARKING ONLY THIS ROW
(18 x 24)
STA. 104+43, 80' RT. (EX.)
STA. 101+08, 153' RT. (PR.)
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
TELESCOPING STEEL SIGN
SUPPORT, 14'

STA. 104+81, 157' RT.
REMOVE SIGN PANEL -
TYPE 1, 3 SQ. FT.

STA. 104+79, 197' RT.
REMOVE SIGN PANEL -
TYPE 1, 3 SQ. FT.

EXISTING TRASH CAN

INFORMATION KIOSK
COMPLETE (SEE DETAIL,)
(SEE DETAIL), 1 EACH

TRAILER PARKING ONLY THIS ROW
(18 x 24)
STA. 108+82, 133' RT. (EX.)
STA. 101+08. 92' RT. (PR.)
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
TELESCOPING STEEL SIGN
SUPPORT, 14'

REMOVE EXISTING SIGN COMPLETE, 1 EACH

GATES WILL BE CLOSED AT ____ PM
REMAINING VEHICLES WILL BE TICKETED OR TOWED
(48 x 48)
STA. 101+66, 235' RT.
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
WOOD SIGN SUPPORT, 10'

INFORMATION KIOSK COMPLETE
(SEE DETAIL), 1 EACH

EXISTING TRASH CAN

REMOVE EXISTING SIGN COMPLETE, 1 EACH

EXISTING TRASH CAN

NO RECREATIONAL BOATING OR SAILING ALLOWED
(30 X 18)

NO SWIMMING
NO WADING
(24 x 24)
STA. 101+42, 235' RT.
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
WOOD SIGN SUPPORT, 15'

EXISTING TRASH CAN

Gates will be locked at ____ PM
ALL BOAT REPLACEMENT SALES BE OFF THE LAKE
BANK BEFORE BOAT MUST BE MOORED ALL OUT
OF THE PARKING LOT BY THE TIME POSTED
(30 X 18)

IF YOU NEED ASSISTANCE CALL
(18 x 24)
STA. 101+61, 234' RT.
REMOVE AND RE-ERECT
EXISTING SIGN, 1 EACH
WOOD SIGN SUPPORT, 15'

RESERVED PARKING
$250 FINE
R7-8 (12 x 18)
R7-101 (12 x 6)
STA. 103+15, 238' RT.
REMOVE SIGN PANEL - TYPE 1, 2 SQ. FT.
SIGN PANEL - TYPE 1, 2 SQ. FT.
(TO BE PLACED ON EXISTING POST)

RESERVED PARKING
$250 FINE
R7-8 (12 x 18)
R7-101 (12 x 6)
STA. 103+31, 239' RT.
REMOVE SIGN PANEL - TYPE 1, 2 SQ. FT.
SIGN PANEL - TYPE 1, 2 SQ. FT.
(TO BE PLACED ON EXISTING POST)

FILE NAME = L:\IDOT\110G618\WD_9\Draw\CADD_Sheets\D09_PARKING LOT MARKING_SIGNING.dgn	USER NAME = Matt Overbay	DESIGNED - MJO	REVISED -
	PLOT SCALE = 40.0000 ' / in.	DRAWN - GLD	REVISED -
Default	PLOT DATE = 2/11/2013	CHECKED - SPH	REVISED -
		DATE - 2/8/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

MAIN PARKING LOT SIGNING PLAN
IDNR LASALLE LAKE STATE FISH & WILDLIFE AREA

SCALE: 1" = 20' | SHEET 1 OF 2 SHEETS | STA. 100+00 TO STA. 105+25

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	PARKS ROADS	LASALLE	20	18
		CONTRACT NO. 46254		
	ILLINOIS FED. AID PROJECT			