

SUMMARY OF QUANTITIES			CONSTRUCTION CODE 0005			
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	NORTH SITE	SOUTH SITE	EAST SITE
			TOTAL QUANTITY			
54215547	METAL END SECTIONS 12"	EACH	2			2
54215553	METAL END SECTIONS 18"	EACH	2	2		
60100080	FRENCH DRAINS	CU YD	54		54	
60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SO YD	132		132	
60900515	CONCRETE THRUST BLOCKS	EACH	1	1		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	9	3	3	3
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.33
* 72000100	SIGN PANEL - TYPE 1	SO FT	183	51	70	62
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	14	5	1	8
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	238	42	112	84
* 73000100	WOOD SIGN SUPPORT	FOOT	279.5	101.5	89.5	88.5
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	143			143
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	13,775	1,978	7,903	3,894
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1		

*Specialty Items

FILE NAME :	USER NAME : Brian Bond	DESIGNED - BMB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES NEWTON LAKE STATE FISH AND WILDLIFE AREA		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
L:\DOT\1185610\MO.J3\Draw\CADD\Sheets\046255_Summary of Quantities.dgn		DRAWN - RAH	REVISED -		SCALE: N/A	SHEET 6 OF SHEETS	STA. TO STA.	N/A	PARKS ROADS	JASPER	66	6
Sheet 4	PLOT SCALE : 100.0000' / 1" =	CHECKED - JMM	REVISED -									
	PLOT DATE : 3/29/2013	DATE - 3/29/2013	REVISED -									
										CONTRACT NO. 46255		
ILLINOIS FED. AID PROJECT												