

20700220 - POROUS GRANULAR EMBANKMENT	
LOCATION	CU YD
1+00, 0' LT TO 1+00, 23' LT	5
TOTAL	5

XX004018 - REMOVE AND RELAY BRICK SIDEWALK	
LOCATION	SQ FT
1+00, 0' TO 1+00, 22' LT	144
TOTAL	144

X0325153 - MASONRY CLEANING AND TUCKPOINTING	
LOCATION	SQ YD
1+00 TO 1+21	6.5
1+21, 0' RT TO 1+21, 28' RT	6.5
TOTAL	13

28000400 - PERIMETER EROSION BARRIER	
LOCATION	FOOT
1+24, 28' RT TO 2+46, 28, RT	125
2+47, 27' RT TO 2+56, 4' RT	33
2+56, 4' RT TO 2+25, 23' LT	36
2+06, 26' LT TO 1+18, 28 LT	88
TOTAL	282

LOCATION	REMOVAL			
	XZ127900	X0325864	X0327070	X4404700
	RETAINING WALL REMOVAL	BRICK SIDEWALK REMOVAL	REMOVE EXISTING FLAGPOLE	SIDEWALK REMOVAL (SPECIAL)
	FOOT	SQ FT	EACH	SQ FT
1+00 TO 2+04				966
2+04, 3' LT TO 5+50, 13' RT		115		
1+00, 13' LT TO 1+21, 18' LT	24			
2+46, 15' RT			1	
TOTAL	24	115	1	966

LOCATION	TREE REMOVAL AND PROTECTION	
	20100210	20101000
	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TEMPORARY FENCE
	UNIT	FOOT
1+40, 12' RT	28	
1+77, 12' RT		32
TOTAL	28	32

LOCATION	LANDSCAPING						
	25200100	25200200	28000250	E20090P2	K0012990	K1005481	X0325788
	SODDING	SUPPLE WATERING	TEMP EROS CONTR SEED	V-EUONY FORT COL 2P	P PL ORNAMENT T GAL P	SHRED BARK MULCH 3	PRE-EMERG HERBICIDE
	SQ YD	UNIT	POUND	EACH	UNIT	SQ YD	SQ YD
GRASS LAWN	650	5	13				
GROUND COVER			2	133			
DAY LILY PERIMETER			1		216		
HOSTA PLANTING BED AND PERIMETER			1		183	127	127
TOTAL	650	5	17	133	399	127	127

LOCATION	EARTHWORK			
	EARTH EXCAVATION	TOTAL EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	BALANCE WASTE (+) SHORTAGE(-)
	CU YD	CU YD	CU YD	CU YD
ENTIRE PROJECT	2	2	60	-58

NOTE:  
EARTHWORK QUANTITIES ARE ESTIMATED. EARTHWORK SHALL BE CONSTRUCTED ACCORDING TO THE TYPICAL SECTION AND TO THE LINES AND GRADES SHOWN ON THE GRADING PLAN.

 Farnsworth GROUP, INC. 2706 McGraw Drive Bloomington, Illinois 61704 800/653-8433, 309/863-1571 fax	USER NAME * #USER#	DESIGNED - JCZ	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE * #SCALE#	DRAWN - JWK	REVISED -										
	PLOT DATE * #DATE#	CHECKED - MSW	REVISED -										
		DATE - 01-11-13	REVISED -										
					SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 46260		