

URBAN
90% FED.
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE							
				ROADWAY	LANDSCAPING	BRIDGE	BRIDGE	BRIDGE	MINOR STRUCTURES	SAFETY	
				0004 S.N.	0001 URBAN	0011 S.N. 016-1322	0011 S.N. 016-1323	0011 S.N. 016-2573	0040 S.N. 016-Z014	0021 URBAN	
* 25100115	MULCH, METHOD 2	ACRE	3.0	3.0							
* 25100135	MULCH, METHOD 4	ACRE	0.5	0.5							
* 25100630	EROSION CONTROL BLANKET	SQ YD	14520	14520							
* 25100900	TURF REINFORCEMENT MAT	SQ YD	67	67							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300	300							
28000305	TEMPORARY DITCH CHECKS	FOOT	590	590							
28000400	PERIMETER EROSION BARRIER	FOOT	505	505							
28000510	INLET FILTERS	EACH	40	40							
28100105	STONE RIPRAP, CLASS A3	SQ YD	4	4							
28200200	FILTER FABRIC	SQ YD	4	4							
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	937	937							
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SQ YD	3628	3628							
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	9401	9401							
31102150	SUBBASE GRANULAR MATERIAL, TYPE C 4 1/2"	SQ YD	5127	5127							
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	9401	9401							
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	3335	3335							
42001300	PROTECTIVE COAT	SQ YD	9401	9401							

FILE NAME: I:\2008 - 194 at Ohio Street\03\0300 SHEETS\016063-500.dwg

• - DENOTES SPECIALTY ITEM
 (C) - DENOTES 100% CITY OF CHICAGO
 (A) - DENOTES NON-PARTICIPATING ITEM

COLLINS ENGINEERS

USER NAME: rgg11	DESIGNED -	REVISED -
PLOT SCALE: 1/8" = 1' in.	DRAWN -	REVISED -
PLOT DATE: 3/25/2013	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 90/94	SECTION 0303-474B-R	COUNTY COOK	TOTAL SHEETS 368	SHEET NO. 5
CONTRACT NO. 60F63				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT