

EARTHWORK SCHEDULE

STAGE 1		EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS CU YD	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
STA. FROM	TO STA.					
STAGE 1						
204+00.00	204+50.00	52.35	11.22	44.50	1.07	43.43
204+50.00	205+00.00	113.00	24.93	96.05	1.83	94.22
205+00.00	205+50.00	88.65	25.66	75.35	4.20	71.15
205+50.00	206+00.00	32.37	17.56	27.51	6.33	21.18
213+00.00	213+50.00	10.19	20.44	8.66	3.34	5.32
213+50.00	214+00.00	13.19	27.62	11.21	4.47	6.74
214+00.00	214+50.00	16.98	23.89	14.43	3.37	11.06
214+50.00	215+00.00	26.01	26.51	22.11	0.99	21.12
215+00.00	215+50.00	30.31	29.56	25.76	1.96	23.81
215+50.00	216+00.00	38.19	30.80	32.46	3.63	28.82
216+00.00	216+50.00	37.31	32.68	31.71	4.53	27.19
216+50.00	217+00.00	40.29	31.46	34.24	3.49	30.75
217+00.00	217+50.00	73.36	35.79	62.35	2.15	60.20
217+50.00	218+00.00	116.73	41.71	99.22	1.44	97.78
218+00.00	218+50.00	133.15	43.41	113.18	5.45	107.73
218+50.00	219+00.00	96.68	44.43	82.18	10.84	71.34
219+00.00	219+50.00	37.19	37.91	31.61	13.50	18.11
219+50.00	220+00.00	6.28	20.86	5.34	11.17	-5.84
220+00.00	220+50.00	0.48	0.00	0.41	0.00	0.41
TOTAL		962.20	526.44	817.87	83.76	734.11

STAGE 2		EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS CU YD	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
STA. FROM	TO STA.					
STAGE 2						
100+50.00	101+00.00	0.26	2.25	0.22	1.37	-1.14
101+00.00	101+50.00	11.38	14.49	9.68	4.74	4.94
101+50.00	102+00.00	72.74	35.31	61.83	4.29	57.54
102+00.00	102+50.00	146.83	47.88	124.81	2.52	122.29
103+00.00	103+50.00	224.89	54.77	191.16	2.09	189.07
103+50.00	104+00.00	254.90	66.05	216.66	3.81	212.85
104+00.00	104+50.00	150.19	59.30	127.66	6.64	121.01
104+50.00	105+00.00	35.38	29.96	30.07	8.79	21.29
TOTAL		896.57	310.00	762.09	34.25	727.83

STAGE 3		EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS CU YD	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
STA. FROM	TO STA.					
STAGE 3						
302+00.00	302+50.00	12.76	5.42	10.85	1.76	9.08
302+50.00	303+00.00	30.71	17.30	26.10	8.01	18.09
303+00.00	303+50.00	18.88	26.06	16.04	28.76	-12.72
303+50.00	304+00.00	0.93	31.59	0.79	95.76	-94.97
304+00.00	304+50.00	0.00	36.66	0.00	188.84	-188.84
304+50.00	305+00.00	0.00	43.46	0.00	312.74	-312.74
305+00.00	305+50.00	0.00	50.69	0.00	446.70	-446.70
305+50.00	306+00.00	0.00	50.44	0.00	420.01	-420.01
306+00.00	306+50.00	0.00	36.00	0.00	170.44	-170.44
316+00.00	316+50.00	0.00	0.00	0.00	0.00	0.00
316+50.00	317+00.00	0.00	0.00	0.00	0.00	0.00
317+00.00	317+50.00	0.48	1.31	0.41	9.10	-8.69
317+50.00	318+00.00	0.55	4.36	0.47	21.81	-21.34
318+00.00	318+50.00	0.12	7.58	0.10	12.70	-12.61
318+50.00	319+00.00	0.27	9.31	0.23	1.17	-0.94
319+00.00	319+50.00	0.22	4.79	0.19	1.17	-0.98
GRAND TOTAL		64.91	324.96	55.17	1718.97	-1663.80

FILE NAME = I:\7000 - 194 at Ohio Street\CADD\CADD_SHEET\SD160663-SCHEDULES.dgn



USER NAME = rge11
 PLOT SCALE = 2.0000' / in.
 PLOT DATE = 3/25/2013

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**I-90/94 AT OHIO STREET
 SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTÉ.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	0303-474HB-R	COOK	368	35
CONTRACT NO. 60F63				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				