

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003	0040	0040	0040	0040	0010	0010	0021	0021	0021	0021	0028	0028	0003	0003
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
X JI782010	GUARDRAIL DELINEATOR, REFLECTOR MARKER TYPE B	EACH	101	14														87
X JI782020	CONCRETE BARRIER DELINEATOR, REFLECTOR MARKER TYPE C	EACH	260															260
X JI782110	TERMINAL MARKER - DIRECT APPLIED	EACH	5															5
X JS804100	ELECTRIC SERVICE INSTALLATION	EACH	1															1
X JS810837	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	23															23
X JS810839	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	91															91
X JS811060	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	117															117
X JS812027	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	45															45
X JS813001	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 20" X 12" X 8"	EACH	3															3
X JS813022	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	4															4
X JS813053	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	8															8
X JS814001	HANDHOLE, TOLLWAY	EACH	1															1

X SPECIALTY ITEM

- |   |  |   |
|---|--|---|
| A ROADWAY AND DRAINAGE - 100% STATE       | H LIGHTING - 100% STATE  | M SHARED-USE PATH - 100% NAPERVILLE   |
| B RETAINING WALL SN 022-W063 - 100% STATE | I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE | N ROADWAY ITEMS - 100% STATE  |
| C RETAINING WALL SN 022-W064 - 100% STATE | J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE  | O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY |
| D RETAINING WALL SN 022-W065 - 100% STATE | K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE   |   |
| E RETAINING WALL SN 022-W066 - 100% STATE | L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE  |   |
| F BRIDGE SN 022-2029 - 100% STATE         |  |   |
| G BRIDGE SN 022-2030 - 100% STATE         |  |   |

FILE NAME -	USER NAME -	DESIGNED - PJD	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE NO.	DESIGNED -	DRAWN - KES	REVISED -			338	(112 & 113) WRS-5	DUPAGE	963	42
PLLOT SCALE -	CHECKED - JCM	DATE - 10/15/2012	REVISED -			CONTRACT NO. 60131				
PLLOT DATE -	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
SCALE:						SHEET NO. 37 OF 41 SHEETS		STA. TO STA.		