EARTHWORK VOLUME (CU YD)

Station To Station		Length	Earth Excavation (Suitable Cut)					Earth Excavation (15% S.F.) Used for Embankment					Embankment (Suitable Fill)					Earthwork Balance (cu yd) (+) - Wastage / (-) - Shortage					Topsoil Excavation And Placement					Removal & Disposal of Unsuitable Material					Aggregate Subgrade Improvement				
			Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4
4045+00	4045+50	50.0	25	417	125	412	0	21	354	106	350	0	0	4	0	8	13	21	350	106	342	-13	0	94	0	58	0	0	0	0	0	0	0	0	0	0	0
4045+50	4046+00	50.0	33	439	127	430	0	28	373	108	366	0	8	4	0	9	16	20	370	108	357	-16	15	88	0	46	0	0	0	0	0	0	0	0	0	0	0
4046+00	4046+50	50.0	37	480	133	460	0	31	408	113	391	0	17	3	0	8	19	15	405	113	382	-19	33	81	0	35	0	0	0	0	0	0	0	0	0	0	0
4046+50	4047+00	50.0	39	506	117	471	1	33	430	99	400	1	16	8	0	7	23	17	422	99	393	-22	32	90	0	43	0	0	0	0	0	0	0	0	0	0	0
4047+00	4047+50	50.0	43	426	78	356	3	36	362	66	303	3	12	11	0	6	31	24	351	66	297	-28	27	96	0	54	0	0	0	0	0	0	0	0	0	0	0
4047+50	4048+00	50.0	41	308	28	236	7	35	261	24	201	6	30	22	0	8	39	5	239	24	193	-33	36	95	0	48	0	0	0	0	0	0	0	0	0	0	0
4048+00	4048+50	50.0	36	227	43	198	9	31	193	36	168	7	50	56	0	26	45	-19	138	36	143	-37	46	92	0	45	0	0	0	0	0	0	0	0	0	0	0
4048+50	4049+00	50.0	33	185	86	159	9	28	158	73	135	7	102	145	0	71	46	-74	13	73	64	-38	52	87	0	41	0	0	0	0	0	0	0	0	0	0	0
4049+00	4049+50	50.0	57	199	84	144	8	48	169	71	122	7	289	294	0	173	45	-241	-125	71	-51	-38	69	97	0	30	0	0	0	0	0	0	0	0	0	0	0
4049+50	4050+00	50.0	85	208	83	132	7	72	177	70	112	6	428	444	0	293	45	-356	-268	70	-181	-39	83	109	0	27	0	0	0	0	0	0	0	0	0	0	0
4050+00	4050+50	50.0	103	206	81	108	6	87	175	68	92	5	456	591	0	399	48	-369	-416	68	-308	-43	89	118	0	28	0	0	0	0	0	0	0	0	0	0	0
4050+50	4051+00	50.0	115	198	75	86	3	98	168	64	73	3	466	751	0	524	53	-368	-583	64	-452	-50	94	126	0	28	0	0	0	0	0	0	0	0	0	0	0
4051+00	4051+50	50.0	128	181	72	65	2	108	154	61	55	2	403	857	0	766	58	-295	-703	61	-711	-56	103	131	0	44	0	0	0	0	0	0	0	0	0	0	0
4051+50	4051+83	33.0	96	126	47	37	2	82	107	40	31	1	167	591	0	532	44	-86	-484	40	-501	-43	53	85	0	58	0	0	0	0	0	0	0	0	0	0	0
4051+83	4052+50	67.0	119	272	93	187	3	101	231	79	159	3	102	1364	0	461	141	-1	-1133	79	-302	-138	35	190	0	75	0	0	0	0	0	0	0	0	0	0	0
4052+50	4053+00	50.0	15	223	63	165	1	13	189	53	140	1	0	1498	0	27	113	13	-1309	53	114	-112	0	201	0	0	0	0	0	0	0	0	0	0	0	0	0
4053+00	4053+50	50.0	12	154	53	179	0	10	131	45	152	0	0	1098	77	161	80	10	-967	-31	-9	-80	0	123	0	25	0	0	0	0	0	0	0	0	0	0	0
4053+50	4054+00	50.0	28	28	25	1059	0	24	24	21	900	0	0	234	77	1116	258	24	-210	-56	-216	-258	0	0	0	231	0	0	0	0	0	0	0	0	0	0	0
4054+00	4054+50	50.0	36	0	0	1963	0	30	0	0	1669	0	0	468	0	2199	249	30	-468	0	-530	-249	0	0	0	438	0	0	0	0	0	0	0	0	0	0	0
4054+50	4055+00	50.0	21	0	50	1256	0	18	0	43	1068	0	0	1660	97	2145	65	18	-1660	-54	-1077	-65	0	112	0	384	0	0	0	0	0	0	0	0	0	0	0
4055+00	4055+50	50.0	2	0	116	358	0	2	0	99	304	0	0	2683	232	2015	145	2	-2683	-134	-1711	-145	0	211	0	250	0	0	0	0	0	0	0	0	0	0	0
4055+50	4055+94	44.0	2	72	58	207	0	2	61	49	176	0	0	2642	119	2069	244	2	-2581	-70	-1894	-244	0	184	0	167	0	0	0	0	0	0	0	0	0	0	0
4055+94	4056+50	56.0	3	189	0	222	0	2	160	0	189	0	0	3560	0	2908	350	2	-3399	0	-2719	-350	0	242	0	210	0	0	0	0	0	0	0	0	0	0	0
4056+50	4056+92	42.0	4	130	0	160	0	3	110	0	136	0	0	2715	40	1881	213	3	-2605	-40	-1744	-213	0	176	0	140	0	0	0	0	0	0	0	0	0	0	0
4056+92	4057+22	30.0	4	81	0	118	0	4	69	0	100	0	0	1966	57	1079	134	4	-1897	-57	-979	-134	0	124	0	87	0	0	0	0	0	0	0	0	0	0	0
OMISSION AT ILLINOIS ROUTE 59 BRIDGE OVER INTERSTATE 88																																						
4059+42	4059+73	31.0	0	74	0	96	0	0	63	0	82	0	0	74	0	96	0	0	-11	0	-14	0	0	0	0	0	0	0	125	0	63	0	0	209	0	91	0
4059+73	4060+00	27.0	1	72	0	110	0	1	61	0	94	0	0	833	0	631	73	1	-772	0	-538	-73	0	51	0	50	0	0	118	0	53	0	0	186	0	79	0
4060+00	4060+50	50.0	2	144	0	244	0	2	123	0	207	0	0	2892	0	2067	273	2	-2770	0	-1860	-273	0	184	0	187	0	0	237	0	84	0	0	355	0	126	0
4060+50	4060+81	31.0	1	87	0	150	0	1	74	0	127	0	0	1860	0	1202	155	1	-1786	0	-1075	-155	0	152	0	114	0	0	155	0	67	0	0	239	0	86	0
4060+81	4061+50	69.0	3	184	0	306	0	3	157	0	260	0	0	4634	0	2450	263	3	-4478	0	-2190	-263	0	510	0	250	0	0	397	0	147	0	0	631	0	186	0
4061+50	4062+00	50.0	1	114	0	168	0	1	97	0	143	0	0	3165	0	1349	78	1	-3068	0	-1206	-78	0	340	0	94	0	0	308	0	55	0	0	481	0	81	0
4062+00	4062+50	50.0	16	50	0	119	0	14	42	0	101	0	0	1397	0	748	0	14	-1355	0	-647	0	0	123	0	3	0	0	152	0	214	0	0	231	0	256	0
4062+50	4063+00	50.0	16	97	0	49	0	13	83	0	42	0	0	1	0	223	0	13	82	0	-181	0	0	0	0	0	0	0	119	0	316	0	0	134	0	348	0
4063+00	4063+50	50.0	32	186	114	61	0	27	158	97	52	0	0	138	0	48	0	27	19	97	5	0	0	84	0	0	0	0	162	50	211	0	0	178	50	211	0
4063+50	4064+19	69.0	120	346	165	183	0	102	294	140	156	0	79	911	15	726	55	24	-617	126	-570	-55	0	210	0	0	0	0	143	69	266	0	0	164	69	359	0
4064+19	4064+50	31.0	87	164	13	69	7	74	139	11	59	6	69	543	14	781	35	5	-403	-3	-723	-29	0	74	0	53	0	0	68	0	98	0	0	85	0	176	0
4064+50	4065+00	50.0	134	208	20	87	22	114	177	17	74	19	104	639	25	1395	39	11	-462	-7	-1321	-20	0	101	0	159	0	0	103	0	110	0	0	131	0	191	0
4065+00	4065+50	50.0	120	224	28	106	24	102	190	23	90	20	89	564	13	1050	44	13	-373	11	-960	-24	0	99	0	138	0	0	112	0	103	0	0	144	0	135	0
4065+50	4066+00	50.0	110	241	23	134	21	94	205	19	114	18	190	509	0	679	44	-97	-304	19	-565	-27	61	97	0	64	0	0	117	0	94	0	0	151	0	113	0
4066+00	4066+50	50.0	107	245	45	155	11	91	208	38	132	9	304	409	0	458	45	-213	-200	38	-327	-36	124	94	0	0	0	0	59	0	47	0	0	75	0	56	0
4066+50	4067+00	50.0	100	239	65	153	6	85	203	55	130	5	311	339	0	334	54	-226	-136	55	-205	-49	126	92	0	4	0	0	0	0	0	0	0	0	0	0	0
4067+00	4067+50	50.0	98	233	39	138	3	83	198	33	117	3	321	299	0	248	60	-238	-101	33	-130	-57	128	92	0	22	0	0	0	0	0	0	0	0	0	0	0
4067+50	4068+00	50.0	91	222	37	128	3	78	188	31	109	2	329	256	0	203	56	-251	-67	31	-95	-54	126	88	0	36	0	0	0	0	0	0	0	0	0	0	0
4068+00	4068+50	50.0	61	204	35	121	1	51	174	30	103	1	284	215	0	160	48	-232	-41	30	-57	-47	120	77	0	36	0	0	0	0	0	0	0	0	0	0	0
4068+50	4069+00	50.0	38	199	32	114	0	33	169	27	97	0	206	183	0	132	34	-173	-13	27	-35	-34	114	70	0	34	0	0	0	0	0	0	0	0	0	0	0
4069+00	4069+50	50.0	38	204	31	113	2	32	173	26	96	2	168	163	0	110	17	-136	11	26	-14	-15	108	69	0	32	0	0	0	0	0	0	0	0	0	0	0
4069+50	4070+00	50.0	38	203	30	110	4	32	172	26	94	3	139	145	0	98	9	-107	28	26	-4	-5	87	70	0	32	0	0	0	0	0	0	0	0	0	0	0
4070+00	4070+50	50.0	38	208	28	68	3	32	176	24	58	2	87	115	0	66	12	-55	62	24	-8	-10	56	79	0	25	0	0	0	0	0	0	0	0	0	0	0
4070+50	4071+00	50.0	35	239	27	24	7	30	203	23	20	6	48	48	0	32	12	-18	155	23	-12	-6	38	58	0	13	0	0	0	0	0	0	0	0	0	0	0
4071+00	4071+50	50.0	34	221	25	21	6	28	188	21	18	5	19	13	0	35	8	10	175	21	-17	-2	16	34	0	18	4	0	0	0	0	0	0	0	0	0	0
4071+50	4072+00	50.0	32	238	25	29	3	27	202	21	25	2	0	13	0	58	7	27	189	21	-33	-5	0	20	0	40	4	0	0	0	0	0	0	0	0	0	0
4072+00	4072+50	50.0	29	185	13	30	10	24	157	11	25	9	0	5	0	43	7	24	153	11	-17	2	0	24	0	27	4	0	0	0	0	0	0	0	0	0	0
4072+50	4073+00	50.0	15	60	0	94	19	13	51	0	80	16	0	38	0	17	7	13	13	0	63	10	0	64	0	0	7	0	0	0	0	0	0	0	0	0	0
4073+00	4073+50	50.0	4	40	0	121	21	3	34	0	103	18	0	70	0	23	7	3	-35	0	80	12	0	81	0	0	6	0	0	0	0	0	0	0	0	0	0
4073+50	4074+00	50.0	3	38	0	51	18	3	32	0	43	15	0	72	0	33	7	3	-40	0	11	8	0	82	0	26	6	0	0	0	0	0	0	0	0	0	0
4074+00	4074+50	50.0	3	39	0	25	16	3	33	0	21	13	0	69	0	40	7	3	-36	0	-19	7	0	80	0	47	6	0	0	0	0	0	0	0	0	0	0
4074+50	4075+00	50.0	3	39	0	25	16	3	33	0	22	13	0	63	0	37	5	3	-30	0	-15	9	0	77	0	36	7	0	0	0	0	0	0	0	0	0	0
4075+00	4075+50	50.0	3	40	0	24	16	2	34	0	20	14	0	58	0	42	3	2	-24	0	-22	10	0	75	0	34	7	0	0	0	0	0	0	0	0	0	0
4075+50	4076+00	50.0	3	40	0	18	16	2	34	0	15	14	0	59	0	60	4	2	-25	0	-45	10	0	72	0	39	7	0	0	0	0	0	0	0	0	0	0