EARTHWORK VOLUME (CU YD)

Station To Station		Length	Earth Excavation (Suitable Cut)					Earth Excavation (15% S.F.) Used for Embankment					Embankment (Suitable Fill)					Earthwork Balance (cu yd) (+) - Wastage / (-) - Shortage					Topsoil Excavation And Placement					Removal & Disposal of Unsuitable Material					Aggregate Subgrade Improvement				
			Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4
1993+50	1994+00	50.0	25	170	0	89	0	21	144	0	76	0	99	57	0	18	0	-77	88	0	57	0	45	100	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1994+00	1994+50	50.0	25	138	0	131	0	21	117	0	111	0	54	116	0	4	0	-33	1	0	107	0	34	118	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1994+50	1995+00	50.0	25	102	0	261	0	21	87	0	222	0	16	219	0	0	0	5	-132	0	222	0	12	118	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1995+00	1995+50	50.0	13	98	0	467	0	11	84	0	397	0	3	499	0	0	0	9	-415	0	397	0	1	120	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1995+50	1996+00	50.0	0	112	0	657	0	0	96	0	559	0	0	1055	0	0	0	0	-960	0	559	0	0	142	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1996+00	1996+50	50.0	14	262	0	809	0	12	223	0	687	0	3	1356	0	1	0	9	-1133	0	686	0	3	189	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1996+50	1997+00	50.0	28	287	0	867	0	24	244	0	737	0	4	1269	0	2	0	20	-1025	0	735	0	3	206	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1997+00	1997+50	50.0	31	148	0	704	0	27	126	0	598	0	39	970	0	2	0	-13	-843	0	597	0	17	163	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1997+50	1998+00	50.0	37	177	0	450	0	31	151	0	382	0	103	626	0	3	0	-71	-475	0	380	0	41	121	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1998+00	1998+50	50.0	40	206	0	263	0	34	175	0	224	0	148	368	0	52	0	-114	-193	0	172	0	56	52	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1998+50	1999+00	50.0	40	97	0	87	0	34	83	0	74	0	199	109	0	50	0	-165	-26	0	24	0	88	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1999+00																																						
SUB-TOTAL =>>			568	2540	0	6109	0	483	2159	0	5192	0	2797	6996	0	718	0	-2315	-4838	0	4475	0	871	1738	0	209	0	0	0	0	0	0	0	0	0	0	0
SUB-TOTAL BY STAGE =>>			4,759	21,425	11,736	24,160	369	4,045	18,211	9,976	20,536	314	23,975	67,052	10,511	35,679	4,190	-19,930	-48,841	-535	-15,143	-3,876	7,024	14,632	1,576	4,431	235	0	2,638	119	1,929	0	0	3,657	119	2,494	0
TOTAL BY PAY-ITEM =>>				62,448					53,081					141,407					-88,326					27,897					4,686					6,270			
SAY =>>				62,450										141,410					-88,330					27,900													

A

FILE NAME = $FILE$	USER NAME = $USER$	DESIGNED PJO	REVISED -ADDENDUM A 12/17/2012	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES EARTHWORK ITEMS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN KES	REVISED -			338	(112 & 113) WRS-5	DUPAGE	963 / 69
	PLOT SCALE = $SCALE$	CHECKED JCM	REVISED -					CONTRACT NO. 60I31	
	PLOT DATE = $DATE$	DATE 10/15/2012	REVISED -		SCALE: SHEET NO. 5 OF 12 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT	