





STAGE 3 TEMPORARY TRAFFIC SIGNALS


SEE SHEET TS-10 FOR STAGE 3 TEMPORARY CABLE PLAN

RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.


THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

LEGEND

-  CONSTRUCTION WORK ZONE
-  TEMPORARY PAVEMENT PLACED IN THIS STAGE
-  DIRECTION OF TRAFFIC
-  VIDEO DETECTION ZONE



INCIDENTAL TO TEMPORARY TRAFFIC SIGNAL INSTALLATION



FILE NAME	USER NAME	DESIGNED	REVISIONS
4	4	MJM	-
		DRAWN	REVISIONS
		KES	-
		CHECKED	REVISIONS
		JCM	-
		DATE	REVISIONS
		10/15/2012	-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TEMPORARY TRAFFIC SIGNAL INSTALLATION
MOT STAGE 3
ILLINOIS ROUTE 59 AND I-88 NORTH RAMPS**

SCALE: AS SHOWN | SHEET NO. 9 OF 53 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-5	DUPAGE	963	424
TS-9			CONTRACT NO. 60131	
ILLINOIS FED. AID PROJECT				