



**EROSION CONTROL LEGEND**

- |  |  |  |   |
|--|--|--|---|
|  | TEMPORARY EROSION CONTROL SEEDING AND TEMPORARY EROSION CONTROL BLANKET              |  | TEMPORARY DITCH CHECK                               |
|  | PERMANENT SEEDING (SEE NOTE 3)   |  | TEMPORARY DITCH CHECK INSTALLED IN PREVIOUS STAGE   |
|  | TEMPORARY EROSION CONTROL SEEDING OR PERMANENT SEEDING INSTALLED IN A PREVIOUS STAGE |  | INLET & PIPE PROTECTION                             |
|  | TEMPORARY PAVEMENT   |  | INLET & PIPE PROTECTION INSTALLED IN PREVIOUS STAGE |
|  | PERIMETER EROSION BARRIER (SEE NOTE 2)   |  | FLOW DIRECTION (SEE NOTE 4)                         |
|  | PERIMETER EROSION BARRIER INSTALLED IN PREVIOUS STAGE                                |  | PROPOSED STORM SEWER (SEE NOTE 1)                   |
|  | INLET FILTER   |  | PROPOSED STORM SEWER INSTALLED IN PREVIOUS STAGE    |
|  | INLET FILTER INSTALLED IN PREVIOUS STAGE   |  | TEMPORARY PIPE CULVERT                              |
|  | PERMANENT DRAINAGE STRUCTURE NUMBER (SEE NOTE 1)                                     |  |   |

**NOTES**

- SEE PROPOSED DRAINAGE PLANS FOR STORM SEWER INFORMATION
- PERIMETER EROSION BARRIER SHALL BE ERECTED ADJACENT TO R.O.W., EASEMENT, AND CONSTRUCTION LIMITS AND AS DIRECTED BY THE ENGINEER.
- SEE LANDSCAPING PLANS FOR LANDSCAPING REQUIREMENTS.
- SEE PRE-STAGE CROSS SECTIONS FOR GRADING INFORMATION.
- REMOVING INLETS/CATCH BASINS/MANHOLES TO MAINTAIN FLOW.

FILE NAME	USER NAME	DESIGNED	REVISED	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EROSION CONTROL - PRESTAGE ILLINOIS ROUTE 59</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILES		DRAWN	REVISED			338	(112 & 113) WRS-5	DUPAGE	963	477	
PLOT SCALE		CHECKED	REVISED			CONTRACT NO. 60131		ILLINOIS FED. AID PROJECT			
PLOT DATE		DATE	REVISED			SCALE: SHEET NO. 2 OF 66 SHEETS STA. 4045+00 TO STA. 4051+00					