


- NOTES:**
1. FOR UNDERPASS LIGHTING PLAN SEE SHEET LT-17.
  2. FOR SYMBOL LIST AND GENERAL ELECTRICAL NOTES, SEE SHEET LT-06.
  3. NEW TOLLWAY LIGHTING CONTROLLER AND SERVICE INSTALLED BEFORE BEGINNING OF THE RAMPS' WORK.

**TOLLWAY CABLEDUCT SCHEDULE**

- (B) UNIT DUCT, WITH 4-1/2 NO. 2 AND 1/2 NO. 4 GROUND, 600V (XLP-TYPE USE), 2" DIA. CNC
- (D) ELECTRIC CABLE, 600V (XLP-TYPE USE) (3)1/2 NO. 3/0 IN UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.
- (G) UNIT DUCT, WITH 4-1/2 NO. 2 AND 1/2 NO. 4 GROUND, 600V (XLP-TYPE USE), 2" DIA. CNC IN UNDERGROUND CONDUIT, PVC COATED GALVANIZED STEEL, 4" DIA.
- (H) UNIT DUCT, WITH 2-1/2 NO. 2 AND 1/2 NO. 4 GROUND, 600V (XLP-TYPE USE), 2" DIA. CNC

NOTE 1



|                     |                     |                    |         |   |   |  |                   |                           |              |           |
|---------------------|---------------------|--------------------|---------|---|---|--|-------------------|---------------------------|--------------|-----------|
| FILE NAME<br>#FILES | USER NAME<br>#USER# | DESIGNED<br>MCP    | REVISED | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>TOLLWAY LIGHTING PLAN - ILLINOIS ROUTE 59<br/>AT INTERSTATE 88</b> | F.A.P. RTE.  | SECTION           | COUNTY                    | TOTAL SHEETS | SHEET NO. |
|                     |                     | DRAWN<br>MLB       | REVISED |   |   | 338  | (112 & 113) WRS-5 | DUPAGE                    | 963          | 567       |
|                     |                     | CHECKED<br>MCP     | REVISED |   |   | <b>LT-12</b>   |                   | CONTRACT NO. 60131        |              |           |
|                     |                     | DATE<br>10/15/2012 | REVISED |   |   | SCALE: AS SHOWN   SHEET NO. 1 OF 6 SHEETS   STA. 4051+75 TO STA. 4067+00 |                   | ILLINOIS FED. AID PROJECT |              |           |