ORIGINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
NO.	PLOTTED		
	TEMPLATE		
	AREAS		
	AREAS CHECKED		

FINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
NO.	PLOTTED		
	TEMPLATE		
	AREAS		
	AREAS CHECKED		

FILE NAME = M:\DLE\s

USER NAME = MUSER4

PLOT SCALE = 1000.0

PLOT DATE = 10/15/2012

DESIGNED - RFA
DRAWN - KES
CHECKED - PJD
DATE 10/15/2012

REVISED
REVISED
REVISED

REVISED
REVISED
REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
RAMP A - STAGE 1 THRU 4

SCALE:

SHEET NO. 22 OF 23 SHEETS STA. 1039+00 TO STA. 1040+50

F.A.P. RTE. 338 | SECTION (112 & 113) WRS-5 | COUNTY DUPAGE | TOTAL SHEETS 963 | SHEET NO. 830

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | CONTRACT NO. 60131

70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100

710 705 700 695 690 685

STAGE 1

705.98

1'

	STAGE 1A	STAGE 1	UNIT
EARTH EXCAVATION	0.0	29.0	SQ FT.
EMBANKMENT	0.0	21.7	SQ FT.
TOPSOIL EXC & PLAC	0.0	22.0	SQ FT.
REM & DISP UNS MATL	0.0	4.7	SQ FT.
AGG SUBGRADE IMPROVE	0.0	4.7	SQ FT.

1040+50

1040+50

STAGE 1

705.70

1'

	STAGE 1A	STAGE 1	UNIT
EARTH EXCAVATION	0.0	31.5	SQ FT.
EMBANKMENT	0.0	24.3	SQ FT.
TOPSOIL EXC & PLAC	0.0	23.0	SQ FT.
REM & DISP UNS MATL	0.0	6.9	SQ FT.
AGG SUBGRADE IMPROVE	0.0	6.9	SQ FT.

1040+00

1040+00

STAGE 1

705.16

1'

AGGREGATE SUBGRADE IMPROVEMENT (TYP.)

	STAGE 1A	STAGE 1	UNIT
EARTH EXCAVATION	0.0	34.9	SQ FT.
EMBANKMENT	0.0	24.1	SQ FT.
TOPSOIL EXC & PLAC	0.0	22.8	SQ FT.
REM & DISP UNS MATL	0.0	13.5	SQ FT.
AGG SUBGRADE IMPROVE	0.0	13.5	SQ FT.

1039+50

1039+50

STAGE 1

704.93

1'

	STAGE 1A	STAGE 1	UNIT
EARTH EXCAVATION	0.0	39.5	SQ FT.
EMBANKMENT	0.0	31.0	SQ FT.
TOPSOIL EXC & PLAC	0.0	30.8	SQ FT.
REM & DISP UNS MATL	0.0	13.5	SQ FT.
AGG SUBGRADE IMPROVE	0.0	13.5	SQ FT.

1039+00

1039+00

NOTE:
A DEPTH OF 12 INCHES IS USED IN THE TOPSOIL EXCAVATION AND PLACEMENT CALCULATION.

70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100