

330

URBAN
90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	① ROADWAY 0004 URBAN	② BRIDGE 0011 SN 016-2439	③ BRIDGE 0011 SN 016-2440	④ BRIDGE 0014 SN 016-2441	⑤ BRIDGE 0014 SN 016-2442	⑥ 2436 BRIDGE 0011 SN 016-2470	⑦ 2438 BRIDGE 0011 SN 016-2471	⑧ SAFETY 0021 URBAN
20101000	TEMPORARY FENCE	FOOT	1,770	1,770							
20200100	EARTH EXCAVATION	CU YD	20,718	20,718							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9,606	9,606							
20400800	FURNISHED EXCAVATION	CU YD	14,722	14,722							
20800150	TRENCH BACKFILL	CU YD	831	831							
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	24,849	24,849							
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	1556	1556							
* 25000210	SEEDING, CLASS 2A	ACRE	11	11							
* 25000310	SEEDING, CLASS 4	ACRE	7	7							
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	330	330							
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	110	110							
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	990	990							
* Δ 25000750	MOWING	ACRE	6	6							
* 25003310	INTERSEEDING, CLASS 4	ACRE	7	7							

Δ NON-PARTICIPATING (100% STATE)

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



FILE NAME *	USER NAME * Default	DESIGNED -	REVISED -
#FILE#		DRAWN - OC	REVISED -
	PLOT SCALE * #SCALE#	CHECKED - RGR	REVISED -
	PLOT DATE * 4/4/2013	DATE - 03/29/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 1 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-059-BR	COOK	631	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60J12	

* Specialty Items

Rev.

S:\1072\105_CADD\060212_Spec\11\060212-INT-spec.dwg