

URBAN  
90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004 URBAN	BRIDGE 0011 SN 016-2439	BRIDGE 0011 SN 016-2440	BRIDGE 0014 SN 016-2441	BRIDGE 0014 SN 016-2442	BRIDGE 0011 SN 016-2470	BRIDGE 0011 SN 016-2471	SAFETY 0021 URBAN
48300510	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	SO YD	17,223	17,223							
50100300	REMOVAL OF EXISTING STRUCTURE NO. 1	EACH	1						1		
50100400	REMOVAL OF EXISTING STRUCTURE NO. 2	EACH	1							1	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1						
50102400	CONCRETE REMOVAL	CU YD	340.4		71.0	103.4	83.0	83.0			
50104650	SLOPE WALL REMOVAL	SO YD	99			99					
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1			1					
50157300	PROTECTIVE SHIELD	SO YD	6,293			3,960			1,373	960	
50200100	STRUCTURE EXCAVATION	CU YD	5,010			390			3,070	2,342	
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	515							515	
50300225	CONCRETE STRUCTURES	CU YD	1,040.4			89.8	68.1	68.1	440.1	367.3	7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3,206.9			1,815.8	215.4	215.4	546.8	413.5	
50300260	BRIDGE DECK GROOVING	SO YD	9,572			5,245	925	925	1,463	1,014	
50300300	PROTECTIVE COAT	SO YD	12,286			6,659	1,196	1,196	1,861	1,374	

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbandainc.com



FILE NAME	USER NAME = default	DESIGNED -	REVISED -
#FILE#		DRAWN - OC	REVISED -
	PLOT SCALE = 1/8"=1'	CHECKED - RGR	REVISED -
	PLOT DATE = 4/4/2013	DATE - 03/29/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 4 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-059-BR	COOK	631	6
CONTRACT NO. 60J12			ILLINOIS FED. AID PROJECT	

Rev.

S:\2012\05-COON\60J12-Sheet4\BIBL12-INT-1203.dwg