

PR RAMP F2	STAGE 1						STAGE 2					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
STATION	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
1206+40.00 TO 1207+00.00	119.01	101.16	4.32	96.84	35.23	23.63	0.00	0.00	0.00	0.00	0.00	0.00
1207+00.00 TO 1208+00.00	257.69	219.03	0.00	219.03	0.00	55.56	0.00	0.00	0.00	0.00	0.00	0.00
1208+00.00 TO 1209+00.00	141.65	120.40	39.15	81.25	47.67	53.80	0.00	0.00	0.00	0.00	0.00	0.00
1209+00.00 TO 1209+59.38	17.21	14.63	84.36	-69.74	66.59	24.51	0.00	0.00	0.00	0.00	0.00	0.00
1209+59.38 TO 1209+98.06	6.14	5.22	82.94	-77.72	48.21	12.94	0.00	0.00	0.00	0.00	0.00	0.00

ALIGNMENT	STAGE 1 SUMMARY					STAGE 2 SUMMARY				
	EARTH EXCAVATION (CY)	EARTHWORK BALANCE (CY)	TOPSOIL REMOVAL (CY)	TOPSOIL PLACEMENT (CY)	TOPSOIL BALANCE (CY)	EARTH EXCAVATION (CY)	BALANCE (CY)	TOPSOIL REMOVAL (CY)	TOPSOIL PLACEMENT (CY)	TOPSOIL BALANCE (CY)
EX_LINE-D	1,124.20	825.12	77.00	81.99	-4.98	998.31	628.59	495.22	195.76	299.45
EX_RAMP_R	0.11	-20.72	10.05	22.04	-11.99	-	-	-	-	-
MOD_LINE-E	355.95	-1,624.15	502.80	203.61	299.19	339.15	-1,215.07	477.02	199.15	277.86
PR_LINE-D	3,900.45	3,256.68	0.00	110.63	-110.63	2,636.34	1,593.67	425.50	1,047.65	-622.16
PR_LINE-E	1,585.08	-11,871.93	1,421.27	1,014.33	406.94	733.16	26.77	401.69	348.63	53.06
PR_LINE-F	1,616.48	-2,209.42	122.66	211.10	-88.44	2,477.76	-1,905.77	445.54	384.84	60.71
PR_LINE-F	-	-	-	-	-	1,956.14	1,131.36	0.00	782.55	-782.55
PR_RAMP-F	1,218.44	-3,608.64	1,855.64	683.75	1,171.89	645.52	470.38	323.05	387.63	-64.59
PR_RAMP_F2	541.69	249.66	197.71	170.43	27.28	-	-	-	-	-
PR_RAMP_R	589.21	281.34	12.88	200.78	-187.90	-	-	-	-	-
	10,932	-14,722	4,200	2,699	1,501	9,786	730	2,568	3,346	-778

EARTHWORK SUMMARY			
CODE NO	ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CY	20,718
20400800	FURNISHED EXCAVATION	CY	14,722
21101505	TOPSIL EXCAVATION AND PLACEMENT	CY	7,546

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



FILE NAME = *FILEL*	USER NAME = default	DESIGNED - DRAWN - BC	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EARTHWORK SCHEDULE	F.A.I. RTE. 94	SECTION 2012-059-BR	COUNTY COOK	TOTAL SHEETS 631	SHEET NO. 37	
PLOT SCALE = *SCALE*	CHECKED - RGR	REVISED -	SCALE: NA			SHEET NO. 4 OF 4 SHEETS	STA. TO STA.	CONTRACT NO. 60J12		ILLINOIS FED. AID PROJECT	
PLOT DATE = 4/26/2013	DATE - 03/29/2013	REVISED -									