


STATE OF ILLINOIS DRAWN - GEP REVISED DBS 23 N. WACKER DRIVE SUITE 2000 HICAGO, ILLINOIS 60606 EL (312)857-1008 EAX (312)857-109 PLOT DATE = CHECKED - GMK REVISED **DEPARTMENT OF TRANSPORTATION** FILE NAME = DATE - 03/29/13 REVISED

NOTES

Detail I - With Bar Splicer or Couplers: Connect one (1) 1" x 7' 'x "W" steel P to the top layer of couplers with $2 - \frac{5}{8}$ " ϕ bolts screwed to coupler at approximate *Q* of each barrier panel. Detail II - With Extended Reinforcement Bars: Connect one (1) 1" x 7" x "W" steel P to the concrete slab or concrete wearing surface with $2-\frac{5}{8}$ " ϕ Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate \mathcal{Q} of each barrier panel. Cost of anchorage is included with Temporary Concrete Barrier. The 1" x 7" x "W" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready



* Required only with Detail II

ARY CONCRETE BARRIER SN 016–2439	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	94	2012-059-BR	СООК	631	478
			CONTRACT	NO. 6	0J12
NO. S3 OF S18 SHEETS	FED. R	DAD DIST. NO. 1 ILLINOIS FED. 4	ID PROJECT		