



<u>Geotextile</u>

re-embedment length

1. Place form brace system on completed reinforcement level; back from the finished fabric face a distance of 1'-0" Min. geotextile reinforcement spacing.





5'-0" cts.

2" x 14" (nominal)
timber planks

—1" \$\phi\$ Steel pipe


\[
\text{Nod wedge to maintain vertical face}
\]

## SECTION A-A

TEMPORARY GEOTEXTILE
FORM BRACE DETAIL

# NOTE:

This is a suggested detail, the Contractor is responsible for the design of the form brace system to be used.



Geotextile Soil

Reinforcemen



3. Compact select fill material in lifts to final lift height, create (±3") depression in zone where re-embedment length will be located and place additional height of compacted select fill against form brace.

4. Fold geotextile re-embedment length back over form brace into zone where depression was made in select fill and place additional select fill (±3") to embed geotextile and bring to final lift height.



5. Pull form brace outward allowing geotextile face to slightly readjust to form tight round face level with plan reinforcement spacing.

#### 176'-10" (Geotextile Wall) 165'-6'2" Bk. to Bk. Abutments Geotextile Wall w/ Compacted Select Top of Geotextile Top of Geotextile Fill (Typ.) a 200 Elev. ±612.17 Elev. ±612.44 Bk of East Abutment--Bk of West Abutment Bottom of Wall EL. = ±604.00 Existing Slopewall (Typ.)GEOTEXTILE WALL ELEVATION

(Looking South)

# TEMPORARY GEOTEXTILE WALL CONSTRUCTION SEQUENCE

### NOTE:

The geotextile soil reinforcement shall have a minimum allowable tensile strength T min. of 42 lb./in. as determined by the procedure described in the Special Provision. The computations supporting the determination of T min. shall be submitted to the Engineer for approval.

| BILL OF MATERIAL          |       |              |  |  |  |  |  |  |  |
|---------------------------|-------|--------------|--|--|--|--|--|--|--|
| ITEM                      | UNIT  | QUANTITY     |  |  |  |  |  |  |  |
| Geotextile Retaining Wall | Sq Ft | <i>1,769</i> |  |  |  |  |  |  |  |

| USER NAME =  | DESIGNED - GFP/ GMK | REVISED - | IND STEED IN CONSULTANTS INC                                     |                              | GEOTEXTILE RETAINING WALL  | RTE.    | SECTION                       | COUNTY         | SHEETS N  | 10. |
|--------------|---------------------|-----------|--|------------------------------|----------------------------|---------|-------------------------------|----------------|-----------|-----|
| PLOT SCALE = | DRAWN - GFP         | REVISED - | DBS 123 N. WACKER DRIVE SUITE 2000                               | STATE OF ILLINOIS            | SN 016-2439                | 94      | 2012-059-BR                   | соок           | 631 4     | 481 |
| PLOT DATE =  | CHECKED - GMK       | REVISED - | CHICAGO, ILLINOIS 60606<br>TEL. (312)857-1006 FAX. (312)857-1056 | DEPARTMENT OF TRANSPORTATION | 3N 010-2433                |         |                               | CONTRAC        | T NO. 60J | 12  |
| FILE NAME =  | DATE - 03/29/13     | REVISED - |  |                              | SHEET NO. S6 OF S18 SHEETS | FED. RO | AD DIST. NO. 1   ILLINOIS FEE | D. AID PROJECT |           |     |