

100% STATE

SUMMARY OF QUANTITIES				CONSTR. TYPE CODE	
CODE	ITEM DESCRIPTION	UNIT	QUANTITY	ROADWAY	STRUCTURE
				0004 URBAN	0014 URBAN
20400800	FURNISHED EXCAVATION	CU YD	25	25	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	20		20
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	54	54	
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2	
25100630	EROSION CONTROL BLANKET	SQ YD	54	54	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	74	27	47
40600300	AGGREGATE (PRIME COAT)	TON	2	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	124	124	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	10	10	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TONS	62	23	39
50102400	CONCRETE REMOVAL	CU YD	20.3		20.3
50104650	SLOPE WALL REMOVAL	SQ YD	452		452

100% STATE

SUMMARY OF QUANTITIES				CONSTR. TYPE CODE	
CODE	ITEM DESCRIPTION	UNIT	QUANTITY	ROADWAY	STRUCTURE
				0004 URBAN	0014 URBAN
50157300	PROTECTIVE SHIELD	SQ YD	567		567
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21.9		21.9
50300260	BRIDGE DECK GROOVING	SQ YD	1030		1030
50300300	PROTECTIVE COAT	SQ YD	272		272
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1530		1530
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2240		2240
50800515	BAR SPLICERS	EACH	24		24
51100100	SLOPE WALL 4 INCH	SQ YD	452		452
52000050	PREFORMED JOINT SEAL, 4"	FOOT	80.0	80.0	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	116.0		116.0
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12		12
52100520	ANCHOR BOLTS, 1"	EACH	48		48
54213867	STEEL END SECTIONS, 12"	EACH	2	2	
59300100	CONTROLLED LOW STRENGTH MATERIAL	CU YD	6.0		6.0
60103500	PIPE DRAINS, CORRUGATED STEEL, 12"	FOOT	20	20	

\\10.11.22.18\11\data\1\possession\0005\6710\6710.02 - BrIDGE Overlay I11\CA00\Structural Drawings\CA00 Sheets\022-0090\016097-akt-50.dgn

19

15

* SPECIALTY ITEMS

FILE NAME :	USER NAME : jachneider	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES STRUCTURE NO. 022-0090			F.A.I. RTE. 290	SECTION 22-3H8-1	COUNTY DuPAGE	TOTAL SHEETS 37	SHEET NO. 3
	PLOT SCALE = 2.0000' / 1"	CHECKED - JMH	REVISED -		SCALE:	SHEET NO. 1	OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 60M97		
	PLOT DATE = 12/6/2012	DATE - JANUARY, 2013	REVISED -		ILLINOIS FED. AID PROJECT							