

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
				100% STATE	66.7% STATE 33.3% HARVARD	100% CITY OF HARVARD
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005 QUANTITY	0021 QUANTITY	0021 QUANTITY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	42	42		
25200110	SODDING, SALT TOLERANT	SQ YD	42	42		
25200200	SUPPLEMENTAL WATERING	UNIT	3	3		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	84	84		
40600300	AGGREGATE (PRIME COAT)	TON	665	665		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	23		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,607	4,607		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	645	645		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9,634	9,634		
42001300	PROTECTIVE COAT	SQ YD	58	58		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	110,698	110,698		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1,301	1,286	10	5
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	240	240		
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	107	107		

* INDICATES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
				100% STATE	66.7% STATE 33.3% HARVARD	100% CITY OF HARVARD
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005 QUANTITY	0021 QUANTITY	0021 QUANTITY
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2,780	2,780		
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	5		3	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20,797	20,797		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,080	2,080		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	203,110	203,110		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,534	6,534		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	252	252		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	6,876	6,876		

* INDICATES SPECIALTY ITEM

COMPANY & JOB OF ENGINEER & ARCHITECT
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 041-0211 - EXPIRES 12/31/2013
 2757002 34813 PM 5/10/2013 10:01:00 AM



DESIGNED - DSH	REVISED - 7-20-11 IDOT REVIEW
DRAWN - KAR	REVISED - 5-29-12 UPDATE
CHECKED - LDH	REVISED - 2-4-13 PER TRAFFIC
DATE - 12-13-10	FILE: 100153-W019-S00.SHP

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US ROUTE 14
DIGINNS STREET (IL ROUTE 173) TO STATE LINE ROAD
SUMMARY OF QUANTITIES**

F.A.P. RTE. 66	SECTION 21-RS-3	COUNTY MCHEMRY	TOTAL SHEETS 32	SHEET NO. 3
C-91-297-11	CONTRACT NO. 60N27		FED. ROAD DIST. NO. 1 ILLINOIS FED AID PROJECT	

SCALE: NONE STA. TO STA.