

40

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 MCHENRY COUNTY	0005 LAKE COUNTY	0014 LAKE COUNTY	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	82	10	72		
40600300	AGGREGATE (PRIME COAT)	TON	404	47	357		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	154	20	134		
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1098	207	891		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8452	970	7482		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	100617	11544	89073		
44201835	CLASS D PATCHES, TYPE I, 16 INCH	SO YD	40	5	35		
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SO YD	365	48	317		
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SO YD	100	13	87		
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SO YD	170	20	150		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	970	143	827		
X5870015	<i>BRIDGE DECK</i> CONCRETE SEALER	SO FT	1872			1872	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1	5		
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5		

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 MCHENRY COUNTY	0005 LAKE COUNTY		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.5	0.5		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	23323	4102	19221		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1176	255	921		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	111486	9825	101661		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3975	975	3000		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1207	198	1009		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	175		175		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	41726	5425	36301		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1176	255	921		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	111486	9825	101661		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3975	975	3000		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1207	198	1009		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175		175		

**Specialty Items*

FILE NAME: <i>10</i>	USER NAME: <i>edwardj</i>	DESIGNED: -	REVISIONS: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 22 (US 14 TO US 12) SUMMARY OF QUANTITIES	F.A.P. RTE.:	SECTION:	COUNTY:	TOTAL SHEETS:	SHEET NO.:	
<i>10</i>		DRAWN: -	REVISIONS: -			337	2010-149-RS	-	30	3	
		CHECKED: -	REVISIONS: -			CONTRACT NO. 60N33					
		DATE: -	REVISIONS: -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					