

100% STATE

| SUMMARY OF QUANTITIES | | | URBAN | | CONSTRUCTION TYPE CODE | |
|-----------------------|--|-------|----------------|---------------|------------------------|--|
| CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | 0005 QUANTITY | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 23 | 23 | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 177 | 177 | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS | TON | 3 | 3 | | |
| 40600827 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 1,249 | 1,249 | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 90 | 90 | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 245 | 245 | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 2,542 | 2,542 | | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 29,465 | 29,465 | | |
| 44002212 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3" | SQ YD | 1,415 | 1,415 | | |
| 44201761 | CLASS D PATCHES, TYPE I, 10 INCH | SQ YD | 100 | 100 | | |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SQ YD | 650 | 650 | | |
| 44201769 | CLASS D PATCHES, TYPE III, 10 INCH | SQ YD | 100 | 100 | | |
| 44201771 | CLASS D PATCHES, TYPE IV, 10 INCH | SQ YD | 350 | 350 | | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 1,485 | 1,485 | | |

* INDICATES SPECIALTY ITEM

100% STATE

| SUMMARY OF QUANTITIES | | | URBAN | | CONSTRUCTION TYPE CODE | |
|-----------------------|--|--------|----------------|---------------|------------------------|--|
| CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | 0005 QUANTITY | | |
| 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 7 | 7 | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 | | |
| 67100100 | MOBILIZATION | LSUM | 1 | 1 | | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | LSUM | 1 | 1 | | |
| 70100600 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336 | LSUM | 1 | 1 | | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 5,403 | 5,403 | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 61,406 | 61,406 | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 96 | 96 | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 601 | 601 | | |
| 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 30,703 | 30,703 | | |
| 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 48 | 48 | | |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 248 | 248 | | |
| 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 7 | 7 | | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 248 | 248 | | |
| Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 1 | 1 | | |

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2005 BY BAXTER & WOODMAN, INC.
 ALL RIGHTS RESERVED. ILLINOIS ROUTE 23, POPLAR ROAD TO INTERSTATE 90, SUMMARY OF QUANTITIES, SHEET NO. 3 OF 3.
 PROJECT NO. 24-RS-4, COUNTY OF MCHENRY, ILLINOIS.
 DATE: 12-12-10, FILE: 100153-W015-500.sht



| | |
|-----------------|----------------------------|
| DESIGNED - TMS | REVISED - |
| DRAWN - BCO | REVISED - |
| CHECKED - RWL | REVISED - |
| DATE - 12-12-10 | FILE - 100153-W015-500.sht |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 23
POPLAR ROAD TO INTERSTATE 90
SUMMARY OF QUANTITIES

| | | | | |
|---|-----------------|----------------|--------------------|-------------|
| F.A.P. RTE. 324 | SECTION 24-RS-4 | COUNTY MCHENRY | TOTAL SHEETS 16 | SHEET NO. 3 |
| SCALE: NONE | | | CONTRACT NO. 60N34 | |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | |