

# SUMMARY OF QUANTITIES

*URBAN  
100%  
STATE*

*URBAN  
100%  
STATE*

CONSTRUCTION TYPE CODE  
ROADWAY  
0005

CONSTRUCTION TYPE CODE  
ROADWAY  
0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	185	185
20400800	FURNISHED EXCAVATION	CU YD	100	100
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,667	1,667
21400100	GRADING AND SHAPING DITCHES	FOOT	800	800
25000210	SEEDING, CLASS 2A	ACRE	0.3	0.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	31	31
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	31	31
25100630	EROSION CONTROL BLANKET	SO YD	1,667	1,667
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	84	84
40600300	AGGREGATE (PRIME COAT)	TON	497	497
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	630	630
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,948	4,948
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	753	753
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	276	276
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10,993	10,993
42001300	PROTECTIVE COAT	SO YD	33	33
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	123,589	123,589
44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SO YD	2,190	2,190
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	100	100
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	460	460
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	760	760
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	870	870
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	90	90
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,182	1,182
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	3	3
63200310	GUARDRAIL REMOVAL	FOOT	150	150
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	42,330	42,330
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1,189	1,189
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	207,626	207,626
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	11,094	11,094
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	6,366	6,366
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	870	870
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	84,050	84,050
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1,189	1,189
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	103,588	103,588
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,322	5,322
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	450	450
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3,184	3,184
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	435	435
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,070	1,070
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,070	1,070
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	313	313
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	118	118
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	85	85
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	70	70
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	154.2	154.2
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
70102025	<i>TRAFFIC CONTROL AND PROTECTION, STANDARD 701606</i>	<i>L SUM</i>	<i>1</i>	<i>1</i>
① 20070604	<i>TRAINEES-TRAINING PROGRAM GRADUATE</i>	<i>HOURL</i>	<i>500</i>	<i>500</i>

\*SPECIALTY ITEMS  
① 0042

FILE NAME: I:\projects\11-2010\15-IL-RS-12-IL-11-0000000000.dwg  
PLOT SCALE: 1/4"=1'-0"  
PLOT DATE: 12/12/2012



DESIGNED	DJB
DRAWN	STANTEC
CHECKED	TMH
DATE	12/12/2012

REVISED	-
REVISED	-
REVISED	-
REVISED	-

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL ROUTE 120 ROADWAY RESURFACING			
SUMMARY OF QUANTITIES			
SCALE: 1/4"=1'-0"	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE. 333	SECTION 15-RS-12	COUNTY MCHENRY	TOTAL SHEETS 33	SHEET NO. 3
CONTRACT NO. 60N54			ILLINOIS FED. AID PROJECT	

Rev.