

URBAN  
100% STATE

URBAN  
100% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0014 STRUCTURE	0004 ROADWAY
20100500	TREE REMOVAL, ACRES	ACRES	0.4		0.4
20200100	EARTH EXCAVATION	CU YD	24		24
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5		5
20400800	FURNISHED EXCAVATION	CU YD	15	15	
20800150	TRENCH BACKFILL	CU YD	22		22
• 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	86		86
• 25000300	SEEDING, CLASS 3	ACRE	0.25		0.25
• 25100630	EROSION CONTROL BLANKET	SQ YD	86		86
28000400	PERIMETER EROSION BARRIER	FOOT	54		54
28000500	INLET AND PIPE PROTECTION	EACH	1		1
28000510	INLET FILTERS	EACH	1		1
28100105	STONE RIPRAP, CLASS A3	SQ YD	1000		1000
28200200	FILTER FABRIC	SQ YD	1000		1000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	587	71	516
40600300	AGGREGATE (PRIME COAT)	TON	1		1
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	49	49	
44003100	MEDIAN REMOVAL	SQ FT	2895		2895
44004250	PAVED SHOULDER REMOVAL	SQ YD	1049		1049
50102400	CONCRETE REMOVAL	CU YD	104.0	104.0	
50104650	SLOPE WALL REMOVAL	SQ YD	51	51	
50157300	PROTECTIVE SHIELD	SQ YD	379	379	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	138.8	138.8	
50300260	BRIDGE DECK GROOVING	SQ YD	1159	1159	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0014 STRUCTURE	0004 ROADWAY
50300300	PROTECTIVE COAT	SQ YD	243	243	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	20360	20360	
50800515	BAR SPLICERS	EACH	78	78	
51100100	SLOPE WALL 4 INCH	SQ YD	51	51	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	143	143	
52100520	ANCHOR BOLTS, 1"	EACH	80	80	
54002020	EXPANSION BOLTS, 3/4 INCH	EACH	342	342	
60100945	PIPE DRAINS 12"	FOOT	60		60
60500060	REMOVING INLETS	EACH	1		1
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	1		1
60900515	CONCRETE THRUST BLOCKS	EACH	2		2
• 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A; 6 FOOT POSTS	FOOT	50.0		50.0
• 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2		2
63200310	GUARDRAIL REMOVAL	FOOT	185		185
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6
67100100	MOBILIZATION	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20		20
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4194		4194
70400100	TEMPORARY CONCRETE BARRIER	FOOT	550		550
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550		550
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3		3
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3		3
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKERS	EACH	24		24

• DENOTES SPECIALTY ITEM



USER NAME - Plotted by Fred 076  
 PLOT SCALE - 2.0000" / IN.  
 PLOT DATE - 12/05/2012

DESIGNED - SEW  
 DRAWN - RK  
 CHECKED - SCW  
 DATE - 11/2011

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
IL 56 (BUTTERFIELD RD.) OVER IL 38 (ROOSEVELT RD.)

SCALE: N/A SHEET NO. 1 OF 2 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	JR-HB-1-1		30	3
CONTRACT NO. 60N77				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT