SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% State 0005					
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	11					
40600300	AGGREGATE (PRIME COAT)	TON	51	51					
40600400	MIXTURE FOR CRACKS, JOINTS, AND	TON	19	19					
	FLANGEWAYS								
40600827	POLYMERIZED LEVELING BINDER (MACHINE	TON	497	497					
	METHOD), IL-4.75, N50								
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT	SQ YD	254	254					
	JOINT								
40601005	HOT-MIX ASPHALT REPLACEMENT OVER	TON	26	26					
	PATCHES								
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX	TON	1471	1471					
	"D", N70								
42001300	PROTECTIVE COAT	SQ YD	95	95					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5	SQ FT	363	363					
	INCH								
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	6382	6382					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1977	1977					
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	4196	4196					

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% State 0005					
44000600	SIDEWALK REMOVAL	SQ FT	363	363					
44002207	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1	SQ YD	97	97					
	3/4"								
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES,	SQ YD	97	97					
	3"								
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	40	40					
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	48	48					
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	80	80					
60266600	VALVE BOXES TO BE ADJUSTED	EACH	16	16					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	28	28					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	17	17					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1					
	STANDARD 701501								
70102640	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1					
	STANDARD 701801								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	531	531					

FILE NAME = c:\pw_work\pwidot\bligomfsc\d0271842\D03912-sht-plan.dgn	USER NAME = Bligomfsc	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1000.000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/27/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NOBLE ST. (AUGUSTA BLVD. TO ERIE ST.)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 3 OF 7 SHEETS | STA. | TO STA.

OR RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	2011-086-RS	COOK	18	3
		CONTRACT NO. 60R13		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT