

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITY	URBAN	
				0014	100% STATE
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SO YD	20	20	
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SO YD	12	12	
Z0006014	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SO YD	2,130	2,130	
Z0012130	BRIDGE DECK SCARIFICATION, 3/4"	SO YD	2,130	2,130	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	43	43	
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	9	9	
Z0018051	DRAINAGE SCUPPERS TO BE ADJUSTED	EACH	11	11	
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	52	52	
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3	3	
* Z0033040	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	2	2	
* Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1	1	
* Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1	1	
Z0065700	SLOPE WALL REPAIR	SO YD	15	15	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	2	
XX004622	REMOVAL OF LUMINAIRE, SALVAGE	EACH	2	2	

15
SPECIALTY ITEM *

FILE NAME: 0160663-shc-500.dgn
PLOT DATE: 11/7/2013
PLOT SCALE: 100.0000 1/ IN.



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.
DRAWN - A.C.S.
CHECKED - M.P.
DATE - OCTOBER 9, 2012

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 53

SCALE: NONE SHEET NO. 4 OF 4 SHEETS STA. 114+15 TO STA. 123+02

F.A.P. RTE. 846	SECTION K-29-A-BR-1	COUNTY WILL	TOTAL SHEETS 55	SHEET NO. 6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60R63	