

FILE NAME = G:\Projects\ILLINOIS Department of Transportation\152 - Item 7 - Various Versions\Work Order No. 9 - US 12 at Old McHenry Rd\ACAD\Drawings\152-001.dwg
 SHT_PLAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0004	0021	0021			
				90% FEDERAL	90% FEDERAL	100% WAUCONDA			
				10% STATE	6.7% STATE	FIRE PROT. DEPT.			
				WIDENING & RESURFACING	3.3% COUNTY TRAF. SIGNALS	SAFETY (EVP)			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60500060	REMOVING INLETS	EACH	1	1					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3	3					
60608582	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	1,686	1,686					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	1,852	1,852					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	4	4					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6,076	6,076					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	146	146					

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	TR-TS	LAKE	58	6
			CONTRACT NO. 60T88	
ILLINOIS FED. AID PROJECT				

SCALE: N.T.S. SHEET 4 OF 8 SHEETS STA. TO STA.

Rev.