

NOTES

- TEMPORARY EROSION CONTROL SEEDING TO BE PROVIDED AT ALL ERODIBLE BARE EARTH AREAS, REFER TO SPECIAL PROVISIONS.
- 2. THE CONTRACTORS SHALL PROVIDE & MAINTAIN INLET PROTECTION AT ALL PROPOSED DRAINAGE STRUCTURES AND AT OTHER LOCATIONS DIRECTED BY THE ENGINEER AND/OR SHOWN ON THE PLANS. INLET PROTECTION SHALL BE PLACED BEFORE THE AREA INVOLVED HAS BEEN DISTURBED.
- 3. ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE STATE STANDARDS SPECIFICATION AND OF THE APPLICABLE STATE STANDARDS FOR THE ENTIRE DURATION OF THE CONTRACT OR UNTIL SUCH A TIME AS DIRECTED BY THE ENGINEER.
- 4. AT ANY AREA WHERE THERE IS NO PROPOSED GRADING, THE EXISTING GROUND COVER SHALL REMAIN.
- 5. EROSION CONTROL ITEMS ARE CONSIDERED TO BE HIGH PRIORITY
 ITEMS ON THIS CONTRACT. THE ENGINEER WILL IMPLEMENT ALL PROVISIONS OF
 THE SPECIFICATIONS NECESSARY TO ASSURE THAT EROSION CONTROL ITEMS
 ARE CONSTRUCTED AND MAINTAINED IN A TIMELY WAY. PERIMETER EROSION
 BARRIER SHALL BE INSTALLED PRIOR TO BEGINNING ANY CONSTRUCTION
 ACTIVITIES WILL WILL DESTRICT. ACTIVITIES WHICH WILL POTENTIALLY CREATE ERODABLE CONDITIONS.
- 6. THE EROSION CONTROL MEASURES SHOWN ARE BUT A GRAPHICAL REPRESENTATION OF SUGGESTED MEASURES, DEVIATIONS FROM THIS PLAN ARE TO BE EXPECTED PENDING JOBSITE INSPECTION BETWEEN THE CONTRACTOR AND THE DEPARTMENT.
- 7. THE CONTRACTOR WILL BE REQUIRED TO IMPLEMENT AND MAINTAIN SEDIMENT CONTROL MEASURES PRIOR TO STRIPPING EXISTING VEGETATION.

FILE NAME =	USER NAME = midyja	DESIGNED -	REVISED -		EROSION CONTROL PLAN	F.A.U.	SECTION	COUNTY	TOTAL SHEET
c:\pw_work\pwidot\midyja\d0267296\P118111	-sht-eros.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS		2845	3160A-RS&N	соок	27 12
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	HARWOOD AVE. (ELM ST. – DIXIE HWY)	CONTRACT NO. 60T99			
\$MODELNAME\$	PLOT DATE = 3/27/2013	DATE -	REVISED -		SCALE: 1"=50" SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT		