CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
				CONSTRUCTION CODE 0021																										
				TRAFFIC SIGNAL																										
				URBAN																										
89500400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH	1									1																		
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	5					3												1				1						
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	5										2						2			1								
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	66	7	1	1	1	2	1	1	1	6	1	2	1	3		3	3	3	6	12	1	2	2	1	2	1	1	1
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	178																178											
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	67	7	1	1	1	2	1	1	1	6	3	2	1	3	1	3	5	3	6	9	1	2	2	1	1	1	1	1
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	5										1				1		2			1								
X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1										1																	
X8600105	MASTER CONTROLLER (SPECIAL)	EACH	1										1																	
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	72	7	1	1	1	2	1	1	1	6	3	2	1	3	1	3	5	3	6	13	1	2	2	1	2	1	1	1
X8880015	PEDESTRIAN PUSH-BUTTON, NON-LATCHING	EACH	80	4										10	6	3		6	7	9	11	17		4	3					
X8803040	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	19	2								4				2		4					2					3	2	
X8803050	SIGNAL HEAD, LED, 3-FACE, 1-3 SECTION, 2-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	1									1																		
X8803060	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	2															2												

Δ Rev. 6-3-13

PREPARED BY:
CEMCON, Ltd.
Consulting Engineers, Land Surveyors & Planners
2280 White Oak Circle, Suite 100
Aurora, Illinois 60504-9675
Ph: 630.862.2100 Fax: 630.862.2199
E-Mail: cadd@cemcon.com Website: www.cemcon.com

FILE NAME = \MICROST\352105\ 08-SUMMARY.DGN	USER NAME = JGC	DESIGNED - BPT	REVISED -
		DRAWN - RDS/JGC	REVISED -
	PLOT SCALE = NOT TO SCALE	CHECKED - BPT	REVISED -
	PLOT DATE = X	DATE - 03-22-13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
(SHEET 5 OF 6)

SCALE: 1"=20' | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2012-084TS	DUPAGE	89	6
		CONTRACT NO. 60W02		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT