SUMMARY OF QUANTITIES																			
		LOCATION OF WORK		1, 3, 4, 5, 9, 10, 13	12	18-33, 35, 38, 39, 41, 43, 47, 50, 52-55, 57-59, 61, 62, 64, 67, 68, 70-72, 80, 82, 87	45, 46, 63, 65, 74, 89	51, 69, 79, 88	14	81	76	2	34	77	78	16, 17, 40, 42, 44, 48, 49, 60, 66	4, 10, 12	21
		FUNDING BREAKDOWNS		95% STATE 5% VILLAGE OF BOLINGBROOK	96.7% STATE 3.3% VILLAGE OF BOLINGBROOK	95% STATE 5% CITY OF JOLIET	96.7% STATE 3.3% CITY OF JOLIET	97.5% STATE 2.5% CITY OF JOLIET	92.5% STATE 5% WILL COUNTY 2.5% CITY OF JOLIET	95% STATE 5% WILL COUNTY	96.7% STATE 3.3% TROY TOWNSHIP	95% STATE 5% PRO LOGISTICS	95% STATE 5% SIMON PROPERTY GROUP	95% STATE 5% CATERPILLAR, INC.	95% STATE 5% CENTER POINT PROPERTIES	100% STATE	100% VILLAGE OF BOLINGBROOK	100% CITY OF JOLIET
				TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS	TRAF. SIGNALS
		TYPE		0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021
CODE NO.	ITEM	UNIT	TOTAL	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2			2												
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	3			2									1			
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	16			2	1		2	2			2		3	4		
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	18			2	3	4	2	4	1		2					
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5			1	1				1					2		
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	7					4		2	1							
88030310	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1												1			
88055150	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1											1				
88060110	COMBINATION SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION OPTICALLY PROGRAMMED, 1-3 SECTION, BRACKET MOUNTED	EACH	1											1				
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	24	20				4										
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	21	11				2	4	4								
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	71			13	6	8	8	8	4		8	4	4	8		

12

NO.	INTERSECTION
1.	IL 53 (BOLINGBROOK DR) AT BRIARCLIFF ROAD
2.	JOLIET ROAD AT INTERNATIONALE PARKWAY
3.	IL 53 (BOLINGBROOK DR) AT BOUGHTON ROAD
4.	IL 53 (BOLINGBROOK DR) AT ROBINHOOD WAY
5.	IL 53 (BOLINGBROOK DR) AT LEE LANE / NORTHRIDGE AVENUE
9.	IL 53 (BOLINGBROOK DR) AT CROSSROADS PARKWAY
10.	IL 53 (BOLINGBROOK DR) AT BEACON RIDGE DR
12.	IL 53 (BOLINGBROOK DR) AT LILY CACHE LANE
13.	IL 53 (BOLINGBROOK DR) AT OLD CHICAGO DRIVE
14.	BRIGGS STREET AT WASHINGTON STREET
16.	I-80 NORTH RAMP AT HOUBOLT ROAD
17.	I-80 SOUTH RAMP AT HOUBOLT ROAD
18.	IL 171 (COLLINS ST) AT COLUMBIA STREET
19.	IL 171 (COLLINS ST) AT OHIO STREET
20.	IL 53 (BROADWAY ST) AT INGALLS AVENUE
21.	IL 53 (BROADWAY ST) AT RUBY STREET
22.	IL 53 (OTTAWA ST) AT CLINTON STREET
23.	IL 53 (OTTAWA ST) AT WASHINGTON STREET
24.	IL 53 (SCOTT ST) AT CLINTON STREET
25.	IL 53 (SCOTT ST) AT VAN BUREN STREET

NO.	INTERSECTION
26.	IL 53 (SCOTT ST) AT CLAY STREET
27.	IL 53 (SCOTT ST) AT JACKSON STREET
28.	IL 53 (SCOTT ST) AT OHIO STREET
29.	IL 7 (LARKIN AV) AT BLACK ROAD
30.	IL 7 (LARKIN AV) AT GLENWOOD AVENUE
31.	IL 7 (LARKIN AV) AT INGALLS AVENUE
32.	IL 7 (LARKIN AV) AT McDONOUGH STREET
33.	IL 7 (LARKIN AV) AT SAM'S CLUB / WAL-MART ENTRANCE
34.	IL 7 (LARKIN AV) AT NORTHRIDGE PLAZA
35.	IL 7 (THEORDORE ST) AT RAYNOR AVENUE
38.	U.S. 30 (CASS ST) AT CHICAGO STREET
39.	U.S. 30 (CASS ST) AT HENDERSON AVENUE
40.	U.S. 30 (CASS ST) AT IL 53 (OTTAWA ST)
41.	U.S. 30 (CASS ST) AT JOLIET STREET
42.	U.S. 30 (CASS ST) AT U.S. 6 (COLLINS ST)
43.	U.S. 30 (CASS ST) AT EASTERN AVENUE
44.	U.S. 30 (CASS ST) AT IL 53 (SCOTT ST)
45.	U.S. 30 (PLAINFIELD RD) AT RAYNOR AVENUE / BLACK ROAD
46.	U.S. 30 (JEFFERSON ST) AT CHICAGO STREET
47.	U.S. 30 (JEFFERSON ST) AT HICKORY STREET

NO.	INTERSECTION
48.	U.S. 30 (JEFFERSON ST) AT IL 53 (OTTAWA ST)
49.	U.S. 30 (JEFFERSON ST) AT IL 53 (SCOTT ST)
50.	U.S. 30 (JEFFERSON ST) AT JOLIET STREET
51.	U.S. 30 (JEFFERSON ST) AT U.S. 30 (CENTER ST)
52.	U.S. 30 (JEFFERSON ST) AT EASTERN AVENUE
53.	U.S. 30 (LINCOLN HWY / CASS ST) AT WALNUT STREET
54.	U.S. 30 (PLAINFIELD RD) AT INGALLS AVENUE
55.	U.S. 30 (PLAINFIELD RD) AT HENNEPIN DRIVE
57.	U.S. 30 (PLAINFIELD RD) AT ESSINGTON ROAD / MALL LOOP DRIVE
58.	U.S. 30 (PLAINFIELD RD) AT VOYAGER DRIVE
59.	U.S. 30 (WESTERN AV) AT HICKORY STREET
60.	U.S. 30 (WESTERN AV) AT U.S. 30 (CENTER ST)
61.	U.S. 52 (JEFFERSON ST) AT BARNEY DRIVE
62.	U.S. 52 (JEFFERSON ST) AT CATERPILLAR DRIVE
63.	U.S. 52 (JEFFERSON ST) AT ESSINGTON ROAD
64.	U.S. 52 (JEFFERSON ST) AT HAMMES AVENUE
65.	U.S. 52 (JEFFERSON ST) AT HOUBOLT ROAD
66.	U.S. 52 (JEFFERSON ST) AT IL 7 (LARKIN AV)
67.	U.S. 52 (JEFFERSON ST) AT 129TH INFANTRY DRIVE
68.	U.S. 52 (JEFFERSON ST) AT MIDLAND AVENUE

NO.	INTERSECTION
69.	U.S. 52 (JEFFERSON ST) AT RAYNOR AVENUE
70.	U.S. 52 (JEFFERSON ST) AT REED STREET
71.	U.S. 52 (JEFFERSON ST) AT SPRINGFIELD AVENUE
72.	U.S. 52 (JEFFERSON ST) AT STRYKER AVENUE / WOODLAWN AVENUE
74.	U.S. 6 (CHANNAHON RD) AT HOLLYWOOD BOULEVARD
75.	U.S. 6 - U.S 30 (COLLINS AV) AT JOLIET HIGH SCHOOL
76.	U.S. 6 (CHANNAHON RD) AT EMPRESS ROAD / BUSH PARKWAY
77.	U.S. 6 (CHANNAHON RD) AT CATERPILLAR EAST DRIVE
78.	U.S. 6 (CHANNAHON RD) AT CATERPILLAR WEST DRIVE / JOHNS MANVILLE DRIVE
79.	U.S. 6 - IL 171 (COLLINS ST) AT U.S. 6 (JACKSON ST)
80.	U.S. 6 (JACKSON ST) AT HENDERSON AVENUE
81.	U.S. 6 (MAPLE RD) AT BRIGGS STREET / FERNWOOD AVENUE
82.	U.S 6 (MAPLE RD) AT WALNUT AVENUE / DRAPER AVENUE
87.	U.S. 6 - U.S. 30 (JEFFERSON ST) AT RICHARDS STREET AND RICHARDS STREET AT WASHINGTON STREET
88.	U.S. 6 - U.S. 52 (McDONOUGH ST) AT IL 53 (CHICAGO ST)
89.	U.S. 6 (CHANNAHON RD) AT McCLINTOCK ROAD

FILE NAME = 60W21-88E-SOO.dgn	USER NAME = g-hutter	DESIGNED - JRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 2 OF 3)	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - GW3	REVISED -			VAR	2013-003-I	WILL	89	6
	PLOT SCALE = 1:1	CHECKED - KLB	REVISED -					CONTRACT NO. 60W21		
$MODELNAME$	PLOT DATE = 3/27/2013	DATE - 03-28-13	REVISED -		SCALE: NONE SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			