CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 1	2	~~3~~	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
				TRAFFIC SIGNAL																						
				0021																						
				URBAN																						
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		1																1					
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	6		3											2					1					
88055150	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	2																						
88055160	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2	2																						
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	42				4				6					24	2	2	4				~~8~~			
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	22	5							2			4		6	2	2	1							
88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2																						
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	18	4	6																8					
88800100	PEDESTRIAN PUSH-BUTTON	EACH	20								2					16			2				~~8~~			
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	44	9	2		1	3	1	1	2	1	1	1	1	6	3	2	3	1	1	2	~~1~~	~~2~~	2	1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	25	4	1		1		1		2		1	1	1	5	2	1	2	1	1	1	~~1~~			
X8620050	UNINTERRUPTABLE POWER SUPPLY, GROUND MOUNTED	EACH	1	1																						
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	41	8	2		1	3	1	1	2	1	1	1	1	5	3	1	3	1	1	2	~~1~~	~~2~~	2	1
X8803038	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED, RETROFIT	EACH	1	1																						

14

Rex.

FILE NAME =	USER NAME = rosadovazquezjy	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 3 OF 4)	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw_work\pwidot\rosadovazquezjy\d0336478\D121713-sht-TS.dgn		DRAWN -	REVISED -			VAR	2013-004-1	WILL	58	7
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -					CONTRACT NO. 60W22		
$MODELNAME$	PLOT DATE = 3/29/2013	DATE -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			