



**ITEM LEGEND (PAY ITEM #)**

- ① COMBINATION CURB AND GUTTER REMOVAL (44000500)
- ② CURB REMOVAL (44000300)
- ③ CONCRETE RETAINING WALL REMOVAL (Z0075498)
- ④ REMOVE BIKE RACK (X0327146)
- ⑤ REMOVE BENCH (X0327149)
- ⑥ GAS LIGHT REMOVAL (XX008662)

**LEGEND (PAY ITEM #)**

- BRICK SIDEWALK REMOVAL (X0326864)
- HOT-MIX ASPHALT SURFACE REMOVAL (2") (44000157)
- PAVEMENT REMOVAL (HOT MIX ASPHALT) (44000100)
- SIDEWALK REMOVAL (44000600)
- COMBINATION CURB AND GUTTER/CURB REMOVAL
- LIMIT OF CONSTRUCTION
- TREE REMOVAL
- ITEM TO BE REMOVED

NOTE:  
 THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENTAL FIRM WITH AT LEAST FIVE (5) DOCUMENTED LEAKING UNDERGROUND STORAGE TANK CLEANUPS OR THAT IS PRE-QUALIFIED IN HAZARDOUS WASTE BY DEPARTMENT TO REMEDIATE THE SOIL CONTAMINATION AND MONITOR FOR WORKER PROTECTION.

NOTE:  
 1. SEE LIGHTING REMOVAL PLAN (SHEET 50) FOR EXISTING ELECTRIC HANDHOLE AND LIGHT POLE REMOVAL.  
 2. SEE SHEETS #31-32 FOR SIGNING REMOVAL/RELOCATION.

FILE NAME = 3737.16REM02.DGN	USER NAME = bkravets	DESIGNED - BS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REMOVAL PLAN PROSPECT AVENUE</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			10-00149-00-LS	COOK	69	13	
		CHECKED - JCK	REVISED -			<b>CONTRACT NO. 63723</b>				
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
				SCALE: 1"=20'		SHEET 2 OF 2		SHEETS: STA. 100+00 TO STA. 105+97		