


LEGEND

- AREA UNDER CONSTRUCTION
- TEMPORARY DRUM WITH STEADY BURN BI-DIRECTIONAL LIGHT
- BARRICADE
- TRAFFIC FLOW DIRECTION

NOTE

1. BEFORE ANY CONSTRUCTION ACTIVITIES IS STARTED ALL NECESSARY TEMPORARY TRAFFIC CONTROL SIGNS AND MARKINGS SHALL BE IN PLACE.
2. ALL TEMPORARY TRAFFIC CONTROL DEVICES SHALL BE REMOVED AS SOON AS PRACTICAL WHEN THEY ARE NO LONGER NEEDED.
3. WHEN WORK IS SUSPENDED FOR SHORT PERIODS OF TIME, TEMPORARY TRAFFIC CONTROL DEVICES THAT ARE NO LONGER APPROPRIATE SHALL BE REMOVED OR COVERED.
4. DURING CONSTRUCTION THE CONTRACTOR SHALL PROVIDE ACCESS TO ADJUTING PROPERTIES. AT NO TIME SHALL ACCESS BE DENIED TO HOMES/BUSINESSES SURROUNDING THE SITE.
5. SIGN LAYOUT AND SPACING SHALL BE IN ACCORDANCE WITH THE CURRENT IDOT STANDARD DRAWINGS AND THE "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES." SEE HIGHWAY STANDARDS FOR ADDITIONAL INFORMATION.
6. THIS WORK SHALL BE INCLUDED IN THE LUMP SUM COST FOR TRAFFIC CONTROL AND PROTECTION (SPECIAL)



FILE NAME = 3737.16MT01.DGN	USER NAME = bkravets	DESIGNED - BS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC PLAN SUMMIT AVENUE - STAGE 1			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:20	DRAWN -	REVISED -		SCALE: 1"=20'	SHEET 1 OF 3 SHEETS	STA. 199+70 TO STA. 208+44	10-00149-00-LS	COOK	69	20	
	PLOT DATE = 4/8/2013	CHECKED - JCK	REVISED -					CONTRACT NO. 63723				
		DATE -	REVISED -					ILLINOIS FED. AID PROJECT				