

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUAN.	STU FUNDS			
					0004	0021	0031	0042
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	203			203	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	118			118	
	20200100	EARTH EXCAVATION	CU YD	7329	7329			
	20200200	ROCK EXCAVATION	CU YD	100	100			
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100			
	20800150	TRENCH BACKFILL	CU YD	380	380			
	21101815	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10555	10555			
	21301048	EXPLORATION TRENCH 48" DEPTH	FOOT	500	500			
	21400100	GRADING AND SHAPING DITCHES	FOOT	20	20			
*	25000210	SEEDING, CLASS 2A	ACRE	2.25			2.25	
*	25000310	SEEDING, CLASS 4	ACRE	0.25			0.25	
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	196			196	
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	196			196	
*	25000800	POTASSIUM FERTILIZER NUTRIENT	POUND	196			196	
*	25100830	EROSION CONTROL BLANKET	SQ YD	10555	10555			
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200			
*	28000400	PERIMETER EROSION BARRIER	FOOT	4694	4694			
	28000500	INLET AND PIPE PROTECTION	EACH	5	5			
	28100101	STONE RIPRAP, CLASS A1	SQ YD	19	19			
	28100107	STONE RIPRAP, CLASS A4	SQ YD	19	19			
	28200200	FILTER FABRIC	SQ YD	19	19			
	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	100	100			
	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	7255	7255			
	35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	3506	3506			

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUAN.	STU FUNDS			
					0004	0021	0031	0042
	35600718	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/2"	SQ YD	530	530			
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24560	24560			
	40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N60	TON	726	726			
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	258	258			
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MX" F", N90	TON	1695	1695			
	40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	866	866			
	40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	1576	1576			
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	89		89		
	42400800	DETECTABLE WARNINGS	SQ FT	16		16		
	44000100	PAVEMENT REMOVAL	SQ YD	3466	3466			
	44000189	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	11338	11338			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	568	568			
	44000600	SIDEWALK REMOVAL	SQ FT	89	89			
	44003100	MEDIAN REMOVAL	SQ FT	67	67			
	44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	50	50			
	44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	250	250			
	44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	100	100			
	48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	1209	1209			
	48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	1918	1918			
	50105220	PIPE CULVERT REMOVAL	FOOT	61	61			
	50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	6	6			
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 16"	EACH	1	1			
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1			

FILE NAME = 08981\_02-QUAN-01 - IDOT P01

USER NAME =	DESIGNED -- WPD	REVISED -- 12-13-12 - SILT FENCE
	CHECKED -- PB	REVISED -- 01-15-13
PLOT SCALE =	DRAWN -- RG	REVISED --
PLOT DATE = 02-28-13	CHECKED -- AG	REVISED --

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

INTERSECTION IMPROVEMENT  
IL RTE 53 AT MATERIAL ROAD  
SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 4 OF 64 SHEETS STA. TO STA.

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	09-00055-00-CH	WILL	64	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(829)			CONTRACT NO. 63753	