

SUMMARY OF QUANTITIES				CONS TYPE CODE	
CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0028 BICYCLE/PED TRAILS	0042 TRAINEES
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2887	2887	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	424	424	
20101000	TEMPORARY FENCE	FOOT	7690	7690	
20101100	TREE TRUNK PROTECTION	EACH	111	111	
20101200	TREE ROOT PRUNING	EACH	41	41	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	8	8	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	2	2	
20200100	EARTH EXCAVATION	CU YD	1049	1049	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1624	1624	
20400800	FURNISHED EXCAVATION	CU YD	500	500	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1000	1000	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	439	439	
25100127	MULCH, METHOD 3A	ACRE	0.5	0.5	
25200110	SODDING, SALT TOLERANT	SQ YD	876	876	
25200200	SUPPLEMENTAL WATERING	UNIT	14	14	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200	
28000400	PERIMETER EROSION BARRIER	FOOT	3977	3977	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28000510	INLET FILTERS	EACH	13	13	
28100105	STONE RIPRAP, CLASS A3	SQ YD	24	24	
28200200	FILTER FABRIC	SQ YD	24	24	
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	500	500	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	5806	5806	
40609335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NSO	TON	820	820	
42001300	PROTECTIVE COAT	SQ YD	318	318	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2658	2658	
42400800	DETECTABLE WARNINGS	SQ FT	225	225	
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	128	128	
44000600	SIDEWALK REMOVAL	SQ FT	590	590	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	289	289	
542A1057	PIPE CULVERTS, CLASS A, TYPE 2 12"	FOOT	18	18	
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	20	20	
54210182	PIPE ELBOW, 12"	EACH	1	1	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
54215547	METAL END SECTIONS 12"	EACH	2	2	
60608250	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.06	FOOT	16	16	
65409600	CHAIN LINK GATES, 8' X 16' DOUBLE	EACH	1	1	
66600205	REERECTING RIGHT OF WAY MARKERS	EACH	2	2	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	400	400	
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	
67100100	MOBILIZATION	L SUM	1	1	
72000100	SIGN PANEL - TYPE 1	SQ FT	43	43	
73000100	WOOD SIGN SUPPORT	FOOT	108	108	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3449	3449	

SUMMARY OF QUANTITIES				CONS TYPE CODE	
CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0028 BICYCLE/PED TRAILS	0042 TRAINEES
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	416	416	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	480	480	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	80	80	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	305	305	
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	64	64	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
87300010	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	8	8	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1110	1110	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1250	1250	
87500500	TRAFFIC SIGNAL POST, 10 FT.	EACH	1	1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	16	
87900200	DRILL EXISTING HANDHOLE	EACH	4	4	
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	1	
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	6	6	
89502200	MODIFY EXISTING CONTROLLER	EACH	1	1	
C2002048	SHRUB, CORYLUS AMERICANA (AMERICAN FILBERT), 4' HEIGHT, BALLED AND BURLAPPED	EACH	8	8	
C2003360	SHRUB, HAMAMELIS VIRGINIANA (COMMON WITCHHAZEL), 5' HEIGHT, BALLED AND BURLAPPED	EACH	4	4	
C2005348	SHRUB, PRUNUS AMERICANA (AMERICAN PLUM), 4' HEIGHT, BALLED AND BURLAPPED	EACH	7	7	
C2012448	SHRUB, VIBURNUM LENTAGO (NANNYBERRY VIBURNUM), 4' HEIGHT, BALLED AND BURLAPPED	EACH	8	8	
C2012748	SHRUB, VIBURNUM PRUNIFOLIUM (BLACKHAW VIBURNUM), 4' HEIGHT, BALLED AND BURLAPPED	EACH	3	3	
K1001988	IRRIGATION SYSTEM SPECIAL	L SUM	1	1	
X0321322	DROP GATE	EACH	3	3	
X0326862	STRUCTURES TO BE ADJUSTED	EACH	7	7	
X2511630	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	3000	3000	
X2800302	TEMPORARY DITCH CHECKS (SPECIAL)	FOOT	196	196	
X2800400	PERIMETER EROSION BARRIER, SPECIAL	FOOT	1336	1336	
X6061700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	FOOT	112	112	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
X7240505	RELOCATE SIGN PANEL AND POST	EACH	6	6	
X8760055	PEDESTRIAN PUSH-BUTTON POST, TYPE A	EACH	3	3	
XX008287	BOARDWALK STRUCTURE	SQ FT	5955	5955	
Z0007510	ENGINEERED BARRIER	SQ YD	1031	1031	
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	224	224	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0022800	FENCE REMOVAL	FOOT	16	16	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
Z0069200	STONE RETAINING WALL	SQ FT	1075	1075	
Z0076600	TRAINEES	HOUR	500		500
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500		500

* DENOTES SPECIAL PROVISION ITEM
 Δ DENOTES SPECIALTY ITEM

6575 W. Higgins Road, Suite 600
 Rosemont, Illinois 60018
 (847) 823-0500



USER NAME = mthomas	DESIGNED - MBT	REVISED -
PILOT SCALE = 3"	DRAWN - PWN	REVISED -
PLOT DATE = 4/11/2013	CHECKED - MEK	REVISED -
	DATE - 4/11/13	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

LAKE COOK ROAD/NORTH BRANCH BICYCLE TRAIL EXTENSION
 SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3726	10-F3000-22-BT	COOK/LAKE	89	3
CONTRACT NO. 63781				