

FUNDS: 80% FEDERAL (HBP), 20% LOCAL
CONSTRUCTION TYPE CODE 0014

PAY CODE	DESCRIPTION	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (8 TO 15 UNITS DIAMETER)	UNIT	40
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	40
20200100	EARTH EXCAVATION	CU YD	180
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100
20300100	CHANNEL EXCAVATION	CU YD	200
20400800	FURNISHED EXCAVATION	CU YD	50
20800150	TRENCH BACKFILL	CU YD	60
* 21101815	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	670
* 25000210	SEEDING, CLASS 2A	ACRE	0.15
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15
25100630	EROSION CONTROL BLANKET	SQ YD	670
* 25200200	SUPPLEMENTAL WATERING	UNIT	10
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	15
28000400	PERIMETER EROSION BARRIER	FOOT	450
28000510	INLET FILTERS	EACH	5
28100107	STONE RIPRAP, CLASS A4	SQ YD	200
28200200	FILTER FABRIC	SQ YD	200
*** 30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	275
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	14
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	516
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	869
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	740
40600300	AGGREGATE (PRIME COAT)	TON	3

FUNDS: 80% FEDERAL (HBP), 20% LOCAL
CONSTRUCTION TYPE CODE 0014

PAY CODE	DESCRIPTION	UNIT	TOTAL QUANTITY
40800625	LEVELING BINDER (MACHINE METHOD), N50	TON	11
40803080	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N50	TON	177
40803335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	381
42001300	PROTECTIVE COAT	SQ YD	123
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	145
42400800	DETECTABLE WARNINGS	SQ FT	10
44000100	PAVEMENT REMOVAL	SQ YD	971
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1780
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	243
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	225
44000300	CURB REMOVAL	FOOT	33
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	462
44000600	SIDEWALK REMOVAL	SQ FT	130
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	10
50200100	STRUCTURE EXCAVATION	CU YD	55
50300225	CONCRETE STRUCTURES	CU YD	18
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21
50300280	BRIDGE DECK GROOVING	SQ YD	163
50300300	PROTECTIVE COAT	SQ YD	290
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	2052
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8450
* 50900105	ALUMINUM RAILING, TYPE L	FOOT	61
51500100	NAME PLATES	EACH	1
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1

* SPECIALTY ITEMS
** CONSTRUCTION TYPE CODE 0042
*** SPECIAL PROVISION REQUIRED

FILE NAME =
H:\ILLINOIS\2014\10-00101-00-BR\CONTRACT\10-00101-00-BR.DWG

USER NAME = prazolan
PLOT SCALE = 20
PLOT DATE = 2/22/2013

DESIGNED = JA
DRAWN = PDR
CHECKED = JCS
DATE = 11/30/12

REVISED =
REVISED =
REVISED =
REVISED =

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CARRIAGE WAY DRIVE
SUMMARY OF QUANTITIES
SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00101-00-BR	COOK	34	3
CONTRACT NO. 63787				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				