

CODED PAY ITEM #	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0028 PEDESTRIAN FACILITIES
28100203	STONE RIPRAP, CLASS A2	TON	523	523
28200200	FILTER FABRIC	SQ YD	42	42
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1,256	1,256
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	89	89
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	2,282	2,282
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,800	2,800
40600300	AGGREGATE (PRIME COAT)	TON	41	41
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	84	84
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	256	256
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,172	2,172
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	1,076	1,076
42001300	PROTECTIVE COAT	SQ YD	199	199
44000100	PAVEMENT REMOVAL	SQ YD	2,417	2,417
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	19,389	19,389
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	703	703
44004250	PAVED SHOULDER REMOVAL	SQ YD	390	390
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,288	1,288
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	313	313
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	3	3
50300225	CONCRETE STRUCTURES	CU YD	742.6	742.6
50300254	RUBBED FINISH	SQ FT	5,227	5,227
50700105	TREATED TIMBER	F.B.M.	4,610	4,610
50700305	HARDWARE	POUND	260	260
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	94,700	94,700

• SPECIALTY ITEMS

FILE NAME: N:\PROJECTS\0220087\01\1\Rollins\Design\Misc\Sheets\0220087\_01\_1000.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4614

USER NAME = jk,jellman	DESIGNED -	REVISED -
PLOT SCALE = 2.0000 "/>		
PLOT DATE = 4/8/2013	DATE = 4/8/2013	REVISED -

**MILLENNIUM TRAIL  
LAKE COUNTY FOREST PRESERVES**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
181	12-F3000-01-BT	LAKE	118	5
CONTRACT NO. 63807				
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				