


SCHEDULE OF EARTH QUANTITIES - ROLLINS ROAD (PRE-STAGE)									
STATION	AREA (SQ FT)				VOLUME (CU YD)				
	TOPSOIL CUT	TOPSOIL FILL	EARTH EX	EMBANKMENT	TOPSOIL CUT	TOPSOIL FILL	EARTH EX	EARTH EX (15% SHRINKAGE)	EMBANKMENT
357+41.00	0.0	0.0	0.0	0.0	0.0	0.6	4.6	3.9	0.0
358+50.00	0.0	0.3	2.3	0.0	1.6	0.8	4.4	3.7	1.3
359+00.00	1.7	0.6	2.4	1.4	4.3	1.6	4.4	3.7	3.9
359+50.00	2.9	1.1	2.3	2.8	6.9	2.9	4.4	3.7	6.9
360+00.00	4.6	2.0	2.4	4.7	8.5	3.4	4.4	3.7	9.7
360+50.00	4.6	1.7	2.4	5.8	10.9	4.6	4.2	3.6	15.8
361+00.00	7.2	3.3	2.1	11.3	17.1	8.2	3.9	3.3	28.6
361+50.00	11.3	5.6	2.1	19.6	20.6	10.1	4.4	3.7	28.1
362+00.00	10.9	5.3	2.7	10.8	16.9	7.7	5.2	4.4	17.2
362+50.00	7.3	3.0	2.9	7.8	14.7	6.3	5.5	4.7	17.8
363+00.00	8.6	3.8	3.0	11.4	15.5	6.7	5.6	4.8	19.3
363+50.00	8.1	3.4	3.1	9.4	15.1	6.1	5.0	4.3	17.8
364+00.00	8.2	3.2	2.3	9.8	14.4	5.3	4.5	3.8	14.6
364+50.00	7.3	2.5	2.6	6.0	13.5	4.8	5.0	4.3	10.8
365+00.00	7.3	2.7	2.8	5.7	10.6	3.1	5.2	4.4	7.3
365+50.00	4.1	0.6	2.8	2.2	8.7	1.9	5.1	4.3	6.7
366+00.00	5.3	1.5	2.7	5.0	10.1	3.1	5.4	4.6	8.1
366+50.00	5.6	1.8	3.1	3.8	9.3	2.8	6.2	5.3	4.9
367+00.00	4.4	1.2	3.6	1.5	13.3	5.1	23.0	19.6	1.4
367+50.00	10.0	4.3	21.2	0.0	18.4	8.2	43.1	36.6	0.8
368+00.00	9.9	4.6	25.3	0.9	4.0	1.9	10.9	9.3	0.4
368+11.00	9.8	4.6	28.0	0.9	14.7	6.9	43.2	36.7	1.3
368+50.00	10.6	5.0	31.8	0.9	21.3	10.3	65.5	55.7	1.6
369+00.00	12.4	6.1	38.9	0.8	22.8	11.1	73.2	62.2	1.6
369+50.00	12.2	5.9	40.2	0.9	23.4	11.4	80.4	68.3	1.7
370+00.00	13.1	6.4	46.6	0.9	24.0	12.2	86.2	73.3	1.7
370+50.00	12.8	6.8	46.5	0.9	22.5	12.4	79.5	67.6	1.7
371+00.00	11.5	6.6	39.4	0.9	18.9	11.2	63.3	53.8	1.7
371+50.00	8.9	5.5	29.0	0.9	16.1	10.6	52.1	44.3	1.7
372+00.00	8.5	6.0	27.3	0.9	12.4	9.6	38.9	33.1	1.8
372+50.00	4.9	4.4	14.7	1.0	4.5	4.1	13.6	11.6	0.9
373+00.00	0.0	0.0	0.0	0.0					
SUBTOTAL					415.0	195.0	760.3	646.3	237.1

SCHEDULE OF EARTH QUANTITIES - ROLLINS ROAD (FINAL)									
STATION	AREA (SQ FT)				VOLUME (CU YD)				
	TOPSOIL CUT	TOPSOIL FILL	EARTH EX	EMBANKMENT	TOPSOIL CUT	TOPSOIL FILL	EARTH EX	EARTH EX (15% SHRINKAGE)	EMBANKMENT
357+41.00	0.0	0.0	0.0	0.0	1.0	0.2	3.2	2.7	0.4
358+50.00	0.5	0.1	1.6	0.2	1.1	0.6	3.6	3.1	0.4
359+00.00	0.7	0.6	2.3	0.2	1.7	2.1	4.4	3.7	0.4
359+50.00	1.1	1.7	2.4	0.2	2.9	4.4	5.7	4.8	0.4
360+00.00	2.0	3.0	3.8	0.2	3.4	5.6	7.2	6.1	0.4
360+50.00	1.7	3.1	4.0	0.2	4.6	7.4	10.3	8.8	0.4
361+00.00	3.3	4.9	7.1	0.2	8.3	11.6	21.9	18.6	0.4
361+50.00	5.7	7.6	16.5	0.2	10.2	13.8	28.6	24.3	0.4
362+00.00	5.3	7.3	14.4	0.2	7.7	11.3	18.4	15.6	0.5
362+50.00	3.0	4.9	5.5	0.3	6.4	9.8	12.4	10.5	0.6
363+00.00	3.9	5.7	7.9	0.4	6.8	10.1	13.1	11.1	1.0
363+50.00	3.4	5.2	6.3	0.7	6.1	9.4	10.9	9.3	1.4
364+00.00	3.2	4.9	5.5	0.8	5.3	8.5	8.7	7.4	1.8
364+50.00	2.5	4.3	3.9	1.1	4.8	8.1	7.7	6.5	2.1
365+00.00	2.7	4.4	4.4	1.2	3.1	6.2	5.2	4.4	2.2
365+50.00	0.6	2.3	1.2	1.2	1.9	5.0	2.9	2.5	2.2
366+00.00	1.5	3.1	1.9	1.2	3.1	5.9	4.0	3.4	2.3
366+50.00	1.8	3.3	2.4	1.3	2.8	5.4	3.5	3.0	2.3
367+00.00	1.2	2.5	1.4	1.2	9.5	11.2	11.4	9.7	5.3
367+29.00	16.4	18.3	19.9	8.7	0.0	0.0	0.0	0.0	0.0
367+29.00	16.4	18.3	80.7	8.7	8.1	9.6	32.0	27.2	8.6
367+50.00	4.4	6.3	1.6	13.4	20.9	22.6	64.3	54.7	49.1
368+00.00	18.2	18.1	67.8	39.6	7.5	7.4	27.7	23.5	16.7
368+11.00	18.4	18.3	68.1	42.4	26.7	26.3	97.5	82.9	61.0
368+50.00	18.5	18.1	66.9	42.0	22.9	24.4	121.9	103.6	81.3
369+00.00	6.2	8.3	64.7	45.8	1.1	1.4	11.9	10.1	7.2
369+05.00	5.3	7.3	64.1	31.6	0.0	0.0	0.0	0.0	0.0
369+05.00	5.3	7.3	0.8	31.6	9.4	12.9	1.3	1.1	62.7
369+50.00	6.0	8.2	0.8	43.6	11.5	15.6	1.5	1.3	85.1
370+00.00	6.4	8.7	0.8	48.3	12.2	16.0	1.5	1.3	91.5
370+50.00	6.8	8.6	0.8	50.5	12.4	15.1	1.5	1.3	88.2
371+00.00	6.6	7.7	0.8	44.8	11.3	12.6	1.5	1.3	70.7
371+50.00	5.6	5.9	0.8	31.6	10.7	10.6	1.5	1.3	57.9
372+00.00	6.0	5.6	0.8	30.9	9.6	8.1	2.3	2.0	43.3
372+50.00	4.4	3.2	1.7	15.9	4.1	3.0	1.6	1.4	14.7
373+00.00	0.0	0.0	0.0	0.0					
SUBTOTAL					259.1	322.2	551.1	468.4	762.9

FILE NAME = H:\PROJ\0820097\01\Rollins\Design\Misc\Sheets\0820097\_01\_schedule01.dgn



**Ciorba Group, Inc.**  
 CONSULTING ENGINEERS  
 5507 North Cumberland Avenue, Suite 402  
 Chicago, Illinois 60656  
 Tel. 773.775.4009 Fax 773.775.4014

USER NAME = jgellman	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / 1" =	DRAWN -	REVISED -
PLOT DATE = 4/8/2013	CHECKED -	REVISED -
	DATE = 4/8/2013	REVISED -

**MILLENNIUM TRAIL  
 LAKE COUNTY FOREST PRESERVES**

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.
--------	---------------------	--------------

F.A.D. RTE. 181	SECTION 12-F3000-01-BT	COUNTY LAKE	TOTAL SHEETS 118	SHEET NO. 13
CONTRACT NO. 63807				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				