

SCHEDULE OF EARTH QUANTITIES - MILLENNIUM TRAIL (EXISTING ALIGNMENT)									
STATION	AREA (SQ FT)				VOLUME (CU YD)				
	TOPSOIL CUT	TOPSOIL FILL	EARTH EX	EMBANKMENT	TOPSOIL CUT	TOPSOIL FILL	EARTH EX	EARTH EX (15% SHRINKAGE)	EMBANKMENT
311+00.00	9.1	6.0	3.4	1.3					
					27.6	18.0	22.7	19.3	11.6
311+50.00	20.7	13.4	21.1	11.2					
					54.9	36.0	20.3	17.3	39.5
312+00.00	38.6	25.5	0.8	31.5					
					82.5	54.0	43.0	36.6	51.1

CONDENSED SCHEDULE OF EARTH QUANTITIES						
LOCATION	VOLUME (CU YD)					
	21101505	20200100	X5020200			
	TOPSOIL CUT	TOPSOIL FILL	EARTH EX	STRUCTURE EX (SPECIAL)	EARTH EX (15% SHRINKAGE)	EMBANKMENT
ROLLINS ROAD - PRE-STAGE	415.0	195.0	760.3		646.3	237.1
ROLLINS ROAD - FINAL	259.1	322.2	551.1		468.4	762.9
NORTH ALIGNMENT	1,927.3	1,141.6	23,031.2		19,576.5	43.8
SOUTH ALIGNMENT	219.8	115.8	210.3		178.8	45.7
EXISTING PATH	82.5	54.0	43.0		36.6	51.1
UNDERPASS				8,826.0	7,502.1	
PROJECT SUBTOTALS	2,903.7	1,828.6	24,595.9	8,826.0	28,408.6	1,140.6
BERM		1,075.1				27,268.0
PROJECT TOTALS	2,903.7	2,903.7	24,595.9	8,826.0	28,408.6	28,408.6

FILE NAME: N:\PROJ\2012\0807\01\Rollins\Design\Misc\Sheets\08020807.01\schedule01.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = jkelliman	DESIGNED -	REVISED -
PLLOT SCALE = 2.0000' / 1"	DRAWN -	REVISED -
PLLOT DATE = 4/8/2013	CHECKED -	REVISED -
	DATE = 4/8/2013	REVISED -

**MILLENNIUM TRAIL  
LAKE COUNTY FOREST PRESERVES**

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.
--------	---------------------	--------------

**SCHEDULE OF QUANTITIES  
ROLLINS ROAD UNDERPASS**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
181	12-F3000-01-BT	LAKE	118	15
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				

CONTRACT NO. 63807