

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HBP FUNDS			
				80% FED 20% LOCAL			
				ROADWAY	BRIDGE	TRAFFIC SIGNALS	LIGHTING
0004	0014	0021	0021				
URBAN	URBAN	URBAN	URBAN				
44000100	PAVEMENT REMOVAL	SQ YD	849	849			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	23	23			
44000300	CURB REMOVAL	FOOT	76	76			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	617	617			
44000600	SIDEWALK REMOVAL	SQ FT	3,687	3,687			
50102400	CONCRETE REMOVAL	CU YD	38.0		38.0		
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1			
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1		
50157300	PROTECTIVE SHIELD	SQ YD	401		401		
50200100	STRUCTURE EXCAVATION	CU YD	319		319		
50200300	COFFERDAM EXCAVATION	CU YD	106		106		
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1		
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1		
50300225	CONCRETE STRUCTURES	CU YD	119.3		119.3		

* SPECIALTY ITEM

PLOT SCALE: 1" = 100' FILE NAME = ...General\Di\xxxx-shr-soq-3.dgn USER NAME = eship PLOT DATE = 4/4/2013

DESIGNED -	REVISIED -
DRAWN -	REVISIED -
CHECKED -	REVISIED -
DATE -	REVISIED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00251-00-BR	COOK	118	6
CONTRACT NO. 63817				
ILLINOIS FED. AID PROJECT				