

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HBP FUNDS			
				80% FED 20% LOCAL			
				ROADWAY	BRIDGE	TRAFFIC SIGNALS	LIGHTING
0004	0014	0021	0021				
URBAN	URBAN	URBAN	URBAN				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	21	21			
550A1000	STORM SEWERS, CLASS A, TYPE 4 21"	FOOT	24	24			
55100200	STORM SEWER REMOVAL 6"	FOOT	25	25			
55100500	STORM SEWER REMOVAL 12"	FOOT	3	3			
55101100	STORM SEWER REMOVAL 21"	FOOT	21	21			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	139		139		
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1	1			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2			
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5	5			
60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2			
60500040	REMOVING MANHOLES	EACH	2	2			

* SPECIALTY ITEM

PLOT SCALE: 1" = 40' (SEE PLAN) DATE: 4/4/2013
 FILE NAME: \\...General\Di\...-sht-soq-5.dgn
 USER NAME: eship
 PLOT DATE: 4/4/2013

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00251-00-BR	COOK	118	8
CONTRACT NO. 63817			ILLINOIS FED. AID PROJECT	