

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HBP FUNDS			
				80% FED 20% LOCAL			
				ROADWAY	BRIDGE	TRAFFIC SIGNALS	LIGHTING
0004	0014	0021	0021				
URBAN	URBAN	URBAN	URBAN				
60500060	REMOVING INLETS	EACH	2	2			
60600605	CONCRETE CURB, TYPE B	FOOT	113.0	113.0			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	563.0	563.0			
* 66400105	CHAIN LINK FENCE, 4'	FOOT	120	120			
* 66400305	CHAIN LINK FENCE, 6'	FOOT	20	20			
67100100	MOBILIZATION	L SUM	1	1			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	100	100			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	800	800			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	120	120			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1,710	1,710			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	618	618			
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	EACH	1	1			
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	EACH	1	1			

* SPECIALTY ITEM

PLOT SCALE: 1"=100'
 R:\Projects\08-00251-00-02\Eng_Docs_Phase-II\General\08055_Civil_Plan_Table.tbl
 ...\General\DIxxxxx-sht-soq-5.dgn
 USER NAME = eship
 PLOT DATE = 4/4/2013

FILE NAME =	DESIGNED -	REVISED -
...	DRAWN -	REVISED -
USER NAME = eship	CHECKED -	REVISED -
PLOT DATE = 4/4/2013	DATE -	REVISED -



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00251-00-BR	COOK	118	9
CONTRACT NO. 63817				
ILLINOIS FED. AID PROJECT				