

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HBP FUNDS			
				80% FED 20% LOCAL			
				ROADWAY 0004 URBAN	BRIDGE 0014 URBAN	TRAFFIC SIGNALS 0021 URBAN	LIGHTING 0021 URBAN
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	614				614
* 81301290	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12" X 12" X 6"	EACH	8				8
* 81301400	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 18" X 18" X 6"	EACH	4				4
* 81400100	HANDHOLE	EACH	1			1	
* 81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	385				385
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	910				910
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	740				740
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	1,480				1,480
* 81702160	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 1/0	FOOT	1,350				1,350
* 82600105	NAVIGATION OBSTRUCTION LIGHTING CONTROLLER	EACH	1				1
* 83000200	LIGHT POLE, ALUMINUM, 30 FT. M.H., 6 FT. DAVIT ARM	EACH	4				4
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	36				36
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	6				6
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	4				4

\* SPECIALTY ITEM

PLOT SCALE: 1" = 40' FILE NAME = \\General1\Drawings\10055-Civil Pen Table.tbl  
USER NAME = eahsp  
PLOT DATE = 4/4/2013

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00251-00-BR	COOK	118	11
CONTRACT NO. 63817				
ILLINOIS FED. AID PROJECT				