

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HBP FUNDS			
				80% FED 20% LOCAL			
				ROADWAY	BRIDGE	TRAFFIC SIGNALS	LIGHTING
0004	0014	0021	0021				
URBAN	URBAN	URBAN	URBAN				
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	188			188	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	390			390	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	449			449	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	195			195	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	933			933	
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	169			169	
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	13.5			13.5	
* 87900200	DRILL EXISTING HANDHOLE	EACH	5			4	1
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4			4	
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	1			1	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	118			118	
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1	
* 89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	3			3	
* 89500400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH	1			1	

* SPECIALTY ITEM

PLOT SCALE: 1"=100'
 R:\Projects\08-00251-00-01\Drawings\08-00251-00-01-01-01.dgn
 USER NAME = oship
 PLOT DATE = 4/4/2013

FILE NAME =	DESIGNED -	REVISED -
...General\DI\xxxxx-shr-soq-9.dgn	DRAWN -	REVISED -
USER NAME = oship	CHECKED -	REVISED -
PLOT DATE = 4/4/2013	DATE -	REVISED -



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00251-00-BR	COOK	118	12
CONTRACT NO. 63817			ILLINOIS FED. AID PROJECT	