

EXISTING TREE REMOVAL AND PROTECTION SCHEDULE						
LOCATION	SIZE (INCHES)	TREE TRUNK PROTECTION (EACH)	TREE REMOVAL (UNITS)		TREE REMOVAL (ACRES)	REMARKS
			6 TO 15	OVER 15		
97+83, 24' LT	10	1				
98+03, 32' LT	25			25		
98+36, 27' LT	24	1				
98+37, 68' LT	5	1				
98+38, 35' RT	10	1				
98+54, 33' RT	10	1				
98+65, 62' LT	24	1				
98+70, 34 RT	10	1				
101+10, 30' RT	3	1				
101+60, 22' LT	12		12			
101+82, 35' RT	14	1				
102+07, 23' LT	10		10			
102+13, 72' RT	3	1				
(99+20) TO (99+52) LT					0.03	30' WIDE
(99+14) TO (99+47) RT					0.02	20' WIDE
(100+40) TO (100+94) RT					0.03	20' WIDE
(100+48) TO (101+04) LT					0.04	30' WIDE
TOTAL	-	10 EACH	22 UNITS	25 UNITS	0.25 AC (MIN.)	-

EXISTING DRAINAGE & UTILITIES STRUCTURE SCHEDULE								
STATION/OFFSET	STR. TYPE	REMOVAL	STR. ADJUSTMENTS				CITY ELECT. MH	REMARKS
			STORM			WATER		
			MH	CB	INLET	MH	VBOX	
98+07, 10' LT	INL TA (MODIFIED)	1						
98+08, 12' RT			1					
98+09, 17' RT				1				
98+13, 7' LT						1		
98+20, 18' RT						1		
98+37, 28' RT			1					
98+83, 58' LT							1	
98+91, 17' LT								1
98+96, 19' LT						1		
100+98, 7' RT	MH TA	1						
101+35, 5' RT			1					
101+43, 3' RT			1					
101+94, 8' RT						1		
102+03, 2' RT						1		
102+07, 16' RT							1	
102+13, 13' LT	MH TA	1						
102+15, 21' RT				1				
TOTAL		3	4	2	0	5	2	1

PROPOSED DRAINAGE STRUCTURE SCHEDULE												
STR NO.	STATION	OFFSET	STRUCTURE TYPE			FRAME & GRATE	RIM ELEV.	INVERT (N)	INVERT (S)	INVERT (E)	INVERT (W)	REMARKS
			MH	CB	INL							
1	102+13	15' LT		TA 4'		T23	600.36	596.52	596.30			USE EXISTING FRAME & GRATE
3	98+07	15' LT			TA (MODIFIED)	7036	598.97	596.30				E. JORDAN, M6 GRATE, T6 BACK, DOUBLE
4	101+19	9' RT	TA 5'			T1, CL	601.47	584.24	584.21	593.12		
5	101+13	30' RT	TA 4'			T1, CL	601.00	593.26			593.23	

PLOT SCALE: \$SCALE\$ SHORT \$SCALE\$

FILE NAME =	DESIGNED -	REVISED -
\$FILEL\$	DRAWN -	REVISED -
USER NAME = \$USER\$	CHECKED -	REVISED -
PLOT DATE = \$DATE\$	DATE -	REVISED -

COOPER CIVIL ENGINEERING, LTD.
 1322 ROSALIE STREET, EVANSTON, ILLINOIS 60201
 (847)864-5343
STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00251-00-BR	COOK	118	17
			CONTRACT NO. 63817	
ILLINOIS FED. AID PROJECT				